

STREET PAVING FOR WOODRIDGE

to serve

WOODS NORTH 3RD ADDITION


PHASE IV

WOODRIDGE: from the north line of Lot 34, Block D, north, east and north to the north line of Lot 9, Block C.

WOODRIDGE COURT (Lots 10-16, Block C) from the east line of Woodridge, southeasterly to and including the cul-de-sac.

CITY OF WICHITA, KANSAS



Gary Janzen, P.E. City Engineer
 Project Number
 472 - 85049
 O.C.A. Number
 766361



Vicinity Map

GENERAL NOTES:

1. Contractor will be required to provide notice to utility companies a minimum of forty-eight (48) hours prior to any excavation, as follows:
 Kansas One-Call 687-2470
 The Contractor must notify the following in case of an emergency:
 Cox Communications 262-4270
 Kansas Gas Service 1-888-482-4950
 Westar Energy 383-8650
 Aquila Energy 1-800-303-0357
 ATT 268-2245
 City of Wichita Water Dept. 268-4563
 City of Wichita Sewer Maint. 268-4024
 City of Wichita Storm Sewer Maint. 268-4090
 City of Wichita Traffic Maint. 268-4034
 Conoco Phillips Pipeline Co. 1-877-267-2290
 Southern Star Pipeline Co. 529-6600
 Kinder-Morgan Pipeline Co. 1-888-844-5658
2. Utility service lines, poles, valve boxes, meters, and etcetera are to be adjusted as necessary by others prior to construction unless the plans specifically call for their adjustment by the Contractor or unless the plans specifically identify a utility to be adjusted by its owner during construction. Existing utilities and their location, as shown on the plans, represent the best information obtainable for design. The Contractor will be required to work around existing utilities within the right-of-way which do not conflict with proposed construction.
3. Rubble from the removal of miscellaneous structures and excess excavation which is to be wasted shall be disposed of on sites to be provided by the Contractor. These sites shall be approved by the Engineer as to suitability, appearance and site location. Locations, in the opinion of the Engineer, that will leave an unsightly appearance will not be approved. All disposal sites must be approved by the Kansas Department of Health and Environment. Material either stockpiled or disposed of in a flood plain would require a Kansas State Board of Agriculture permit. Any material dumped in waters of the United States or wetlands is subject to U.S. Corps. of Engineers permitting regulations. Any material buried or stockpiled beyond approved construction limits would require additional archaeological investigations unless buried in a previously approved borrow location.
4. Trees and shrubs in public right-of-way which are in direct conflict with proposed new construction shall be removed by the Contractor ONLY with the Developer or Baughman Company approval. Trees and shrubs which are not in direct conflict with proposed new construction shall be saved and protected from damage.
5. The Contractor shall give all property owners and/or tenants of developed property abutting the construction of this project a minimum of ten (10) days notice prior to start of construction.
6. The Contractor shall be responsible for preserving property irons. The Contractor will be required to re-establish any property irons which are damaged or destroyed by his construction operations. Such irons shall be re-established by a licensed Land Surveyor in accordance with state laws.
7. All existing and proposed erosion control measures including silt fencing, erosion control mat, straw bales, inlet barriers, and const. entrance shall be maintained throughout construction by the Contractor and until project is accepted by the City of Wichita. The on-site Engineer shall complete weekly reports on the status of erosion control measures. The Contractor shall be required to comply with maintenance and/or replacement of erosion control measures as determined by the on-site Engineer until project is accepted by City of Wichita.
8. A saw cut of at least one-half the depth of existing surface courses or one-fourth the depth of the existing total pavement thickness shall be provided at locations where proposed construction abuts the existing surface course or pavement for which partial removal of that surface or pavement is required. Sawed joint to facilitate removal within three (3) feet of existing joints will not be permitted and for such instances the limits of removal shall extend to the existing joint. Such saw cuts will not be paid for directly and this cost shall be considered as subsidiary to the removal of the surface or pavement.
9. Disturbed areas within 29th St. N. shall be seeded with fescue at a rate of 8 lbs/1000 sq. ft. and annual rye at 2 lbs/1000 sq. ft. with fertilizer and mulch per City specs (no mulch where EC mat will be installed).
 All other disturbed areas shall be temporarily seeded with annual rye at 5 lbs/5000 sq. ft.
 Contractor shall prepare ground per City of Wichita Specifications. All costs associated with seeding shall be included in bid item "Project Seeding"
10. The Contractor shall adjust valve boxes as necessary to match proposed grade. Cost to be included in bid item, "Site Restoration."
11. The Contractor shall drain any standing water in sump areas of the proposed pavement. Contractor shall overexcavate and recompact these areas as required to maintain compaction of 95% Standard Proctor Density. Cost to be incidental to pavement.
12. Limits of earthwork shall match existing ground elevations at the right-of-way line unless otherwise noted on the plans with a new finished grade elevation. When a new finished grade elevation is shown, the earthwork shall extend one foot beyond the right-of-way line and then slope up or down using permissible slopes to match the existing ground surface.
13. The Developer for this project is Ritchie Development Kevin Mullen, President (316) 684-7300.
14. Excess excavation shall be stockpiled or spread on-site at a location determined by the Developer or Design Engineer.



BENCHMARKS

BM #1: "□" cut in top of curb near intersection of 27th Street North & Woodridge, south of SE corner of Lot 24, Block C, Woods North 3rd Addition.
 Elev. = 1392.97 NGVD29

BM #2: "□" cut in top of curb near intersection of Woodridge Court & Woodridge, south of SE corner of Lot 6, Block A, Woods North 3rd Addition.
 Elev. = 1390.10 NGVD29

SHEET INDEX

| | |
|------------------------------|-------|
| Title Sheet | 1 |
| 35' Pavement Details | 2 |
| Curb & Gutter Details | 4 |
| Sign Details | 4 |
| Valley Gutter Details | 5 |
| Entrance Details | 6 |
| Curb Inlet Underdrain Detail | 7 |
| Woodridge Court | 8-9 |
| Woodridge | 10-12 |
| Erosion Control Plan | 13 |
| Erosion Control BMP Details | 14-18 |
| Earthwork Cross Sections | 19-22 |
| Coordinate Sheet | 23 |
| Copy of Plat | 24 |

| Project Earthwork Totals (Unadjusted) | | | |
|---------------------------------------|--------------------------|-------------------------------|------------------------------|
| | Excavation, Unclassified | Fill, Compacted (95% Density) | Fill, Loose (not a bid item) |
| Easement Grading | 10 | | 538 |
| Street (R/W) | 884 | 46 | 491 |
| Project Total | 894 | 46 | 1,029 |

NOTE: There is 400-500 CY of excess excavation expected from the sewer and water job that will remain on-site and will be available to use for grading the easements.

Total Project Length
 1,366 L.F. = 0.26 Miles

Proposed Streets:

Benefit District:



Baughman Company, P.A. 315 Ellis St. Wichita, KS 67211 P 316-262-7271 F 316-262-0149
 ENGINEERING | SURVEYING | PLANNING | LANDSCAPE ARCHITECTURE