



**EROSION CONTROL PLAN LEGEND**

- CONSTRUCTION ENTRANCE
- CURB INLET PROTECTION
- BACK OF CURB PROTECTION

Existing Ground ——— 1364 ———

**NOTES:**  
Contractor shall make sure all erosion control is in place before project is accepted. This plan represents the minimum standard. Any additional erosion control measures shall be installed by the Contractor as needed.

All areas disturbed during construction shall be seeded at 300 lbs./acre with Rye Grass immediately following construction in that area. Contractor shall prepare ground per City Specifications.

EROSION CONTROL MEASURE	INSTALL	MAINTAIN
BACK OF CURB PROTECTION (LF)	2,137	0
CONSTRUCTION ENTRANCE (EA)	0	1
CURB INLET BARRIER (EA)	2	0
DROP INLET PROTECTION (EA)	0	0
EROSION CONTROL MAT (SY)	0	0

\* ANY EXISTING BMPs INCLUDING CONSTRUCTION ENTRANCE, SEDIMENT BARRIERS, SILT FENCE, CUT-OFF TRENCH, AND EROSION CONTROL MAT SHALL BE MAINTAINED AND REPAIRED IF NECESSARY.



Baughman Company, P.A. 315 Ellis St. Wichita, KS 67211 P 316-262-7271 F 316-262-0149  
ENGINEERING | SURVEYING | PLANNING | LANDSCAPE ARCHITECTURE

SHERIDAN AVE.  
**EROSION CONTROL**

PROJECT NUMBER 472-	DESIGN NBW	DRAWN JAK
REVISIONS:	APPROVED	DATE 1/19/16
		SCALE Noted
		SHEET <b>11 OF 23</b>

E:\Projects\Sheridan Avenue 1507-E277\Engineering\STREET PLANS.dwg