



**EROSION CONTROL PLAN  
LEGEND**

- CONSTRUCTION ENTRANCE

Existing Ground ——— 1364 ———

**NOTES:**  
Contractor shall make sure all erosion control is in place before project is accepted. This plan represents the minimum standard. Any additional erosion control measures shall be installed by the Contractor as needed.

All areas disturbed during construction shall be seeded, mulched, and fertilized as per Cover Sheet General Notes.

EROSION CONTROL MEASURE	INSTALL	MAINTAIN
BACK OF CURB PROTECTION (LF)	0	0
CONSTRUCTION ENTRANCE (EA)	0	1
CURB INLET BARRIER (EA)	0	0
DROP INLET PROTECTION (EA)	0	0
EROSION CONTROL MAT (SY)	0	0

\* ANY EXISTING BMPs INCLUDING CONSTRUCTION ENTRANCE, SEDIMENT BARRIERS, SILT FENCE, CUT-OFF TRENCH, AND EROSION CONTROL MAT SHALL BE MAINTAINED AND REPAIRED IF NECESSARY.



<b>Baughman</b> <small>ENGINEERING   SURVEYING   PLANNING   LANDSCAPE ARCHITECTURE</small>	Southwest Industrial Addition <b>EROSION CONTROL</b> Water Distribution System
	<small>Baughman Company, P.A. 315 Ellis St. Wichita, KS 67211 P 316-262-7271 F 316-262-0149</small>
PROJECT NUMBER 448-90691	DESIGN NBW DRAWN JAK
REVISIONS:	APPROVED DATE 3/15/16
	SCALE Noted SHEET
<b>6 OF 13</b>	