| FHWA REGION NO. | STATE | PROJECT NO. | YEAR | SHEET NO. | TOTAL SHEETS |
|---|---|---|---|---|---|
| 7 | KANSAS | 87 N-019F | 2000 | 52 | 82 |

STA. 3+000.00 TO STA. 3+150.0

# SUMMARY OF PAVEMENT MARKINGS

| LOCATION | 100 mm Solid WHITE Edge Line | 150 mm Broken WHITE Lane Line | 150 mm Dotted WHITE Extension Line | 150 mm Solid WHITE LANE LINE | 200 mm Solid WHITE Gore Line | 300 mm Solid WHITE Diagonal Line | 300 mm Solid WHITE Chevron Line | 300 mm Solid WHITE Type I Crosswalk Line | 600 mm Solid WHITE Type II Crosswalk Line | 600 mm Solid WHITE Stop Line | 100 mm Solid YELLOW Edge Line | 100 mm Solid YELLOW Double Line | 100 mm Solid YELLOW Line | 100 mm Broken YELLOW Line | 300 mm Solid YELLOW Diagonal Line |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| STA. 3+000.00 TO STA. 3+150.00 | -- | 37.8 | -- | 85.0 | -- | -- | -- | 92.7 | -- | 31.1 | -- | 119.2 | -- | -- | 25.4 |
| STA. 3+150.00 TO STA. 3+311.00 | -- | 67.5 | -- | 457.2 | -- | -- | -- | -- | -- | 23.4 | -- | -- | 259.6 | -- | -- |
| STA. 3+311.00 TO STA. 3+444.00 | -- | 31.2 | -- | 140.6 | -- | -- | -- | -- | -- | 24.4 | -- | 3.4 | 137.5 | -- | -- |
| STA. 3+444.00 TO STA. 3+600.00 | -- | 51.3 | -- | 256.0 | -- | -- | -- | -- | -- | 16.9 | -- | 114.2 | 85.2 | -- | 12.3 |
| STA. 49+904.18 TO STA. 50+076.89 | -- | -- | -- | 146.8 | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- |
| TOTALS | -- | 187.75 | -- | 1085.6 | -- | -- | -- | 92.7 | -- | 107.9 | -- | 236.8 | 482.3 | -- | 37.7 |

# SUMMARY OF WORD & SYMBOL MARKINGS

| LOCATION | | | | | | | | STOP | ONLY | X-ING | SCHOOL |
|---|---|---|---|---|---|---|---|---|---|---|---|
| STA. 3+000.00 TO STA. 3+150.00 | | | | 2 | | | | | | | |
| STA. 3+150.00 TO STA. 3+311.00 | | | | 2 | 2 | | | | | | |
| STA. 3+311.00 TO STA. 3+444.00 | | | | | | | | | | | |
| STA. 3+444.00 TO STA. 3+550.00 | | | | 3 | 2 | | | | | | |
| STA. 49+904.18 TO STA. 49+76.89 | 2 | | | 2 | 2 | | | | | | |
| TOTALS | 2 | | | 9 | 6 | | | | | | |

NOTE: For specific pavement marking details and dimensions see plan sheets

NOTE: ALL TOTALS REFLECT ACTUAL QUANTITY OF PAVEMENT MARKING MATERIALS REQUIRED.

# *RECAPITULATION OF QUANTITIES

| ITEMS | TOTAL | UNITS |
|---|---|---|
| PAVEMENT MARKING (THERMOPLASTIC)(WHITE)(100 mm) | | m |
| PAVEMENT MARKING (THERMOPLASTIC)(WHITE)(150 mm) | 879.3 | m |
| PAVEMENT MARKING (THERMOPLASTIC)(WHITE)(200 mm) | | m |
| PAVEMENT MARKING (THERMOPLASTIC)(WHITE)(300 mm) | 92.7 | m |
| PAVEMENT MARKING (THERMOPLASTIC)(WHITE)(600 mm) | 54.5 | m |
| PAVEMENT MARKING (THERMOPLASTIC)(YELLOW)(100 mm) | 662.3 | m |
| PAVEMENT MARKING (THERMOPLASTIC)(YELLOW)(300 mm) | 34.6 | m |
| PAVEMENT MARKING SYMBOL (THERMOPLASTIC)(WHITE)(RIGHT ARROWS) | | EACH |
| PAVEMENT MARKING SYMBOL (THERMOPLASTIC)(WHITE)(LEFT ARROWS) | | EACH |
| PAVEMENT MARKING SYMBOL (THERMOPLASTIC)(WHITE)( ) | | EACH |
| PAVEMENT MARKING SYMBOL (THERMOPLASTIC)(WHITE)( ) | | EACH |
| | | |
| | | m |
| PAVEMENT MARKING (COLD PLASTIC)(WHITE)(100mm) | | m |
| PAVEMENT MARKING (COLD PLASTIC)(WHITE)(150mm) | | m |
| PAVEMENT MARKING (COLD PLASTIC)(WHITE)(600mm) | | m |
| PAVEMENT MARKING (COLD PLASTIC)(WHITE)(300mm) | | m |
| PAVEMENT MARKING (COLD PLASTIC)(YELLOW)(100mm) | | m |
| PAVEMENT MARKING (COLD PLASTIC)(YELLOW)(300mm) | | m |
| | | |
| PAVEMENT MARKING (PREFORMED THERMOPLASTIC)(WHITE)(300mm) | | m |
| PAVEMENT MARKING (PREFORMED THERMOPLASTIC)(WHITE)(600mm) | | m |
| | | |
| PAVEMENT MARKING (EPOXY)(WHITE)(100mm) | | m |
| PAVEMENT MARKING (EPOXY)(WHITE)(150mm) | 394.1 | m |
| PAVEMENT MARKING (EPOXY)(WHITE)(300mm) | | m |
| PAVEMENT MARKING (EPOXY)(WHITE)(600mm) | 53.4 | m |
| PAVEMENT MARKING (EPOXY)(YELLOW)(100mm) | 293.6 | m |
| PAVEMENT MARKING (EPOXY)(YELLOW)(300mm) | 3.1 | m |
| PAVEMENT MARKING SYMBOL (PREFORMED THERMOPLASTIC)(WHITE)(LEFT ARROWS) | 4 | EACH |
| PAVEMENT MARKING SYMBOL (PREFORMED THERMOPLASTIC)(WHITE)(RIGHT ARROWS) | 5 | EACH |
| PAVEMENT MARKING SYMBOL (EPOXY)(WHITE)(RIGHT/THROUGH ARROWS) | 2 | EACH |
| PAVEMENT MARKING SYMBOL (EPOXY)(WHITE)(LEFT ARROWS) | 2 | EACH |
| PAVEMENT MARKING SYMBOL (EPOXY)(WHITE)(RIGHT ARROWS) | 4 | EACH |
| | | |
| PAVEMENT MARKING REMOVAL | 1543 | m |

*-QUANTITIES FOR INFORMATION ONLY- PAVEMENT MARKINGS PAID FOR AS LUMP SUM

NOTE:

WORDS & SYMBOLS SHALL CONFORM TO THE LATEST EDITION OF "STANDARD ALPHABETS FOR HIGHWAY SIGNS AND PAVEMENT MARKINGS" PRINTED BY THE U.S. DEPARTMENT OF TRANSPORTATION, FEDERAL HIGHWAY ADMINISTRATION.

PRIOR TO COMMENCEMENT OF PAVEMENT MARKING WORK THE ENGINEER WILL ESTABLISH THE LIMITS FOR "NO PASSING" ZONES. THESE LIMITS SHALL BE USED FOR THE LOCATION OF "NO PASSING" LINES AND FOR THE COMPUTATION OF ACTUAL MARKING QUANTITIES FOR THIS LINE TYPE.

| NO. | DATE | REVISION | BY | APP'D |
|---|---|---|---|---|
| 3 | | | | |
| 2 | | | | |
| 1 | 03/06/98 | Add "NO PASSING" zone note | JFF | LCV |

KANSAS DEPARTMENT OF TRANSPORTATION
SUMMARY AND RECAPITULATION
OF PAVEMENT MARKING
QUANTITIES
(THERMOPLASTICS AND EPOXY)

TE311SI 03/15/96

| | | | |
|---|---|---|---|
| FHWA APPROVAL | 05/18/98 | APP'D JAMES E. TOBASEN | |
| DESIGNED JFF | DETAILED GSB | QUANTITIES | TRACED |
| DESIGN CK. JET | DETAIL CK. JFF | QUAN. CK. | TRACE CK. |

Plotted By : @@USERNAME@@Pmacher Bldg. 4th Floor
Plot File : @@@@@@@@@@@@DGNSPEC@@@@@@@@@@@@
Plot Date : @@@@@SYTIME@@@@@@