STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	87 N-0597-01	2016	27	191

MKEC
Wichita, KS · 316-684-9600

SUMMARY OF QUANTITIES - STORM SEWER PIPE AND STRUCTURES*

LINE NO.	PIPE												HEADWALLS	INLETS													MANHOLES						MISCELLANEOUS ITEMS						
	Pipe, SWS 15" RCP (lf)	Pipe, SWS 18" RCP (lf)	Pipe, SWS 24" RCP (lf)	Pipe, SWS 30" RCP (lf)	Pipe, SWS 36" RCP (lf)	Pipe, HERCP (14"x23") (lf)	Pipe, HERCP (19"x30") (lf)	Pipe, HERCP (29"x45") (lf)	Pipe, HERCP (38"x60") (lf)	Pipe, SWS 48" RCP (lf)	Pipe, SWS 54" RCP (lf)	Fill, Sand (Flushed & Vibrated) (lf)	Headwall RC 54" (ea)	Inlet, Curb (Type 1) (L=5', W=4') (ea)	Inlet, Curb (Type 1) (L=10', W=4') (ea)	Inlet, Curb (Type 1) (l=10', W=5') (ea)	Inlet, Curb (Type 1) (L=10', W=7') (ea)	Inlet, Curb (Type 1) (L=15', W=4') (ea)	Inlet, Curb (Type 1) (L=15', W=7') (ea)	Inlet, Curb (Type 1) (L=15', W=9') (ea)	Inlet, Curb (Type 1A) (L=10', W=4') (ea)	Inlet, Curb (Type 2) (L=6'-4", W=3'-4") (ea)	Inlet, Curb (Type 2), Special (L=6'-4", W=7'-0") (ea)	Inlet, Drop (Single) (ea)	Inlet, Drop (Double-Double) (ea)	Inlet, Grated Driveway, Double (ea)	MH, Std. SWS (5') (ea)	MH, Std. SWS (6') (ea)	MH Stack (4') (ea)	MH, Reinf. Conc. (L=4', W=4') (ea)	MH, Reinf. Conc. (L=5', W=5') (ea)	MH, Reinf. Conc. (L=8'6", W=8'6") (ea)	Temp. Pipe Plug (38"x60") (ea)	Temp. Pipe Plug, 48" (ea)	Sidewalk Flume (ea)	Concrete Flume (lf)	Inlet Top (ea)	Inlet Hookup (ea)	Snout≠ (ea)
1		68										42												1							1									
2A		40										40										1									1							1	
2B		23										23			1																							1	
3	33	133										166			1															1	1							1	1
4															1																							1	
5						66	179					152			1										1													1	
6		243	99									342			3																							3	
7		64										64			1																							1	
8		239	66	184	533							980			3	1							1				1	2										5	1
9		218										218			1											1													1	
THERE IS NO LINE 10																																							
11														1																								1	
12		5										5										1							1									1	
13		30										30										1							1									1	
14						79	145	76	153			379						1	1	1												1	1					3	
15							26					26										1																1	
16								86				86					1																					1	
17										13	43	13	1				1																	1				1	1
18															1																							1	
THERE IS NO LINE 19																																							
20		34	190									89									2	2																4	
TOTALS	33	1097	355	184	533	145	350	162	153	13	43	2655	1	1	13	1	2	1	1	1	2	6	1	1	1	1	1	2	2	1	3	1	1	1	1**	17**	1**	30***	3

* All pipe conduit is measured per lineal feet and headwalls and structures are measured per each
** These items are not associated with a specific stormwater sewer line. They are noted on the paving plan sheets.
*** This total includes a hook-up associated with the new inlet top which is not associated with a specific stormwater sewer line. It is noted on the paving plan sheets.
≠ Bid as "Manhole Water Quality BMP".

STREET IMPROVEMENTS FOR:
PAWNEE AVENUE
FROM HYDRAULIC TO POPLAR
WICHITA, KANSAS

©2013
MKEC Engineering
All Rights Reserved
www.mkec.com
These drawings and their contents, including, but not limited to, all concepts, designs, & ideas are the exclusive property of MKEC Engineering (MKEC), and may not be used or reproduced in any way without the express consent of MKEC.

STORM SEWER SUMMARY

PROJECT NO.	87 N-0597-01
DATE	DATE
SCALE	NO SCALE

DESIGNED	DRAWN	CHECKED
JRA	JSB	JRA

NO.	REVISION	DATE

SHEET NO.
27 OF 191

PLOTTED: Monday, May 09, 2016 @ 02:32PM
J:\CIVIL\05745\DWGS\VS\05745SVS-SUMMARY.DWG