






EXPANSION JOINT


NOTE: Extra Thickness to be Subsidiary to Price of Square Yards Pavement




KEYWAY DETAIL




CONTRACTION JOINT DETAIL (C.J.)




LONGITUDINAL JOINT DETAIL (L.J.)




OPTIONAL LONGITUDINAL JOINT DETAIL (L.J.)



OPTIONAL CONTRACTION JOINT




WING REINFORCING DETAIL




SECTION A-A
SCALE: NONE

REINFORCED VALLEY GUTTER DETAIL




WHEELCHAIR RAMP PLAN VIEW


WHEELCHAIR RAMP DETAIL




GROOVE DETAIL



DEPRESSED CURB DETAIL




SECTION A-A




SAW JOINT DETAIL

JOINT TO BE SAWS IN TWO SEPARATE OPERATIONS



8' REINFORCED CONCRETE ENTRANCE RAMP



8' REINFORCED CONCRETE DRIVE

- GENERAL NOTES
1. DRIVEWAY CONSTRUCTION DETAILED ON THIS SHEET IS FOR USE WITH FULL HEIGHT STREET CURBS AND IN AREAS WITHOUT FULL WALK CONSTRUCTION IN THE PARKING. SEE OTHER DETAIL SHEETS FOR DRIVEWAY CONSTRUCTION WITH ROLL CURB AND/OR FULL WALK.
 2. ONE LONGITUDINAL JOINT SHALL BE CONSTRUCTED ALONG THE CENTERLINE OF DRIVES HAVING A "W" DIMENSION OF 24' OR LESS. TWO LONGITUDINAL JOINTS SHALL BE CONSTRUCTED WITH EQUAL SPACINGS NOT TO EXCEED 10' FOR DRIVES WITH A "W" DIMENSION GREATER THAN 24'.
 3. DRIVEWAY WIDTH DENOTED AS "W" ON THE DETAIL DRAWINGS SHALL BE A MINIMUM OF 10' AND A MAXIMUM OF 30'. THE MAXIMUM OPENING FOR RADIUS TYPE DRIVES WITH CURBS THROUGH THE RADIUS SHALL NOT EXCEED 52' AT THE STREET CURB LINE.
 4. CONTRACTION JOINT SPACING IN THE DRIVEWAY WALK SECTION SHALL BE A MINIMUM OF 3' AND A MAXIMUM OF 6' AND ARE TO BE EQUALLY SPACED WITHIN THIS RANGE. WALK SECTION SHALL BE CONSTRUCTED TO THE SAME THICKNESS AS THE DRIVEWAY.
 5. DOWEL BARS SHALL BE OMITTED FROM THE KEYED CONSTRUCTION JOINT ALONG THE BACK OF THE STREET CURB LINE WHEN DRIVEWAYS ARE CONSTRUCTED IN CONJUNCTION WITH NEW CONCRETE PAVEMENT CONSTRUCTION.
 6. ONE HALF INCH EXPANSION JOINTS SHALL BE INSTALLED WHEREVER DRIVE CONSTRUCTION ABUTS SIDEWALK. ONE HALF INCH EXPANSION JOINTS SHALL ALSO BE INSTALLED ALONG THE PROPERTY LINE AND/OR BACK OF WALK LINE WHEN DRIVE CONSTRUCTION ALONG THIS LINE ABUTS CONCRETE PARKING LOTS OR CONCRETE DRIVE EXTENSION.

K:\MEPS\MESSIAH-BAPTIST\CIVIL\02212\PAVE\VALEYGUT.DWG



CITY OF WICHITA
PROJECT NAME

PAVEMENT DETAILS
SHEET TITLE

DAC DESIGN BY:	DAC DRAWN BY:	JTC CHECKED BY:
MAY 2003 DATE	02212 JOB NO.	3 / 20 SHEET/OF