



GRAY'S 5TH ADDITION WICHITA, SEDGWICK COUNTY, KANSAS



This plat of "GRAY'S 5TH ADDITION", Wichita, Sedgwick County, Kansas has been submitted to and approved by the Wichita-Sedgwick County Metropolitan Area Planning Commission, Wichita, Kansas.
 Dated this 6th day of December, 2001.
 Wichita-Sedgwick County Metropolitan Area Planning Commission

J.D. Michaelis, Chair
Marvin S. Krout, Secretary

This plat approved and all dedications shown herein accepted by the City Council of the City of Wichita, Kansas, this 6th day of August, 2002.

At the Direction of the City Council
Chris Cherkas, City Manager
Pat Burnett, City Clerk

Reviewed in accordance with K.S.A. 58-2005 on this 20th day of March, 2002.

Tricia L. Robello, L.S. #1246
 Deputy County Surveyor
 Sedgwick County, Kansas

Entered on transfer record this 25th day of September, 2002.


Don Brace, County Clerk

This is to certify that this plat has been filed for record in the office of the Register of Deeds, this 25th day of September, 2002 at 11:22 o'clock P.M.; and is duly recorded.

Bill Meek, Register of Deeds
Linda Kizzire, Deputy

LOT	BLOCK	CITY DATUM	NGVD
4, 5	D	105.8	1231.0
12-21	D	105.8	1231.0

BENCHMARK:
 Hoover & 47th Street South - City of Wichita Benchmark Disc, NE corner of intersection, 21.00' N. of & 1720' St. S, 71.50' E. of & Hoover, 71.60' ENE of Sec. Cor, 5.90' W. of Power Pole Elev. = 108.08 City Datum (1220.48 NGVD)
 Hoover & MacArthur - City of Wichita Benchmark Disc, NE corner of intersection, 41.00' N. of & MacArthur, 63.00' E. of & Hoover, 20.00' E. of City Pole, 79.80' NE. of Sec. Cor, Elev. = 114.22 City Datum (1308.62 NGVD)



- = #1 REBAR W/ "BAUGHMAN" CAP (SET)
- = #1 REBAR (FOUND)
- △ = #5 REBAR (FOUND)
- = STONE (FOUND) - 3/4" IRON ON N. SIDE
- ⊠ = CONCRETE FLOORWAY MONUMENT (FOUND)
- = #4 REBAR W/ "WOODRING" CAP (FOUND)
- (M) = MEASURED
- (D) = DESCRIBED
- (P) = PLATTED
- (C) = CALCULATED
- (PM) = PROPORTION MEASUREMENT
- (C-D) = CALCULATED PER DESCRIBED INFO.
- (C-P) = CALCULATED PER PLATTED INFO.

NOTE:
 A master grading plan for drainage has been developed for this subdivision and is on file with the City of Wichita, Kansas. All drainage easements, rights-of-way, or reserves shall remain established grades or as modified with the approval of the City Engineer of the City of Wichita, Kansas. No obstructions which impede the flow of this drainage system be allowed.

Note:
 Blanket Pipeline Right of Way granted to Citrus Service Oil Company (Note Book 825 Page 442) and assigned to Citrus Service Oil and Gas Corporation. (Plan 853, Page 1232) and assigned to Citrus Service M&L, Inc. (Plan 868, Page 228) and assigned to Fidelity M&L, Inc. (Plan 1194, Page 523) and assigned to MOORE Pipelines, Inc. (Plan 1354, Page 1966)

State of Kansas) SS We, Baughman Company, P.A., Surveyors in and said county and state do hereby certify that we have surveyed and platted "GRAY'S 5TH ADDITION", Wichita, Sedgwick County, Kansas and that the accompanying plat is a true and correct exhibit of the property surveyed, described as follows: That part of the SW1/4 of Sec. 14, Twp. 28-S, R-1-W of the 6th P.M., Sedgwick County, Kansas described as beginning at the NW corner of said SW1/4; thence N89°34'13"E along the north line of said SW1/4, 1780.20 feet to the intersection with the westerly right-of-way line of the Wichita-Valley Center Flood Control (Condemnation Case A-30410); thence southeasterly along said westerly right-of-way line to a point 1075.69 feet south of the NW corner of said SW1/4 as measured along the west line of said SW1/4; thence N89°58'21"W perpendicular to the west line of said SW1/4, 1510.53 feet, more or less, to a point 663.00 feet normally distant east of the west line of said SW1/4; thence N00°01'39"E parallel with the west line of said SW1/4, 5.50 feet; thence N89°58'21"W perpendicular to the west line of said SW1/4, 120.00 feet; thence S00°01'39"W parallel with the west line of said SW1/4, 5.50 feet; thence N89°58'21"W perpendicular to the west line of said SW1/4, 549.00 feet to a point on the west line of said SW1/4, said point being 1075.69 feet south of the NW corner of said SW1/4; thence N00°01'39"E along the west line of said SW1/4, 1075.69 feet to the point of beginning, EXCEPT that part platted as Hope Community Baptist Church Addition, Sedgwick County, Kansas, all being subject to road rights-of-way of record.

Existing public easements and dedications being vacated by virtue of K.S.A. 12-512(b).
 Baughman Company, P.A.

Michael A. Conroy, Surveyor
 Michael & Conroy

Know all men by these presents that we, the undersigned, have caused the land in the surveyors certificate to be platted into Lots, Blocks, Streets, and a Reserve, to be known as "GRAY'S 5TH ADDITION", Wichita, Sedgwick County, Kansas. The utility easements are hereby granted as indicated for the construction and maintenance of all public utilities. The drainage and utility easements are hereby granted as indicated for drainage purposes and for the construction and maintenance of all public utilities. The drainage easements are hereby granted as indicated for drainage purposes. The wall easements are hereby granted as indicated for the construction and maintenance of a private screening wall and utility main lines and service lines shall be allowed to cross these easements. The streets are hereby dedicated to and for the use of the public. Reserve "A" is hereby reserved for drainage purposes, landscaping, berms, open space, sidewalks, utilities as confined to easement, pipelines as confined to easement, public park and park related uses. Reserve "A" shall be deeded to the City of Wichita, Kansas to be used as a public park. All abutters rights of access to or from Hoover Road over and across the west line of Lot 1, Block A, and the west line of Lots 1, 11, and 12, Block B, are hereby granted to the City of Wichita, Kansas. The Minimum Building Pad Elevations for the lowest opening to the structures shall be as indicated on the face of the plat.

Alice W. Wall Revocable Trust dated October 13, 1989
Percival J. Kirk, Trustee

State of Arizona) SS The foregoing instrument acknowledged before me, this 17th day of March, 2002, by Percival J. Kirk, Trustee of the Alice W. Wall Revocable Trust dated October 13, 1989, on behalf of the trust.

Melanie Marks, Notary Public
 My App't. Exp. 3-28-04

BAUGHMAN COMPANY P.A.
 ENGINEERING, SURVEYING, & PLANNING
 318-262-7821 • 318 ELLIS • WICHITA, KANSAS 67211
 P:\EAT\GRAY 5TH ADD\DWG\GRAY5THDRG-002

20.00
 CC