

LAKEVIEW DRIVE

STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
0+00	0.00	0.00				
0+16.59	58.41	0.00	17.95	0.00	17.95	0.00
0+50	82.16	1.16	86.97	0.72	104.92	0.72
1+00	91.83	0.00	161.10	1.07	266.01	1.79
1+50	105.95	0.00	183.13	0.00	449.14	1.79
2+00	97.86	0.76	188.71	0.70	637.85	2.49
2+50	65.70	0.16	151.44	0.85	789.29	3.34
3+00	45.92	1.29	103.36	1.34	892.64	4.68
3+50	49.47	0.46	88.33	1.62	980.97	6.30
4+00	38.97	4.78	81.89	4.85	1062.87	11.16
4+50	32.84	9.41	66.50	13.14	1129.36	24.29
5+00	40.17	3.46	67.61	11.92	1196.97	36.21
5+50	72.37	0.00	104.21	3.21	1301.18	39.42
6+00	104.08	0.00	163.39	0.00	1464.57	39.42
6+50	101.66	0.00	190.51	0.00	1655.08	39.42
7+00	81.02	0.00	169.15	0.00	1824.23	39.42
7+50	64.59	0.00	134.83	0.00	1959.06	39.42
8+00	59.88	0.19	115.25	0.18	2074.31	39.59
8+50	41.57	7.04	93.93	6.70	2168.24	46.29
9+00	18.00	24.65	55.15	29.34	2223.39	75.63
9+15.07	13.75	28.65	8.86	14.87	2232.26	90.51
			0.00	0.00	2232.26	90.51

CACTUS

STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
2+81.93	64.34	0.00				
3+00	62.95	0.21	42.03	0.08	42.03	0.08
3+50	28.42	11.18	83.95	11.54	125.98	11.62
3+62.01	22.67	16.87	11.32	6.55	137.30	18.16
3+78.90	21.60	8.33	14.00	7.64	151.30	25.80
3+91.57	9.51	16.31	7.36	5.44	158.66	31.24
4+00	11.00	11.22	3.21	4.04	161.87	35.28
4+04.23	7.50	33.06	1.45	3.34	163.32	38.62
4+21.12	6.56	33.76	4.36	21.49	167.68	60.11
4+50	3.32	37.11	5.20	38.70	172.88	98.82
5+00	17.35	17.43	19.06	48.93	191.94	147.75
5+50	4.29	42.95	20.04	55.90	211.98	203.65
6+00	20.03	10.73	22.52	49.71	234.50	253.36
6+00.06	20.04	10.73	0.04	0.02	234.55	253.38
6+19.56	38.87	0.01	21.28	3.88	255.82	257.26
6+34.06	47.45	0.00	23.18	0.00	279.00	257.26
6+48.56	54.40	0.00	27.35	0.00	306.35	257.26
6+50	33.46	3.68	2.34	0.10	308.69	257.36
6+68.06	40.71	1.43	24.80	1.71	333.50	259.07
7+00	34.16	0.75	44.28	1.29	377.78	260.36
7+50	41.60	0.00	70.15	0.69	447.93	261.05
8+00	57.44	3.04	91.71	2.81	539.64	263.86
8+19.09	38.94	15.95	34.07	6.71	573.71	270.57
			0.00	0.00	573.71	270.57

CACTUS COURT

STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
0+31.72	0.00	91.50				
0+50	0.00	107.52	0.00	67.37	0.00	67.37
1+00	0.00	247.47	0.00	328.69	0.00	396.06
1+09.81	0.00	273.80	0.00	94.70	0.00	490.76
1+25.53	0.00	378.75	0.00	189.96	0.00	680.72
1+53.04	0.00	568.22	0.00	482.43	0.00	1163.15
1+89.54	0.00	494.61	0.00	718.39	0.00	1881.54
2+03.04	0.41	12.51	0.10	126.78	0.10	2008.32
			0.00	0.00	0.10	2008.32


TOTALS

STATION	VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL
LAKEVIEW	2232.26	90.51	2232.26	90.51
CACTUS	573.71	270.57	2805.97	361.08
CACTUS COURT	0.10	2008.32	2806.07	21337.10
			2806.07	2369.40

Springdale East 2nd

Xsec Quantities

WICHITA, KANSAS



Ruggles & Bohm, P.A.

Engineering, Surveying, Land Planning

924 North Main
Wichita, Kansas 67203
www.rbkansas.com

(316) 264-8008
(316) 264-4621 fax
E-mail: info@rbkansas.com

DESIGN
CMB

DRAWN
EJG

REVIEW

UTILITY

DRAWING FILE
Paving {Xsec Quantity}

PROJECT NUMBER
472-83482

DATE
Nov. 27, 2002

RUG
JOB
2006E

SHEET
24
OF
27