



Total Volume Table							
Station	Cut Area	Fill Area	Cut Vol	Fill Vol	Cum Cut Vol	Cum Fill Vol	Net Vol
10+30.11	29.05	0.54	0.00	0.00	0.00	0.00	0.00
10+50.00	25.81	1.13	20.21	0.61	20.21	0.61	19.60
11+00.00	28.61	2.37	50.39	3.24	70.60	3.86	66.75
11+50.00	34.71	0.34	58.63	2.51	129.23	6.37	122.87
12+00.00	37.25	0.62	66.63	0.89	195.86	7.25	188.61
12+50.00	40.22	0.08	71.73	0.65	267.60	7.90	259.70
12+75.00	39.02	0.01	36.69	0.04	304.29	7.95	296.34
12+99.36	30.42	1.83	31.33	0.83	335.62	8.78	326.84

Drawing File: E:\Projects\10th Street Paving\10th Street Paving Base.dwg (XSEC.01)
 Project No. 16074507 CAPITAL IMPROVEMENT PROJECT
 Design: TPV
 Drawn: TPV
 Approved: TPV
 Scale: 1" = 10'

EARTHWORK CROSS SECTIONS

Baughman Company, P.A.
 315 Ellis St. Wichita, KS 67211 P 316-262-7271 F 316-262-0149
 ENGINEERING | SURVEYING | PLANNING | LANDSCAPE ARCHITECTURE