GENERAL SITE LAYOUT NOTES

1. SITE LAYOUT IS BASED ON A SURVEY PREPARED BY RUGGLES & BOHM. ALL PROPOSED IMPROVEMENTS AND ALIGNMENT ARE BASE UPON THE SURVEY INFORMATION INCLUDING ALL TOPOGRAPHICAL INFORMATION AND PROPOSED GRADES.

2. WRITTEN DIMENSIONS SHALL TAKE PRECEDENCE OVER SCALED DIMENSIONS. NOTIFY LANDSCAPE ARCHITECT OF ANY DISCREPANCIES BEFORE PROCEEDING WITH WORK.

3. GENERAL CONTRACTOR TO CALL KANSAS ONE-CALL 48 HOURS PRIOR TO BEGINNING EXCAVATION OR DEMOLITION WORK AT 316-687-2470 OR 1-800-DIG-SAFE.

4. UNDERGROUND FACILITIES, STRUCTURES AND UTILITIES ARE FROM DISK PROVIDED BY CIVIL ENGINEER. THEREFORE, THE RELATIONSHIP BETWEEN PROPOSED WORK AND EXISTING FACILITIES, STRUCTURES AND UTILITIES MUST BE CONSIDERED APPROXIMATE AND SUBJECT TO CHANGE. IT IS THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THEIR EXACT LOCATIONS AND THE EXISTENCE OF ANY NOT SHOWN. NOTIFY THE LANDSCAPE ARCHITECT AND CIVIL ENGINEER IMMEDIATELY OF ANY DISCREPANCIES AND VERIFY EXISTING CONDITIONS PRIOR TO COMMENCING WORK.

5. GENERAL CONTRACTOR TO CONTACT ALL LOCAL UTILITIES PRIOR TO THE BEGINNING OF ANY CONSTRUCTION TO COORDINATE THE LOCATION OF UTILITIES AND THE POSSIBLE RELOCATION OF EXISTING UTILITIES.

   KANSAS GAS COMPANY: 1-888-482-4950
   AQUILA ENERGY: 1-800-303-0357
   WESTAR ELECTRIC: 383-8650
   SOUTHWESTERN BELL: 1-800-286-8313
   COX COMMUNICATIONS: 262-4270
   WICHITA WATER & SEWER DEPARTMENT: 268-4908
   WICHITA ENGINEERING DEPARTMENT: 268-4501
   OFFICE OF CENTRAL INSPECTION: 268-4461

6. CONTRACTOR IS TO PROVIDE ALL SAFETY BARRIERS, FENCING ETC. AROUND CONSTRUCTION SITE AS REQUIRED BY LOCAL REGULATIONS. ALL CONSTRUCTION ACTIVITY MUST BE CONTAINED WITHIN THE LIMITS OF CONSTRUCTION BOUNDARY SHOWN ON PLANS.

7. THE CONTRACTOR SHALL RESTORE TO THE ORIGINAL CONDITION, ANY ADJACENT (OFF-SITE) PROPERTY DISTURBED BY HIS OPERATIONS, AND SHALL BE RESPONSIBLE FOR ALL DAMAGES AND ASSOCIATED COSTS AT NO EXPENSE TO OWNER.

8. THE GENERAL CONTRACTOR IS RESPONSIBLE FOR COORDINATING ALL WORK ON SITE. THIS INCLUDES BUT IS NOT LIMITED TO: COORDINATION BETWEEN THE EXISTING BIKE PATH AND TRAILHEAD, PROPOSED WATER LINE EXTENSIONS AND IRRIGATION SERVICE, AND EXISTING SITE IMPROVEMENTS AND PROPOSED IMPROVEMENTS. ANY DISCREPANCIES BETWEEN CONTRACT DOCUMENTS MUST BE BROUGHT TO THE ATTENTION OF THE PROJECT ENGINEER OR OWNER'S REPRESENTATIVE FOR RESOLUTION.

9. EARTH FORMED CONCRETE SHALL HAVE NO JOINTS ,EXCEPT, AS SHOWN ON THE PLANS. CONCRETE SHALL BE ALLOWED TO CRACK AND "SPIDER WEB" NATURALLY. CONCRETE SHALL HAVE #3 REBAR PLACED AT MID DEPTH PER DETAIL.

10. THE GENERAL CONTRACTOR SHALL SUBMIT ALL REQUIRED SHOP DRAWINGS FOR REVIEW AND APPROVAL BY OWNER'S REPRESENTATIVE A MINIMUM OF TWO WEEKS PRIOR TO SCHEDULED INSTALLATION OR CONSTRUCTION OF THOSE ITEMS.

11. THE GENERAL CONTRACTOR SHALL SUBCONTRACT LANDSCAPE WORK TO A LICENSED LANDSCAPE CONTRACTOR WITH A HISTORY OF COMPLETING SIMILAR PROJECTS IN SIZE AND TYPE IN THE WICHITA AREA.

12. PRIOR TO PURCHASE AND DELIVERY OF ALL NATURAL STONE SLABS AND BOULDERS, THE GENERAL CONTRACTOR SHALL CONTACT THE OWNER'S REPRESENTATIVE AND THE PROJECT ENGINEER TO BE PRESENT FOR THE SELECTION OF FINAL STONE AT THE SOURCE.

13. GENERAL CONTRACTOR TO INSTALL IRRIGATION SLEEVES UNDER PROPOSED SIDEWALKS/ PAVING. COORDINATE THIS PORTION OF THE WORK WITH THE IRRIGATION PLANS AND IRRIGATION CONTRACTOR.

14. REFER TO CIVIL DRAWINGS FOR LOCATION AND CONSTRUCTION OF WATER SERVICE LINES AND SITE ELECTRICAL SERVICE.

15. TRAFFIC CONTROL DURING CONSTRUCTION SHALL BE IN ACCORDANCE WITH STATE AND CITY REQUIREMENTS. AT ALL TIMES, TRAFFIC CONTROL AND CONSTRUCTION PROCEDURES SHALL BE PERFORMED IN A WAY AS TO PROTECT PERSONS AND PROPERTY. PROJECT SAFETY AND SECURITY SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR.

16. SURROUNDING AREAS AND PROPERTY SHALL BE PROPERLY PROTECTED FROM DAMAGE. IF DAMAGE OCCURS, IT SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO REPAIR IT TO PREVIOUS CONDITION, OR REPLACE IT AS DIRECTED BY THE OWNER'S REPRESENTATIVE.

17. REGARDLESS OF LAYOUT SHOWN ON PLANS, CONTRACTOR IS RESPONSIBLE FOR COMPLYING WITH CODE REQUIREMENTS REGARDING UTILITY CROSSINGS AND CLEARANCES. NOTIFY THE OWNER'S REPRESENTATIVE AND PROJECT ENGINEER OF ANY DISCREPANCIES IMMEDIATELY.

18. CONCRETE PAVER CONTRACTOR SHALL HAVE A MINIMUM OF FIVE YEARS EXPERIENCE WITH INSTALLATION OF CONCRETE PAVERS WITH SIMILAR PROJECT SCOPE. PROVIDE EXPERIENCE AND REFERENCE INFORMATION AT THE TIME OF BIDDING.

19. THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR CONTACTING WESTAR ENERGY TO ORDER AND COORDINATE THE INSTALLATION OF A GROUND MOUNT TRANSFORMER ON-SITE. THIS TRANSFORMER SHALL PROVIDE POWER FOR THE PROPOSED IRRIGATION SYSTEM AS WELL AS PROVIDE POWER FOR THE FUTURE RESTROOM FACILITY TO BE LOCATED ADJACENT TO THE PARKING LOT. (RESTROOM FACILITIES AND ASSOCIATED WORK NOT A PART OF THIS CONTRACT)

20. ALL TRASH RECEPTACLES, SIGNAGE, BOULDERS, BENCHES AND ANY OTHER IMPROVEMENTS SHALL BE LOCATED A MINIMUM OF 2' FROM THE EDGE OF THE BIKE PATH.

21. THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR THE INSTALLATION OF ALL STONE ASSOCIATED WITH THIS PROJECT. THIS INCLUDES THE ARTIST STONES. FINAL LOCATIONS AND ORIENTATIONS SHALL BE FIELD DIRECTED BY THE OWNER'S REPRESENTATIVE AND ARTIST CONSULTANT.

22. THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR THE PURCHASE OF ALL STONE ASSOCIATED WITH THIS PROJECT EXCLUDING THE ARTIST STONES.

23. PRIOR TO PURCHASE AND DELIVERY OF NATURAL STONE AND BOULDERS, THE GENERAL CONTRACTOR SHALL CONTACT THE LANDSCAPE ARCHITECT FOR A MATERIALS INSPECTION AND APPROVAL AT THE MATERIAL'S SOURCE OR SOURCES. CONTRACTOR SHALL REIMBURSE THE COST OF TRAVEL FOR TRAVEL DISTANCES GREATER THAN 100 MILES (ONE WAY).

24. ALL STONE TO BE INSTALLED ON SITE, INCLUDING THE ARTIST STONES SHALL BE COATED WITH AN ANTI-GRAFFITTIANT SYSTEM. APPLY PER APPROVED MANUFACTURER'S RECOMMENDATIONS. (BY GENERAL CONTRACTOR)
   GENERAL CONTRACTOR TO DO A TEST PRIOR TO APPLICATION.
   APPROVED PRODUCT:
   PROFESSIONAL Water Sealant & Anti-Graffiti System (OR APPROVED EQUIVALENT)
   AS MANUFACTURED BY:
   Professional Products of Kansas, Inc.
   4456 S. Clifton, Wichita, KS 67216
   800-676-7346

25. THE DRINKING FOUNTAINS SHALL BE THE FOLLOWING:
   MODEL 440 surface mount freeze resistant (OR APPROVED EQUIVALENT)
   AS MANUFACTURED BY:
   Most Dependable Fountains
   5705 Commander Dr.
   Arlington, TN 38002-0587
   (901)-867-0039 ph
   (901)-867-4008 fax
   www.mostdependable.com

26. SUBMIT MANUFACTURER'S WRITTEN SPECIFICATIONS AND SHOP DRAWINGS TO THE OWNER'S REPRESENTATIVE FOR FINAL APPROVAL PRIOR TO PRODUCT PURCHASE.

27. SUBSTITUTION REQUESTS MUST BE MADE DURING THE BIDDING PROCESS APPROVAL OF THE DESIRED SUBSTITUTE BY THE OWNER'S REPRESENTATIVE MUST BE GIVEN IN WRITING PRIOR TO THE SUBSTITUTION BEING ACCEPTED. GENERAL CONTRACTOR TO SUBMIT ALL PERTINENT PRODUCT DATA WITH THE SUBSTITUTION REQUEST.

28. CONCRETE CONTRACTOR SHALL HAVE A MINIMUM OF FIVE YEARS EXPERIENCE WITH COLORED CONCRETE INSTALLATION WITH SIMILAR PROJECT SCOPE. PROVIDE EXPERIENCE AND REFERENCE INFORMATION AT THE TIME OF BIDDING.

29. THE GENERAL CONTRACTOR SHALL CONSTRUCT 2 MOCK-UP PANELS OF THE PROPOSED INTEGRALLY COLORED EARTH-FORMED CONCRETE PAVEMENT. THE MOCK-UP PANELS SHALL BE APPROXIMATELY 5'x5' SQUARE IN SIZE AND BE LOCATED ON-SITE FOR APPROVAL. SEE COLORED CONCRETE SPECIAL PROVISIONS FOR ADDITIONAL REQUIREMENTS.

30. THE GENERAL CONTRACTOR SHALL INSTALL ALL SITE AMENITIES (BENCHES, TRASH RECEPTACLES, DRINKING FOUNTAIN, AND BIKE RACK PER MANUFACTURER'S SPECIFICATIONS AND RECOMMENDATIONS. PRIOR TO INSTALLATION AN INSPECTION OF AMENITIES IN THEIR FINAL LOCATIONS FOR REVIEW AND APPROVAL BY THE OWNER'S REPRESENTATIVE.

31. GEOTEXTILE FILTER FABRIC SHALL BE INSTALLED UNDER SPECIFIED AGGREGATE UNDER LIMESTONE BOULDERS AND LEDGEROCK. THIS FILTER FABRIC AND AGGREGATE SHALL BE INCIDENTAL ITEMS TO THE INSTALLATION OF THE NATURAL LIMESTONE ON THE PROJECT.

32. THE OWNER (CITY OF WICHITA) SHALL RENDER ALL INSPECTIONS AND TESTING FOR THIS PROJECT. COORDINATE INSPECTIONS AND TESTING REQUIREMENTS WITH THE CITY OF WICHITA.

33. THIS PROJECT IS SUBJECT TO ALL CITY OF WICHITA STANDARD SPECIFICATIONS.

34. GENERAL CONTRACTOR SHALL EMPLOY THE SERVICES OF A LICENSED KANSAS LAND SURVEYOR TO STAKE THE FINAL HORIZONTAL AND VERTICAL ALIGNMENT OF THE PROPOSED IMPROVEMENTS. THIS SHALL BE SUBSIDIARY TO THE OTHER ITEMS IN THE CONTRACT.

GENERAL SITE GRADING NOTES

1. THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR ALL SITE GRADING AND EARTHWORK ON SITE. THIS INCLUDES BUT IS NOT LIMITED TO; ALL EARTH BERMS, RETAINING WALL BACKFILL, EXCAVATION, AND PAVING SUBGRADE.

2. THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR ENSURING THAT ALL GRADED AREAS ON SITE HAVE POSITIVE DRAINAGE AND NO PONDING OR PUDDLING OCCURS. ALL DEPRESSIONS MUST BE GRADED TO DRAIN AS SHOWN ON THE GRADING PLANS.

3. THE GENERAL CONTRACTOR IS RESPONSIBLE FOR GRADING ALL SLOPES AS SHOWN ON THE PLANS. THIS INCLUDES GRADING SLOPES AT THE GIVEN GRADES AND SLOPES. NO SLOPES SHALL EXCEED THE MAXIMUM ALLOWABLE GRADE SHOWN ON THE PLANS.

4. ALL PAVED AREAS MUST BE GRADED SO THAT SLOPES DON'T EXCEED THE MAXIMUM OF 1.9% CROSS SLOPE AND 4.9% LONGITUDINAL SLOPE. ALL SLOPES SHALL BE CHECKED WITH A DIGITAL LEVEL. ANY PAVED AREAS SLOPED MORE THAN THE NOTED MAXIMUMS SHALL BE REMOVED AND REPLACED AT NO EXPENSE TO THE OWNER.

5. GENERAL CONTRACTOR SHALL EMPLOY THE SERVICES OF A LICENSED KANSAS LAND SURVEYOR TO STAKE THE ELEVATION AND LOCATION OF ALL IMPROVEMENTS AT THE TRAILHEAD AND ESTABLISH AN ON-SITE BENCHMARK AT THE TRAILHEAD LOCATION.

6. CONCRETE PAVEMENT LOCATED UNDER PROPOSED BENCHES SHALL BE SLOPED AT NO MORE THAN 1% IN ANY DIRECTION TO ENSURE A LEVEL SEATING SURFACE.

ARTIST WORK

1. THE SCOPE OF THE ARTIST WORK IS AS FOLLOWS:
   PURCHASE OF ARTIST STONES
   CARVING, SANDBLASTING, AND ANY OTHER RELATED WORK DONE TO THE STONES,
   CUTTING AND SANDBLASTING OF TEXT ON THE "BROKEN STONE BOULDER",
   PURCHASE AND INSTALLATION OF BRONZE INTERPRETIVE PLAQUE

2. THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR THE TRANSPORTATION COSTS OF THE "ARTIST STONES" FROM THE SELECTED QUARRY. TRAVEL DISTANCE TO THE JOB SITE IS APPROXIMATELY 60 MILES ONE WAY. APPROXIMATE ARTIST STONE WEIGHT: 16 TONS.

3. THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR INSTALLATION OF THE ARTIST STONES AS SHOWN ON THE DRAWINGS.

4. THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATION OF THE ARTIST CONSULTANT'S WORK TO ENSURE THAT COMPLETION OF THE ARTWORK IS DONE IN A MANNER AND TIMEFRAME TO NOT DELAY THE PROJECT.

5. THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE THE PURCHASE AND APPLICATION OF THE SPECIFIED ANIT-GRAFFITTIANT SEALER ON ALL STONE INCLUDING THE "ARTIST STONES".

SITE DESCRIPTION/CALCULATIONS:

DESCRIPTION:
SITE CLEARING OF APPROXIMATELY 4 ACRES OF VACANT LAND ALONG THE EAST BORDER OF GROVE PARK ADJACENT TO HILLSIDE AVE. SITE SHALL BE RESEEDED AND PLANTED WITH NATIVE PRAIRIE TYPE GRASSES, FORBS, SHRUBS, AND TREES. CONSTRUCTION OF A TRAILHEAD AT THE NORTHEAST CORNER OF THE EXISTING PARKING LOT. TRAILHEAD SHALL FEATURE COLORED CONCRETE PATHS, DRINKING FOUNTAIN, TRASH RECEPTACLES, BENCHES, AND LANDSCAPING. NATURAL STONE BOULDERS AND SLABS, AND BIKE RACKS.

INFORMATION:

- PROPOSED USE: RECREATION
- TOTAL IMPROVED SITE AREA: 174,240± (4 ACRES±)

BENCHMARK

CITY OF WICHITA DISC LOCATED AT THE INTERSECTION OF HILLSIDE AND 29TH STREET NORTH SOUTHWEST CORNER OF RCB ON THE TOP, SOUTH END OF THE HUB GUARD 401.54 FEET SOUTHWEST OF THE SECTION CORNER.

ELEVATION: 1343.21 M.S.L.

SUMMARY OF QUANTITIES

ITEMS	TOTAL	UNIT
KDOT Participating Items		
Integral Colored Concrete Pavement (5") W/Agg. Base	1,550	SF
Plain Sidewalk Concrete (5") W/Agg. Base	50	SF
Concrete Pavers W/Agg. Base	600	LS
Site Clearing/Site Preparation/Site Restoration	1	LS
Common Excavation	750	CY
Common Excavation Contractor Furnished	1,200	CY
Fence Removal	190	LF
Erosion Control Measures/Tree Protection	1	LS
Concrete Foundations (Artist Stones)	24.5	CY
Sleeves (4" PVC Schedule 40)	135	LF
Sleeves (2" PVC Schedule 40)	120	LF
Limestone Boulders (Purchase, Transportation, & Installation)	28	TON
Artist Stones (Transportation & Installation Only)	16	TON
Stacked Limestone	60	TON
Limestone Step Stones	3.5	TON
Weathered Limestone Bench	3	EA
2" Water Service Line (Irrigation Service)	541	LF
1" Short Service (in duplex setter) (Irrigation Service)	2	EA
1" Check Valve	1	EA
Automatic Irrigation System	1	LS
Native Prairie Seeding	4	AC
Permanent Seeding (Cody Buffalo Grass Seed)	1	AC
Buffalo Sod (Legacy Variety)	1,700	SY
Overstory Trees (3" Caliper)	41	EA
Understory Trees (2" Caliper)	35	EA
Shrubs (2-Gal.)	166	EA
Shrubs (1-Gal.)	18	EA
Perennials (1-Gal.)	151	EA
Perennials (4"-Pots)	746	EA
Planting Bed Preparation	6,500	SF
Shredded Cypress Mulch	7,000	SF

Non-KDOT Participating Items		
Drinking Fountain	2	EA
Bike Rack Loop	3	EA
Bench/Trash Receptacle	1	LS
Artist Work	1	LS
Anti-Graffitiant Sealant	1	LS
Electric Panel,Switch,Rack, Associated Equip.	1	LS
2" Conduit w/pull-wire	300	LF
Electric Transformer W/Pad	1	LS
2" Water Service Line (Domestic Service)	1,097.07	LF
1" Water Service Line (Domestic Service)	116.61	LF
1" Short Service (in duplex setter) (Domestic Service)	2	EA
1" Gate Valve & Box	3	EA
1" Check Valve	1	EA

ADD ALTERNATE BID ITEMS

ITEMS	TOTAL	UNIT
Add Alternate Bid Item #1		
2" Custom Meter (Domestic Service)	1	EA
2" Custom Meter (Irrigation Service)	1	EA

Description of Add Alternate:
Contractor to submit an add alternate bid price for one 2" Custom Meter for the domestic water supply and one 2" Custom Meter for the irrigation supply in lieu of the base bid items for 1" duplex setters for both the domestic and irrigation supply and associated check valves.

FHWA REGION NO.	STATE	PROJECT NUMBER	FISCAL YEAR	SHEET NUMBER	TOTAL SHEETS
7	KANSAS	TE-0254-01	2005	3	21
FED. AID NO.					

CONCRETE PAVER PRODUCTS

MANUFACTURER/ SUPPLIER	PRODUCT	FINISH/COLOR
Pavestone, Inc. Lee's Summit, MO (816) 524-9900 ph (816) 524-9901 fax www.pavestone.com	Plaza Stone Series	Color: Red/Brown (Kansas City) Finish: Heritage
Belgard Atlanta, GA (770) 804-3363 ph (770) 804-3369 fax www.belgard.com	Dublin Cobble Combo	Color: Esterel Red
Hanover Arch. Products Hanover, PA (717) 637-0500 ph (717) 637-7145 fax www.hanoverpavers.com	Tumbled Prest Brick	Color: Salmon/Charcoal Blend

- APPROVED STEEL EDGE RESTRAINT MANUFACTURERS LISTED IN SPECIAL PROVISION ITEM #3.

INTEGRAL CONCRETE COLOR

MANUFACTURER/ SUPPLIER	PRODUCT	FINISH/COLOR
QC Construction Products Madera, CA 93639 (800) 453-8213 ph (717) 436-9839 fax www.qconcprod.com	QC Integral Color	Integral Color: Submit Standard Color Range Finish: Medium Broom
L.M. Scofield Douglasville, GA (770) 920-6000 ph (777) 920-6060 fax www.lmscofield.com	Chromix Admixture	Integral Color: Submit Standard Color Range Finish: Medium Broom
Increte Systems Inc. Tampa, FL (800) 752-4626 ph (813) 886-8811 www.incrte.com	Color-Crete	Integral Color: Submit Standard Color Range Finish: Medium Broom

- FOLLOW MANUFACTURER'S WRITTEN SPECIFICATIONS FOR INTEGRAL COLOR
- CONSTRUCTION OF TWO (2) 60"x60" MOCK-UP PANELS ARE REQUIRED TO ESTABLISH FINAL COLOR AND STANDARD OF WORKMANSHIP TO BE ACHIEVED.

BIKE RACK

MANUFACTURER/ SUPPLIER	PRODUCT	FINISH/COLOR
DuMor Inc. P.O. Box 142 Mifflinton, PA (717) 436-2106 ph (717) 436-9839 fax www.dumor.com	Bike Rack 83-S-1 Embedment	Powder Coat - Bronze
BRP Enterprises, Inc. 3200 O St. Lincoln, NE (402) 438-5311 ph (402) 438-5349 fax www.brponline.com	Manchester LL-02-PF Embedment	Color: Custom,Match Bench (Bronze)
Keystone Ridge P.O. Box 2008 Butler, PA (800) 284-8208 ph www.keystoneridgedesigns.com	SNO1-Sinle Loop Embedment	Color: Custom,Match Bench (Bronze)

BENCH/TRASH RECEPTACLE

BENCH (3) TRASH RECP. (2)	DuMor 131 Series PL DuMor 85-22 PL	Arcata Backless Chase Park w/ Liner Side Opening	Yukon YBR-2572-SG Backless Yukon YTS 2232 S SG
FINISH/COLOR	Slats: Recycled Plastic-Cedar Legs: Powder Coat - Bronze	Powder Coat - Bronze	Powder Coat - Bronze
SPECIAL ITEMS	6' length Surface Mount	6' length Surface Mount	6' length Surface Mount
MANUFACTURER/ SUPPLIER	DuMor Inc. P.O. Box 142 Mifflinton, PA 17059 (717) 436-2106 ph (717) 436-9839 fax www.dumor.com	Landscape Forms 431 Lawndale Ave. Kalamazoo, MI (800) 521-2546 ph (269) 381-3455 fax www.landscapeforms.com	Hines III 3600 St. Agustine Rd. Jacksonville, FL (904) 399-4592 ph (904) 396-1867 fax www.hinesiii.com

- BENCHES AND TRASH RECEPTACLES MUST BE PURCHASED FROM THE SAME MANUFACTURER.

PRINTS ISSUED		
DATE	ITEM	NO.
1/10/05	FIELD CHECK SET	
6/13/05	OFFICE CHECK SET	
9/29/05	REVISED OFFICE CHECK	
11/29/05	FINAL PLANS	
1/22/07	FOR CONSTRUCTION	

LAW/KINGDON, INC.
ARCHITECTS ● ENGINEERS ● PLANNERS
LANDSCAPE ARCHITECTS
345 RIVERVIEW #200, WICHITA, KS 67203
Phone (316) 266-9230 Fax: (316) 266-9205

Copyright © 2007

DRAWN	CHECKED
JAB	JAB

K-96 TRAILHEAD LANDSCAPE PROJECT

GROVE PARK WICHITA, KANSAS

PROJECT NUMBER 044150

GENERAL NOTES

SHEET TITLE
SHEET NUMBER

SA0.1

OF 1 SHEETS