



NOTES:

1. The Contractor shall protect traffic by use of proper and necessary flags, lights, signals, barricades or other warning devices as needed, all in accordance with the latest edition of the Manual On Uniform Traffic Control Devices (MUTCD).
2. Channelizing Devices shall be either "Reflectorized Drum" type at least 36" tall, or "Tubular Markers" at least 28" tall with retroreflectorized bands.
3. All cost associated with the Installation, Maintenance, and Removal of Traffic Control Devices shall be included in Lump Sum Bid Item "Traffic Control."

	Northgate Offsite Drainage Traffic Control & Sign Details Storm Water Drain #307	
	<small>Baughman Company, P.A. 315 8th St. W. Palm Beach, FL 33411 P 3162627271 F 3162620149 ENGINEERING SURVEYING PLANNING LANDSCAPE ARCHITECTURE</small>	
PROJECT NUMBER 468-54253	DESIGN RDM/AEG	DRAWN RDM
REVISIONS:	APPROVED AEG	DATE 3-14-07
SCALE No Scale		SHEET 10 OF 22