

J:\PROJECTS\2015\150104077\_COW\_17TH STREET REHAB\_150177\_CADD\SHS\06\CIVIL\PAV\15177E01.DWG  
 J:\PROJECTS\2015\150104077\_COW\_17TH STREET REHAB\_150177\_CADD\SHS\06\CIVIL\PAV\15177E01.DWG  
 ROUTED: Wednesday, May 03, 2017 @ 03:52PM

PAVEMENT REPAIR SUMMARY											
Plan Sheet No.	Station	Offset	Repair Type	Repair Size	Concrete Pavement Removed & Replaced (> 16.0 S.Y.) (sy)	Concrete Curb, Mono Edge, Removed and Replaced (lf)	Concrete Pavement Removed & Replaced (≤ 16.0 S.Y.) (sy)	Concrete Sidewalk Removed and Replaced (sf)	Concrete Curb, Mono Edge (6" & 1 1/2") (lf)	Sidewalk Thickening (lf)	Notes

4	15+00.0 to 15+02.0	C/L	Conc. Patch	2'x36'			8.0				
	15+17.8 to 15+29.8	Lt.	Conc. Patch	2'x12'			2.7				
	15+29.8 to 15+60.0	Lt.	Full Panel	24'x30'	80.0				30.0		
	15+60.0 to 15+66.0	Lt.	Conc. Patch	2'x6'			1.4				
	15+60.0 to 15+62.0	Lt.	Corner Patch	2'x2'			0.5				
	15+55.2 to 15+61.3	Lt.	Sidewalk	6'x6'				36.0			
	15+89.7 to 15+94.7	Lt.	Curb	5'		5.0					
	16+17.1 to 16+23.1	Rt.	Conc. Patch	6'x17'			11.3				
	16+34.3 to 16+41.3	Lt.	Sidewalk	4'x7'				28.0			
	16+50.1 to 16+56.1	Rt.	Conc. Patch	6'x17'			11.3				
	16+63.6 to 16+78.6	Lt.	Conc. Patch	2'x15'			3.3				
	16+70.7 to 16+75.7	Lt.	Curb	8'		8.0					
	16+78.4 to 17+01.0	Rt.	Full Panel	23'x17'	43.4						
	16+98.7 to 17+01.0	Rt.	Curb	43'					43.0		
	16+91.4 to 17+13.0	Rt.	Valley Gutter		60.0						
	17+37.1 to 17+41.3	Rt.	Curb	15'		15.0					
	18+05.7 to 18+35.7	Lt.	Full Panel	24'x30'	80.0				30.0		
	18+03.4 to 18+09.3	Rt.	Corner Patch	6'x7'			4.7				
	18+05.7 to 18+35.7	Lt.	Sidewalk	4'x30'				120.0		30.0	
	18+33.0 to 18+39.0	Rt.	Conc. Patch	6'x17'			11.3				
18+78.9 to 18+88.9	Lt.	Curb	10'		10.0						
18+78.9 to 18+88.9	Lt.	Sidewalk	4'x10'				40.0				
18+92.9 to 18+98.9	Rt.	Conc. Patch	6'x19'			12.7					
19+22.7 to 19+28.7	C/L	Corner Patch	6'x7'			4.7					
19+22.4 to 19+28.4	Lt.	Corner Patch	6'x7'			4.7					
19+82.6 to 19+88.6	Lt.	Conc. Patch	6'x24'			16.0		6.0			
19+82.6 to 19+88.6	Lt.	Sidewalk	4'x6'				24.0		6.0		
Sheet Totals					263.4	38.0	92.6	248.0	109.0	36.0	

5	20+09.6 to 20+15.6	Rt.	Conc. Patch	6'x17'			11.3				
	20+27.3 to 20+48.3	Lt.	Sidewalk & Curb	4'x21'		21.0		84.0		21.0	
	20+73.6 to 20+79.6	Lt.	Conc. Patch	6'x12'			8.0				
	20+73.6 to 20+79.6	Lt.	Sidewalk & Curb	4'x6'				24.0	6.0	6.0	
	20+98.5 to 21+01.5	Lt.	Sidewalk	4'X3'		10.0		40.0		3.0	
	21+07.5 to 21+10.5	Lt.	Sidewalk	4'x3'						3.0	
	21+32.7 to 21+38.7	C/L	Corner Patch	6'x7'			4.7				
	21+32.9 to 21+38.5	Lt.	Conc. Patch	6'x12'			8.0				
	21+32.9 to 21+38.5	Lt.	Sidewalk & Curb	4'x6'				24.0	6.0	6.0	
	21+62.7 to 21+68.7	Rt.	Conc. Patch	6'x19'			12.7				
	22+22.8 to 22+28.7	Lt.	Conc. Patch	6'x12'			8.0				
	22+22.8 to 22+28.7	Lt.	Sidewalk & Curb	4'x6'				24.0	6.0	6.0	
	22+22.8 to 22+28.8	Rt.	Conc. Patch	6'x3.5'			2.3				
	22+49.8 to 22+55.8	Lt.	Conc. Patch	6'x12'			8.0				
	22+49.8 to 22+55.8	Lt.	Sidewalk & Curb	4'x6'				24.0	6.0	6.0	
	22+52.8 to 22+58.8	Rt.	Conc. Patch	6'x8'			5.3				
	22+85.8 to 23+45.5	Lt.	Conc. Panel	12'x59'	78.7						
	22+85.8 to 23+45.5	Lt.	Sidewalk & Curb	4'x59'				236.0	59.0	59.0	
	23+12.8 to 23+18.8	Rt.	Conc. Patch	6'x5'			3.3				
	23+83.2 to 23+99.5	Rt.	Conc. Panel	17'x17'	32.1						
23+99.5 to 24+17.5	Lt. & Rt.	Conc. Patch	18'x36'	72.0							
23+99.5 to 24+17.5	Lt.	Sidewalk & Curb	4'x18'				72.0	18.0	18.0		
24+25.9 to 24+31.9	C/L	Conc. Patch	4'x6'			2.7					
24+57.3 to 24+72.4	Lt.	Sidewalk	8'x15'				13.3				
24+60.4 to 24+71.7	Lt.	Curb	11.5'		11.5						
24+71.7 to 24+77.7	Lt.	Conc. Patch & Curb	6'x24'			16.0		6.0			
25+14.6 to 25+20.6	Lt.	Conc. Patch & Curb	6'x24'			16.0		6.0			
25+44.5 to 25+50.5	Lt.	Conc. Patch & Curb	6'x24'			16.0		6.0			
Sheet Totals					182.8	42.5	122.3	541.3	119.0	128.0	

PAVEMENT REPAIR SUMMARY											
Plan Sheet No.	Station	Offset	Repair Type	Repair Size	Concrete Pavement Removed & Replaced (> 16.0 S.Y.) (sy)	Concrete Curb, Mono Edge, Removed and Replaced (lf)	Concrete Pavement Removed & Replaced (≤ 16.0 S.Y.) (sy)	Concrete Sidewalk Removed and Replaced (sf)	Concrete Curb, Mono Edge (6" & 1 1/2") (lf)	Sidewalk Thickening (lf)	Notes

6	26+20.4 to 27+59.5	Lt.	Panel Replacement	12'x107'	142.7						
	26+20.4 to 27+59.5	Lt.	Curb	107'						107.0	
	26+34.6 to 26+40.6	Lt.	Conc. Patch	6'x12'			8.0				
	27+24.6 to 27+30.6	Lt.	Conc. Patch	6'x12'			8.0				
	27+27.7 to 27+59.5	Lt.	Panel Replacement	9.5'x32'	33.8						
	27+87.5 to 27+93.1	Lt.	Corner Patch	6'x7'			4.7				
	28+20.6 to 28+47.7	Lt.	Panel Replacement	9.5'x27'	28.5						
	28+42.8 to 28+47.7	Lt.	Panel Replacement	4'x5'	2.2						
	28+42.8 to 28+47.7	Lt.	Curb	5'						5.0	
	28+44.7 to 28+50.7	C/L	Corner Patch	6'x7'			4.7				
	28+47.7 to 29+55.8	Lt.	Panel Replacement	12'x108'	144.0						
	28+47.7 to 29+55.8	Lt.	Curb	108'						108.0	
	28+59.6 to 28+65.2	C/L	Corner Patch	6'x3.5'			2.3				
	28+74.9 to 28+80.6	C/L	Corner Patch	3'x3.5'			1.2				
	28+77.8 to 29+58.4	Lt.	Panel Replacement	12'x80.5'	107.3						
	29+80.9 to 30+23.2	Lt.	Panel Replacement	12'x42.5'	56.7						
	29+80.9 to 30+23.2	Lt.	Curb	42.5'						42.5	
	30+80.4 to 30+86.4	Lt.	Conc. Patch	6'x12'			8.0				
	30+80.4 to 30+86.4	Lt.	Curb	6'						6.0	
	Sheet Totals					515.2	0.0	36.9	0.0	268.5	0.0

7	31+87.9 to 31+95.9	Lt.	Conc. Patch	4'x8'						3.6	
	32+75.2 to 32+80.9	C/L	Corner Patch	6'x7'						4.7	
	33+28.2 to 33+38.0	Lt.	Conc. Patch	4'x10'						4.4	
	33+38.2 to 33+45.2	Lt.	Conc. Patch	4'x7'						3.1	
	33+38.2 to 33+45.2	Lt.	Curb	6.5'						6.5	
	34+25.4 to 34+31.1	C/L	Corner Patch	6'x7'						4.7	
	34+60.8 to 35+21.6	Lt.	Panel Replacement	12'x61'	81.3						
	34+60.8 to 35+21.6	Lt.	Curb	61'						61.0	
	34+94.6 to 35+21.9	Lt.	Sidewalk	6'x27.5'						165.0	27.5
	35+25.2 to 35+30.2	Lt.	Curb	5'					5.0		
	35+58.2 to 35+88.4	Lt.	Panel Replacement	12'x30'	40.0						
	35+58.2 to 35+88.4	Lt.	Curb	30'						30.0	
	36+18.0 to 36+41.9	Lt.	Panel Replacement	12.5'x24'	33.3						
	36+18.0 to 36+41.9	Lt.	Curb	24'						24.0	
	36+56.8 to 36+78.3	Lt.	Panel Replacement	12'x21.5'	28.7						
36+56.8 to 36+78.3	Lt.	Curb	21.5'						21.5		
Sheet Totals					183.3	5.0	20.5	165.0	143.0	27.5	

8	37+98.8 to 38+04.8	Lt.	Conc. Patch	6'x12'						8.0	
	37+98.8 to 38+04.8	Lt.	Curb	6'						6.0	
	38+29.4 to 38+35.0	Lt.	Corner Patch	6'x7'						4.7	
	38+63.6 to 38+68.6	Lt.	Curb	5'					5.0		
	39+88.6 to 40+00.6	Rt.	Conc. Patch	6'x12'						8.0	
	39+88.6 to 40+00.6	Rt.	Curb	12'						12.0	
	40+15.5 to 40+21.1	C/L	Corner Patch	6'x7'						4.7	
	40+46.0 to 40+51.7	C/L	Corner Patch	6'x7'						4.7	
	40+46.0 to 40+51.7	Rt.	Conc. Patch	6'x12'						8.0	
	40+46.0 to 40+51.7	Rt.	Curb	6'						6.0	
	40+75.6 to 40+81.6	Rt.	Conc. Patch	6'x24'						16.0	
	40+75.6 to 40+81.6	Rt.	Curb	6'						6.0	
	41+08.6 to 41+14.6	Rt.	Conc. Patch	6'x24'						16.0	
	41+08.6 to 41+14.6	Rt.	Curb	6'						6.0	
	41+19.4 to 41+25.4	C/L	Conc. Patch	5'x6'						3.3	
41+38.8 to 41+44.8	Lt.	Conc. Patch	6'x12'						8.0		
41+38.8 to 41+44.8	Lt.	Curb	6'						6.0		
Sheet Totals					0.0	5.0	81.4	0.0	42.0	0.0	



STREET REHABILITATION FOR  
**17TH STREET BETWEEN HILLSIDE & OLIVER**  
 WICHITA, KS

©2017  
 MKEC Engineering  
 All Rights Reserved  
 www.mkec.com  
 These drawings and their contents, including, but not limited to, all concepts, designs, & ideas are the exclusive property of MKEC Engineering (MKEC), and may not be used or reproduced in any way without the express consent of MKEC.

**PAVEMENT REPAIR SCHEDULE**

PROJECT NO.	472-85215	
DATE	5/3/2017	
SCALE	NTS	
DESIGNED	DRAWN	CHECKED
JRA	BKS	BLB

NO.	REVISION	DATE

SHEET NO.