

J:\PROJECTS\2015\150104077_COW_17TH STREET REHAB_150177_CADSHTS\06_CIVIL\PAV15177E02.DWG
 J:\PROJECTS\2015\150104077_COW_17TH STREET REHAB_150177_CADSHTS\06_CIVIL\PAV15177E02.DWG
 ROUTED: Wednesday, May 03, 2017 @ 03:49PM

PAVEMENT REPAIR SUMMARY											
Plan Sheet No.	Station	Offset	Repair Type	Repair Size	Concrete Pavement Removed & Replaced (> 16.0 S.Y.) (sy)	Concrete Curb, Mono Edge, Removed and Replaced (lf)	Concrete Pavement Removed & Replaced (≤ 16.0 S.Y.) (sy)	Concrete Sidewalk Removed and Replaced (sf)	Concrete Curb, Mono Edge (6" & 1 1/2") (lf)	Sidewalk Thickening (lf)	Notes

9	42+58.1 to 42+64.1	Lt.	Conc. Patch	6'x24'			16.0				
	42+58.1 to 42+64.1	Lt.	Curb	6'					6.0		
	43+45.7 to 43+51.7	Lt.	Conc. Patch	6'x24'			8.0				
	43+45.7 to 43+51.7	Lt.	Curb	6'					6.0		
	43+45.7 to 43+51.7	Rt.	Conc. Patch	6'x24'			8.0				
	43+45.7 to 43+51.7	Rt.	Curb	6'					6.0		
	43+78.7 to 44+38.6	Rt.	Panel Replacement	12'x60'		80.0					
	43+78.7 to 44+38.6	Rt.	Curb	60'					60.0		
	44+05.7 to 44+11.7	Lt. & Rt.	Conc. Patch	6'x36'			24.0				
	44+05.7 to 44+11.7	Lt.	Curb	6'					6.0		
	44+35.6 to 44+41.6	Lt. & Rt.	Conc. Patch	6'x36'			24.0				
	44+35.6 to 44+41.6	Lt.	Curb	6'					6.0		
	44+65.8 to 44+71.5	Rt.	Corner Patch	6'x7'			4.7				
	44+95.9 to 45+01.6	C/L	Corner Patch	6'x7'			4.7				
	44+95.7 to 45+01.4	Rt.	Corner Patch	6'x7'			4.7				
	45+26.1 to 45+31.7	Rt.	Corner Patch	6'x7'			4.7				
	45+86.1 to 45+91.8	Lt.	Corner Patch	6'x7'			4.7				
	45+85.6 to 45+91.3	Rt.	Corner Patch	6'x7'			4.7				
	46+15.8 to 46+21.8	Lt.	Conc. Patch	6'x24'			16.0				
	46+15.8 to 46+21.8	Lt.	Curb	6'					6.0		
	46+15.8 to 46+21.8	Rt.	Conc. Patch	6'x24'			16.0				
	46+15.8 to 46+21.8	Rt.	Curb	6'					6.0		
	46+45.8 to 46+51.8	Lt. & Rt.	Conc. Patch	6'x36.5'			24.3				
	47+06.0 to 47+12.0	Lt.	Conc. Patch	6'x24'			16.0				
	47+06.0 to 47+12.0	Lt.	Curb	6'					6.0		
	47+06.0 to 47+12.0	Rt.	Conc. Patch	6'x24'			16.0				
	47+06.0 to 47+12.0	Rt.	Curb	6'					6.0		
	47+35.8 to 47+41.8	Lt.	Conc. Patch	6'x24'			16.0				
	47+35.8 to 47+41.8	Lt.	Curb	6'					6.0		
	47+35.8 to 47+41.8	Rt.	Conc. Patch	6'x24'			16.0				
	47+35.8 to 47+41.8	Rt.	Curb	6'					6.0		
	47+65.9 to 47+71.9	Lt.	Conc. Patch	6'x24'			16.0				
	47+65.9 to 47+71.9	Lt.	Curb	6'					6.0		
47+65.9 to 47+71.9	Rt.	Conc. Patch	6'x24'			16.0					
47+65.9 to 47+71.9	Rt.	Curb	6'					6.0			
47+95.6 to 48+01.6	Rt.	Conc. Patch	6'x24'			16.0					
47+95.6 to 48+01.6	Rt.	Curb	6'					6.0			
Sheet Totals					80.0	0.0	276.5	0.0	144.0	0.0	

10	48+56.0 to 48+62.0	Lt. & Rt.	Conc. Patch	6'x36'			24.0				
	48+56.0 to 48+62.0	Rt.	Curb	6'					6.0		
	49+06.1 to 49+11.7	C/L	Corner Patch	6'x7'			4.7				
	49+36.1 to 49+41.7	C/L	Corner Patch	6'x7'			4.7				
	49+36.0 to 49+41.7	Rt.	Corner Patch	6'x7'			4.7				
	49+66.1 to 49+71.7	Rt.	Corner Patch	6'x7'			4.7				
	49+96.2 to 50+01.8	Rt.	Corner Patch	6'x7'			4.7				
	50+26.1 to 50+32.1	Lt. & Rt.	Conc. Patch	6'x36'			24.0				
	50+26.1 to 50+32.1	Lt.	Curb	6'					6.0		
	50+56.2 to 50+62.2	Lt.	Conc. Patch	6'x12'			8.0				
	50+56.2 to 50+62.2	Lt.	Curb	6'					6.0		
	50+56.1 to 50+61.8	Rt.	Corner Patch	6'x7'			4.7				
	50+83.2 to 50+89.2	Rt.	Conc. Patch	6'x24'			16.0				
	50+83.2 to 50+89.2	Rt.	Curb	6'					6.0		
	50+89.2 to 51+11.9	Rt.	Panel Replacement	12'x23'		30.7					
	51+76.0 to 51+82.0	Rt.	Conc. Patch	6'x24'			16.0				
	51+76.1 to 51+81.8	Lt.	Corner Patch	6'x7'			4.7				
	52+06.2 to 52+12.2	Lt. & Rt.	Conc. Patch	6'x48'			32.0				
	52+06.2 to 52+12.2	Lt. & Rt.	Curb	6'					6.0		
	52+36.3 to 52+42.3	Rt.	Conc. Patch	6'x24'			16.0				
	52+36.3 to 52+42.3	Rt.	Curb	6'					6.0		
	52+96.2 to 53+02.2	Rt.	Conc. Patch	6'x24'			16.0				
	52+96.2 to 53+02.2	Rt.	Curb	6'					6.0		
	53+26.2 to 53+32.2	Rt.	Conc. Patch	6'x24'			16.0				
	53+26.2 to 53+32.2	Rt.	Curb	6'					6.0		
	53+26.4 to 53+32.4	Lt.	Conc. Patch	6'x12'			8.0				
53+26.4 to 53+32.4	Lt.	Curb	6'					6.0			
53+53.3 to 53+59.3	Rt.	Conc. Patch	6'x12'			8.0					
53+53.3 to 53+59.3	Rt.	Curb	6'					6.0			
Sheet Totals					30.7	0.0	216.9	0.0	60.0	0.0	

PAVEMENT REPAIR SUMMARY											
Plan Sheet No.	Station	Offset	Repair Type	Repair Size	Concrete Pavement Removed & Replaced (> 16.0 S.Y.) (sy)	Concrete Curb, Mono Edge, Removed and Replaced (lf)	Concrete Pavement Removed & Replaced (≤ 16.0 S.Y.) (sy)	Concrete Sidewalk Removed and Replaced (sf)	Concrete Curb, Mono Edge (6" & 1 1/2") (lf)	Sidewalk Thickening (lf)	Notes

11	54+16.2 to 54+22.2	Rt.	Conc. Patch	6'x24'			16.0				
	54+16.2 to 54+22.2	Rt.	Curb	6'					6.0		
	54+46.5 to 54+52.5	Rt.	Conc. Patch	6'x24'			16.0				
	54+50.1 to 54+79.6	Lt.	Panel Replacement	12'x30'	40.0						
	54+50.1 to 54+79.6	Lt.	Curb	30'					30.0		
	54+76.4 to 54+82.4	Rt.	Conc. Patch	6'x24'			16.0				
	54+76.4 to 54+82.4	Rt.	Curb	6'					6.0		
	55+39.5 to 55+69.6	Lt.	Panel Replacement	12'x30'	40.0						
	55+39.5 to 55+69.6	Lt.	Curb	30'					30.0		
	55+66.5 to 55+72.5	Rt.	Conc. Patch	6'x24'			16.0				
	56+29.5 to 56+59.7	Lt.	Panel Replacement	12'x30'	40.0						
	56+29.5 to 56+59.7	Lt.	Curb	30'					30.0		
	56+56.6 to 56+62.6	Rt.	Conc. Patch	6'x24'			16.0				
	56+56.6 to 56+62.6	Rt.	Curb	6'					6.0		
	56+86.6 to 56+92.6	Lt.	Conc. Patch	6'x12'			8.0				
	56+86.6 to 56+89.7	Lt.	Conc. Patch	3'x12'			4.0				
	56+86.6 to 56+89.7	Lt.	Curb	3'					3.0		
	56+86.6 to 56+92.3	Rt.	Corner Patch	6'x7'			4.7				
	56+89.7 to 57+19.7	Lt.	Panel Replacement	12'x30'	40.0						
	56+89.7 to 57+19.7	Lt.	Curb	30'					30.0		
	57+16.6 to 57+22.6	Lt. & Rt.	Conc. Patch	6'x36'			24.0				
	57+16.6 to 57+22.6	Rt.	Curb	6'					6.0		
	57+49.6 to 57+90.0	Lt.	Conc. Patch	3'x40'			13.3				
	58+82.3 to 58+88.0	C/L	Corner Patch	6'x7'			4.7				
	59+12.3 to 59+18.3	Rt.	Conc. Patch	6'x12'			8.0				
	59+12.3 to 59+18.3	Rt.	Curb	6'					6.0		
Sheet Totals					160.0	0.0	146.7	0.0	153.0	0.0	

12	59+72.2 to 59+78.2	Rt.	Conc. Patch	6'x24'			16.0				
	59+72.2 to 59+78.2	Rt.	Curb	6'					6.0		
	60+02.3 to 60+08.3	Rt.	Conc. Patch	6'x22'			14.7				
	60+35.2 to 61+36.5	Lt.	Conc. Patch	3'x101'			33.7				
	60+62.4 to 60+68.4	Rt.	Conc. Patch	6'x24'			16.0				
	60+62.4 to 60+68.4	Rt.	Curb	6'					6.0		
	60+92.4 to 60+98.4	Rt.	Conc. Patch	6'x24'			16.0				
	60+92.4 to 60+98.4	Rt.	Curb	6'					6.0		
	61+22.6 to 61+28.6	Rt.	Conc. Patch	6'x12'			8.0				
	61+22.6 to 61+28.6	Rt.	Curb	6'					6.0		
	Sheet Totals					0.0	0.0	104.4	0.0	24.0	0.0

Project Total					1,415.4	90.5	1,098.2	954.3	1,062.5	191.5	
---------------	--	--	--	--	---------	------	---------	-------	---------	-------	--



STREET REHABILITATION FOR
17TH STREET BETWEEN HILLSIDE & OLIVER
 WICHITA, KS

©2017
 MKEC Engineering
 All Rights Reserved
 www.mkec.com
 These drawings and their contents, including, but not limited to, all concepts, designs, & ideas are the exclusive property of MKEC Engineering (MKEC), and may not be used or reproduced in any way without the express consent of MKEC.

PAVEMENT REPAIR SCHEDULE		
PROJECT NO.	472-85215	
DATE	5/3/2017	
SCALE	NTS	
DESIGNED	DRAWN	CHECKED
JRA	BKS	BLB
NO.	REVISION	DATE
SHEET NO.		
14 OF 54		