



EAGLE CT.

Eagle Ct. CY Excavation (unadjusted)			
Station	Area	Volume	Cumulative Volume
-0+50.00	0.00	0.00	0.00
-0+35.00	8.70	2.42	2.42
-0+15.00	27.74	13.50	15.91
-0+00.00	30.43	16.16	32.07
0+24.99	22.20	24.36	56.43
0+50.00	12.96	16.28	72.71
1+00.00	12.96	24.01	96.71
1+31.32	12.97	15.04	111.75

Eagle Ct. CY Loose Fill (unadjusted)			
Station	Area	Volume	Cumulative Volume
-0+50.00	0.00	0.00	0.00
-0+35.00	23.13	6.43	6.43
-0+15.00	11.61	12.87	19.30
-0+00.00	10.84	6.24	25.53
0+24.99	13.74	11.38	36.91
0+50.00	10.87	11.40	48.30
1+00.00	10.85	20.11	68.42
1+31.32	10.85	12.59	81.00

