






Note: Reinforcement placed on bar supports as recommended by C.R.S.I. Manual of Standard Practices.




Note: Reinforcement not required when h is 1'-0" or less. Special Sidewalk shall be paid as "Concrete Sidewalk (Special)"




SIDEWALK CURB DETAILS

Seneca:
Sta. 24+14.2 to Sta. 24+44.7, Rt.
Sta. 24+24.8 to Sta. 24+46.4, Lt.
Sta. 25+25.1 to Sta. 25+60.0, Rt.
Sta. 25+25.5 to Sta. 25+60.0, Lt.
Sta. 27+69.0 to Sta. 27+99.4, Rt.
Sta. 27+80.0 to Sta. 27+99.8, Lt.
Sta. 35+53.0 to Sta. 33+50.0, Rt.
Sta. 39+78.4 to Sta. 40+08.8, Rt.
Sta. 40+78.8 to Sta. 41+07.3, Rt.
Sta. 42+33.3 to Sta. 42+43.0, Lt.
Sta. 42+47.2 to Sta. 42+62.0, Lt.
Sta. 42+95.7 to Sta. 43+10.0, Lt.
Sta. 44+07.1 to Sta. 44+66.7, Lt.
Sta. 44+96.7 to Sta. 45+52.9, Lt.
Sta. 46+31.1 to Sta. 47+10.0, Lt.
Sta. 46+32.9 to Sta. 46+58.1, Rt.
Sta. 47+95.9 to Sta. 48+20.0, Lt.
Sta. 48+90.0 to Sta. 49+31.0, Lt.
Sta. 48+90.0 to Sta. 49+59.1, Rt.
Sta. 50+32.7 to Sta. 50+95.0, Lt.



TYPICAL 8" REINFORCED CONCRETE ALLEY ENTRANCE DETAIL





SIDEWALK CROSS SLOPE TRANSITION

(Seneca Sta. 52+98, Rt.)

* Slope as required to match door entrance.

Warp Sidewalk to match slopes.

At other locations which require a slope greater than 1/2"/ft., use similar transition methods.




A - 2" PVC or Copper (to be extended completely through vault to ensure proper alignment)
B - 2" F PVC to M Iron or 2" F Copper to M Iron**
C - 2" Bronze IPT Gate Valve, Wheel Operated**
D - 2" x 4" or 2" x 6" Brass Nipple**
E - Lok-Pak Meter Couplings**
F - 2" Meter**

* = Contractor Installed
** = Installed By Wichita Water & Sewer

2" DOMESTIC SERVICE

Notes For All Services - 2" thru 12":

- When the standard vault dimensions are not applicable, such as when additional space is required for special pipe, fittings, additional meters, etc., the design engineer shall design a vault with the required dimensions for Water & Sewer Dept. approval and Public Works approval.
- The vault shall be poured concrete, cement blocks (voids to be completely filled with 2500 P.S.I. concrete), or approved precast structure (such as Clutter Inc. vaults approved 8/1/2000). The intent of these details shall not be limited by drawings or standards of precast structures.
- Vault location to be determined by Wichita Water & Sewer prior to construction and approved by Department's field supervisor prior to installation. A final inspection will be required for acceptance. Vault location standards include but not limited to: not to be located where subjected to vehicular loads, not to be located in any right-of-way or utility easement, and must be located on the property being served.
- The manhole ring and lid shall be Neenah R-6034 Frame with Type "C" Solid Lid and Drop Down Handle or US Foundry APS-30x30 (Aluminum). Where applicable the standard 10" Wichita Water & Sewer pattern meter reading lid and ring shall be located directly above water meter register. All meter registers shall have an approved lid directly vertical above. All joints of concrete to concrete or metal to concrete in the construction of the vault shall have an approved water tight mastic joint seal.
- Any fittings or appurtenances required to achieve proper elevation of pipe through the vault shall be provided by the contractor and appropriately noted on as-builts submitted by the inspecting engineer. Such fittings shall be a minimum of 2' from the exterior wall of vault.
- For all services larger than 2" the contractor shall provide an outlet flange connection as shown 12-inches from the inside wall. Inlet and outlet wall sleeves shall be provided and installed by the contractor and shall be in alignment with one another. The inlet and outlet pipe shall be ductile iron pipe, cement lined, Class 150 per Standard Specifications and shall be continuous through vault wall and joint no less than two(2) feet from the exterior wall of vault. Flanges of inlet and outlet pipes shall be in proper alignment and bolt pattern shall be rotated in such a way that valves and other fittings shall be in their proper vertical alignment when installed.
- For all services 4" and larger the contractor shall install a mega lug, restrained joint, or approved equal on the exterior walls of the vault, which shall be manufactured of ductile iron conforming to ASTM A 536-80, heat treated to a minimum hardness of 370 BHN and have a working pressure of at least 250 P.S.I. For all services smaller than 4" the contractor shall install an approved vault clamp on the exterior walls of the vault.
- All valves, meters, assemblies, and fittings shall be provided with sufficient concrete or other approved supports to the vault floor.
- The "Confined Space Warning" sign shall be fastened to the top of all vaults. If necessary for landscaping or site considerations, the sign may be fastened to the vault lid if it does not impede access to the handle. Acceptable materials: Aluminum 73415HH, Plastic 73439HH, or S.A. Vinyl 73463HH.
- All meters shall have an electronic read register compatible with the current City of Wichita meter reading system. All detector meters shall be an 5/8 cubic foot Badger meter with ERT register or approved equal. Gallon meters shall not be accepted.



SENECA STREET
PROJECT NAME

MISC. DETAILS
SHEET TITLE

MID-KANSAS ENGINEERING
CONSULTANTS, INC.
411 N. WEBB ROAD
WICHITA, KS. 67206
316-684-9600

DCH

DESIGN BY:

WNJ

DRAWN BY:

DCH

CHECKED BY:

OCT. 2001

DATE

MISCDET

JOB NO.

32 / 87

SHEET / OF