

FHWA REGION NO.	STATE	PROJECT NUMBER	FISCAL YEAR	SHEET NUMBER	TOTAL SHEETS
7	KS	87N-0080-01	1997	75	162

CONCRETE PAVEMENT (160 mm) (AE) (PLAIN)

STATION	ROADWAY	SIDE	WIDTH (M)	160 mm CONC. PAVT. (PL.) (SQ. METERS)	Edge Curb (AE) 150 mm (LIN. METERS)	REMARKS
0+075.393	Meridian	Rt.	3.000	27.364	11.960	Full Radius
0+081.508	Meridian	Lt.	3.000	27.362	11.544	Full Radius
0+091.179	Meridian	Rt.	3.000	28.322	11.298	Full Radius
0+096.719	Meridian	Lt.	6.431	58.746	11.298	Full Radius
0+113.492	Meridian	Lt.	3.000	30.992	11.298	Full Radius
0+114.788	Meridian	Rt.	3.940	37.208	11.298	Full Radius
0+132.356	Meridian	Rt.	3.000	29.285	11.298	Full Radius
0+145.528	Meridian	Lt.	3.000	27.359	11.298	Full Radius
0+150.109	Meridian	Rt.	5.961	46.153	11.298	Full Radius
0+162.664	Meridian	Lt.	6.149	50.113	11.298	Full Radius
0+164.995	Meridian	Rt.	6.987	52.612	11.298	Full Radius
0+221.687	Meridian	Rt.	3.000	27.361	11.298	Full Radius
0+237.642	Meridian	Rt.	3.000	27.361	11.298	Full Radius
0+252.173	Meridian	Rt.	3.000	27.361	11.298	Full Radius
0+269.109	Meridian	Rt.	3.000	27.361	11.298	Full Radius
0+292.647	Meridian	Rt.	3.000	25.972	8.644	Full Radius
0+298.228	Meridian	Rt.	3.651	29.946	8.530	Full Radius
0+461.619	Meridian	Lt.	3.287	31.628	11.298	Full Radius
0+476.151	Meridian	Lt.	3.000	38.117	11.298	Full Radius
0+476.351	Meridian	Rt.	6.650	57.879	11.298	Full Radius
0+491.179	Meridian	Lt.	3.386	40.569	11.298	Full Radius
0+494.113	Meridian	Rt.	3.000	32.195	11.298	Full Radius
0+504.974	Meridian	Lt.	3.000	38.459	11.298	Full Radius
0+520.232	Meridian	Rt.	3.000	31.529	11.298	Full Radius
0+530.460	Meridian	Lt.	3.059	31.569	11.298	Full Radius
0+535.143	Meridian	Rt.	3.335	29.486	11.298	Full Radius
0+544.087	Meridian	Lt.	3.793	35.363	11.298	Full Radius
0+552.244	Meridian	Rt.	5.750	44.776	11.298	Full Radius
0+559.212	Meridian	Lt.	3.000	36.359	11.298	Full Radius
0+571.677	Meridian	Rt.	3.000	27.361	11.298	Full Radius
0+575.240	Meridian	Lt.	3.861	31.379	6.734	Full Radius
0+580.970	Meridian	Rt.	3.000	25.936	8.918	Full Radius
0+636.198	Meridian	Lt.	3.000	27.359	11.298	Full Radius
0+651.186	Meridian	Lt.	3.471	30.343	11.298	Full Radius
0+667.375	Meridian	Lt.	3.000	27.359	11.298	Full Radius
0+676.993	Meridian	Rt.	3.000	27.361	11.298	Full Radius
0+682.478	Meridian	Lt.	4.589	63.448	11.298	Full Radius
0+697.420	Meridian	Lt.	3.000	47.486	11.298	Full Radius
0+701.097	Meridian	Rt.	4.943	39.664	11.298	Full Radius
0+712.388	Meridian	Lt.	3.000	27.359	11.298	Full Radius
0+715.079	Meridian	Rt.	3.000	27.361	11.298	Full Radius
0+735.719	Meridian	Lt.	3.000	27.359	11.298	Full Radius
0+750.411	Meridian	Lt.	3.017	27.469	11.298	Full Radius
0+764.574	Meridian	Lt.	3.000	27.359	11.298	Full Radius
0+779.791	Meridian	Lt.	3.000	36.671	11.298	Full Radius
0+467.748	Second	Lt.	2.789	19.411	8.803	Full Radius
0+557.395	Second	Rt.	4.209	37.488	13.041	Full Radius
0+557.598	Second	Lt.	3.000	25.216	11.128	Full Radius
0+827.680	Meridian	Lt.	3.000	22.705	6.340	Full Radius
0+847.020	Meridian	Lt.	7.802	31.028		Full Ramp
0+877.228	Meridian	Lt.	3.000	13.610		Full Ramp
0+880.470	Meridian	Rt.	3.011	19.037		Full Ramp
0+901.022	Meridian	Lt.	3.000	11.300		Full Ramp
0+919.929	Meridian	Lt.	4.532	16.118		Full Ramp
0+937.270	Meridian	Lt.	3.523	15.162		Full Ramp
0+942.308	Meridian	Rt.	3.011	23.984		Full Ramp
0+951.855	Meridian	Lt.	3.000	24.314		Full Ramp
0+956.943	Meridian	Rt.	3.000	18.344		Full Ramp
0+972.364	Meridian	Rt.	3.000	32.201		Full Ramp
0+979.983	Meridian	Lt.	6.710	58.819		Full Ramp
0+998.230	Meridian	Rt.	3.000	30.215		Full Ramp
1+057.588	Meridian	Lt.	3.000	27.377		Full Ramp
1+066.233	Meridian	Rt.	3.225	20.903		Full Ramp
1+070.001	Meridian	Lt.	3.000	26.510		Full Ramp
1+103.473	Meridian	Lt.	3.000	29.378		Full Ramp
1+103.860	Meridian	Rt.	3.000	29.378		Full Ramp
1+120.204	Meridian	Rt.	3.000	11.307		Full Ramp
1+130.945	Meridian	Lt.	3.000	14.582		Full Ramp
1+146.184	Meridian	Lt.	3.000	20.988		Full Ramp
1+163.290	Meridian	Lt.	6.464	35.890		Full Ramp
1+171.275	Meridian	Rt.	5.112	20.712		Full Ramp
1+219.313	Meridian	Lt.	4.272	50.306		Full Ramp
1+258.908	Meridian	Lt.	3.000	16.394		Full Ramp
1+270.514	Meridian	Rt.	4.167	23.764		Full Ramp
1+271.716	Meridian	Rt.	3.000	20.669		Full Ramp
1+277.749	Meridian	Lt.	4.211	23.767		Full Ramp
1+291.515	Meridian	Rt.	5.137	33.427		Full Ramp
1+298.533	Meridian	Lt.	3.000	20.300		Full Ramp
1+305.233	Meridian	Lt.	3.419	22.872		Full Ramp
1+309.325	Meridian	Rt.	7.008	44.896		Full Ramp
1+318.429	Meridian	Lt.	3.000	20.300		Full Ramp
1+326.568	Meridian	Rt.	4.941	32.150		Full Ramp
1+339.633	Meridian	Lt.	3.000	20.382		Full Ramp
1+363.052	Meridian	Lt.	3.000	11.300		Full Ramp
1+374.561	Meridian	Rt.	3.000	33.689		Full Ramp
1+438.027	Meridian	Lt.	15.483	96.482	12.516	Full Radius
1+454.623	Meridian	Rt.	3.925	42.042		Full Ramp
TOTALS				2724.729	548.780	

REMOVAL OF EXISTING STRUCTURES (FOR INFORMATION ONLY)

STATION	ROADWAY	SIDE	ITEM
0+076.000	Meridian	Lt.	Sign
0+104.600	Meridian	Rt.	Sprinkler Head
0+109.100	Meridian	Rt.	Sprinkler Head
0+116.800	Meridian	Rt.	Sprinkler Heads (4)
0+198.000	Meridian	Rt.	Sign
0+208.400	Meridian	Lt.	Sign
0+230.751	Meridian	Lt.	Sign
0+243.600	Meridian	Lt.	Sign
0+328.600	Meridian	Lt.	Signs (2)
0+335.200	Meridian	Rt.	Sign
0+348.200	Meridian	Lt.	Sign
0+351.600	Meridian	Rt.	Sign
0+394.500	Meridian	Lt.	Sign
0+399.300	Meridian	Rt.	Sign
0+487.700	Douglas	Lt.	Sign
0+522.400	Douglas	Lt.	Sign
0+529.000	Douglas	Rt.	Sign
0+409.100	Meridian	Rt.	Sign
0+426.300	Meridian	Rt.	Sign
0+439.100	Meridian	Rt.	Sign
0+518.300	Meridian	Lt.	Sign
0+578.400	Meridian	Lt.	Sign
0+624.900	Meridian	Lt.	Sign
0+647.900 to 0+652.300	Meridian	Rt.	Hand Rail
0+663.100	Meridian	Rt.	Sign
0+724.200	Meridian	Lt.	Sign
0+725.600	Meridian	Lt.	Sign
0+754.400	Meridian	Lt.	Sign
0+794.800	Meridian	Lt.	Sign
0+798.100	Meridian	Rt.	Sign
0+811.300	Meridian	Rt.	Sign
0+821.000	Meridian	Rt.	Sign
0+824.800	Meridian	Lt.	Sign
0+454.000	Second	Lt.	Sign
0+460.200	Second	Rt.	Sign
0+480.600	Second	Rt.	Sign
0+514.800	Second	Lt.	Bench
0+523.200	Second	Lt.	Sign
0+533.700	Second	Lt.	Sign
0+555.300	Second	Lt.	Sign
0+850.300	Meridian	Rt.	Sign
0+873.200	Meridian	Lt.	Sign
0+884.200	Meridian	Rt.	Sign
0+907.800	Meridian	Rt.	Sign
0+919.900	Meridian	Rt.	Sign
0+934.200	Meridian	Lt.	Sign
0+993.600	Meridian	Lt.	Sign
1+001.300	Meridian	Rt.	Sign
1+012.100	Meridian	Lt.	Sign
1+012.800	Meridian	Lt.	Sign
1+029.600	Meridian	Rt.	Sign
0+480.100 to 0+491.500	Third	Lt.	Fence
1+024.800 to 1+040.900	Third	Lt.	Fence
1+041.300	Meridian	Lt.	Sign
1+098.200	Meridian	Lt.	Sign
1+119.800	Meridian	Rt.	Sign
1+127.500	Meridian	Rt.	Sign
1+129.200	Meridian	Lt.	Inlet-Plug Pipe (NE & W)
1+129.254	Meridian	Lt.	Inlet-Plug Pipe (E)
1+129.400	Meridian	Rt.	SWS Manhole-Plug Pipe (E & W)
1+131.000	Meridian	Rt.	Sign
1+140.800	Meridian	Rt.	Inlet-Plug Pipe (N & SW)
1+141.000	Meridian	Rt.	Inlet-Plug Pipe (NW & S)
1+145.400	Meridian	Rt.	Sign
1+128.000 to 1+130.300	Meridian	Rt.	Inlet-Plug Pipe (SW)
1+155.500	Meridian	Rt.	Posts (3)
1+189.700	Meridian	Lt.	Sign
1+190.300	Meridian	Lt.	Sign
1+191.700 to 1+194.600	Meridian	Rt.	Gourd Rail
1+193.100	Meridian	Rt.	RR Signal
1+208.200 to 1+211.100	Meridian	Lt.	Gourd Rail
1+209.600	Meridian	Lt.	RR Signal
1+223.600	Meridian	Rt.	Sign
1+225.500	Meridian	Lt.	Sign
1+231.600	Meridian	Rt.	Sign
1+237.300	Meridian	Rt.	Inlet-Plug Pipe (NE)
1+242.200	Meridian	Lt.	Inlet-Plug Pipe (SW & NW)
1+129.54 to 1+242.240	Meridian	Lt.	SWS MH-Plug Pipe (W, SE & NE)
1+242.240 to 1+348.721	Meridian	Lt.	113.0 m x 600 mm Pipe
1+242.500	Meridian	Lt.	106.5 m x 600 mm Pipe
1+242.500	Meridian	Lt.	Inlet-Plug Pipe (E)
1+247.300	Meridian	Rt.	Inlet-Plug Pipe (SW & NW)
1+250.000	Meridian	Rt.	Sign
1+253.000	Meridian	Rt.	Sign
1+262.800	Meridian	Lt.	Inlet-Plug Pipe (SE)
1+283.100	Meridian	Lt.	Sign
1+316.100	Meridian	Rt.	Sign
1+339.000	Meridian	Rt.	Sign
1+345.000	Meridian	Rt.	Inlet-Plug Pipe (NE)
1+348.700	Meridian	Lt.	Inlet-Plug Pipe (SW & NW)
1+350.000	Meridian	Lt.	SWS MH-Plug Pipe (NW, SE & NE)
1+354.300	Meridian	Rt.	Inlet-Plug Pipe (SE)
1+360.000	Meridian	Rt.	Inlet-Plug Pipe (SW & NW)
1+419.000	Meridian	Lt.	Inlet-Remove 7.0 m x 300 mm Pipe (E)
1+420.100	Meridian	Lt.	SWS MH-Remove 8.8 m x 300 mm Pipe (S)
1+411.500	Meridian	Lt.	SWS MH
1+411.800	Meridian	Rt.	Inlet-Remove 9.3 m x 300 mm Pipe (NE)
1+417.500	Meridian	Rt.	Inlet-Plug Pipe (N)
1+420.000	Meridian	Rt.	SWS MH to Remain-Plug Pipe (N & S)
1+427.700	Meridian	Rt.	Inlet-Remove 7.6 m x 300 mm Pipe (S)

REMOVAL OF EXISTING STRUCTURES (cont.) (FOR INFORMATION ONLY)

STATION	ROADWAY	SIDE	ITEM
1+331.100	Meridian	Lt.	Sign
1+355.200	Meridian	Rt.	Sign
1+355.800	Meridian	Rt.	Sign
1+356.300	Meridian	Rt.	Sign
1+357.500 to 1+369.800	Meridian	Rt.	Fence
1+366.800	Meridian	Rt.	Sign
1+415.000	Meridian	Rt.	Sign
1+411.800	Meridian	Rt.	Inlet
1+411.500	Meridian	Lt.	SWS MH
1+409.400	Meridian	Lt.	Inlet
1+419.300	Meridian	Lt.	Inlet
1+420.100	Meridian	Lt.	SWS MH
1+417.500	Meridian	Rt.	Inlet
1+427.600	Meridian	Rt.	Inlet
1+429.700	Meridian	Rt.	Sign
1+437.100	Meridian	Rt.	Sign
1+460.100	Meridian	Rt.	Sign
0+009.000	McLean	Rt.	Sign
0+019.000	McLean	Lt.	Sign
0+026.500	McLean	Lt.	Sign
0+028.100	McLean	Lt.	Sign

MONUMENT BOX

STATION	ROADWAY	LOCATION	MONUMENT BOX EACH	REMARKS (COORDINATE PT. NO.)
0+490.856	First	First & Meridian	1	(62)
0+804.739	Meridian		1	(28)
0+500.000	Second			
0+508.144	Martha	Martha & Meridian	1	(33)
1+018.153	Meridian		1	(36)
0+500.000	Third			
0+509.150	Third	Third & Meridian	1	(37)
0+509.144	Caroline	Caroline & Meridian	1	(47)
1+223.843	Meridian		1	(43)
0+509.144	St. Louis	St. Louis & Meridian	1	(44)
0+509.144	Vermont	Vermont & Meridian	1	(50)
1+414.340	Meridian		1	(52)
TOTALS			10	

PROTECTION CURB (150 mm) (SPECIAL) (A) (AE)