FHWA REGION NO.	STATE	PROJECT NUMBER	FISCAL YEAR	SHEET NUMBER	TOTAL SHEETS
7	KANSAS	87N-0080-01	1997	89	162

BY	DATE
REFERENCES NOTED	
REFERENCES CHECKED	

Existing Underground Interconnect Cable. Abandon in Place.

Remove Interconnect Cable and Conduit from Power Pole.

Remove Existing Overhead Interconnect Cable.

Interconnect in Conduit on Power Pole

Sta. 0+317.90, 12 78 Lt. Install Junction Box.

MERIDIAN

Project Baseline

FIRST

DOUGLAS

SEE SHEETS 106, 108 FOR INTERSECTION TRAFFIC CONTROL INFORMATION.

Sta. 0+443.39, 6 69 Lt. Install Junction Box.

Sta. 0+493.33, 6 69 Lt. Install Junction Box.

Sta. 0+541.73, 6 69 Lt. Install Junction Box.

Sta. 0+593.39, 6 69 Lt. Install Junction Box.

6PR Comm. Cable (#19 AWG) in 50 mm RGC. Typical this sheet.

Remove Existing Overhead Interconnect Cable.

SRB

SCALE

10 0 10 20

PLAN: Lat. & Long. (meters)

SIGNAL INTERCONNECTION PLAN
MERIDIAN - STATION 0+300 TO STATION 0+600

SRB 924 NORTH MAIN WICHITA, KANSAS 67203 316-264-8008 FAX 264-4621 http://www.feist.com/~srb E-Mail: srb@feist.com

SAVOY, RUGGLES & BOHM, P.A.
ENGINEERING & SURVEYING

PROJECT NUMBER 472-76-245-82740-000-000-001

DRAWN	DESIGN	REVIEW	DATE	UTILITY	SRB JOB
KWL	T.C.R.	JCR	Oct. 2, 1998		539T

REVISED

SHT. NO. (Interconnect) 89 / 162