FHWA REG NO.	STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
7	KANSAS	87 N-0199-01	2002	132	158

FED. AID NO. CMQ-N019(901)

For specific pavement marking details and dimensions see plan sheets.

ALL TOTALS REFLECT ACTUAL QUANTITY OF PAVEMENT MARKING MATERIALS REQUIRED.

SUMMARY OF PAVEMENT MARKINGS

LOCATION	100 mm Solid WHITE Edge Line	150 mm Broken WHITE Lane Line	150 mm Dotted WHITE Extension Line	150 mm Solid WHITE Lane Line	450 mm Solid WHITE Diagonal Line	300 mm Solid WHITE Diagonal Line	600 mm Solid WHITE Type II Crosswalk Line	600 mm Solid WHITE Stop Line	200 mm Solid WHITE Gore Line	100 mm Solid YELLOW Edge Line	100 mm Solid YELLOW Double Line	300 mm Solid YELLOW Diagonal Line	100 mm Broken WHITE Line	100 mm Solid YELLOW Line	100 mm Broken YELLOW Line	450 mm Solid YELLOW Diagonal Line
Rock Road																
Sta. 0+435 to Sta. 0+750		1260 m		133 m						766 m						
Sta. 0+750 to Sta. 1+186		1592 m		283 m						800 m						
21st Street																
Sta. 49+422 to Sta. 49+700		834 m		69 m		72 m				440 m	99 m	15 m				
Sta. 49+700 to Sta. 50+100		1056 m	80 m	520 m						612 m						
Sta. 50+100 to Sta. 50+356	80 m	783 m		237 m						282 m	90 m					
TOTALS																

SUMMARY OF WORD & SYMBOL MARKINGS

LOCATION	↱	↰↑	↑	↱	↰		R⃠R	STOP	ONLY	X-ING	SCHOOL			
Rock Road														
21st Street														
Sta. 49+700 to Sta. 50+100				2										
Sta. 50+100 to Sta. 50+400				1										
TOTALS														

SUMMARY OF PAVEMENT MARKINGS

ITEM	TOTAL	UNITS
100 mm Solid WHITE Edge Line	80	m
150 mm Broken WHITE Lane Line	5525	m
150 mm Solid WHITE Lane Line	1242	m
300 mm Solid WHITE Diagonal Line	72	m
100 mm Solid YELLOW Edge Line	2900	m
100 mm Solid YELLOW Double Line	189	m
300 mm Solid YELLOW Diagonal Line	15	m
150 mm Dotted WHITE Extension Line	80	m
Pavement Marking Symbol (Preformed Thermoplastic)(WHITE)(Right Arrow)	3	ea

NOTE:

WORDS & SYMBOLS SHALL CONFORM TO THE LATEST EDITION OF "STANDARD ALPHABETS FOR HIGHWAY SIGNS AND PAVEMENT MARKINGS" PRINTED BY THE U.S. DEPARTMENT OF TRANSPORTATION, FEDERAL HIGHWAY ADMINISTRATION.

ROCK ROAD & N 21st STREET

SUMMARY AND RECAPITULATION OF PAVEMENT MARKING QUANTITIES

HWS Consulting Group Inc
Omaha Office
10844 Old Mill Rd., Ste 1
Omaha, NE 68154
Phone: (402) 333-5792
Fax: (402) 333-2248

Designed By:	BWE	Checked By:	RJK	
Drawn By:	HS , TS	Date:	4/10/02	Job No. 55-70-2003

F:/proj/55702003/21st/dwg/plan/pavementmarkingsummarysheet.dwg