

JEWELL CY Excavation (unadjusted)				JEWELL CY Compacted Fill (unadjusted)			
Station	Area	Volume	Total	Station	Area	Volume	Total
0+95.38	15.59	0.0	0.0	0+95.38	22.33	0.0	0.0
1+50	19.47	35.1	35.1	1+50	23.73	47.0	47.0
2+00	11.00	28.2	63.3	2+00	28.76	48.6	95.6
2+58.43	7.41	19.9	83.2	2+58.43	23.46	56.5	152.1
2+90.87	16.93	14.6	97.9	2+90.87	14.17	22.6	174.7
3+26.49	32.59	32.7	130.5	3+26.49	19.40	22.1	196.9
3+50	14.08	20.3	150.9	3+50	19.79	17.1	213.9
4+00	11.80	24.0	174.8	4+00	10.61	28.2	242.1
4+50	8.43	18.7	193.5	4+50	1.66	11.4	253.4
5+00	14.77	21.5	215.0	5+00	2.83	4.2	257.6
5+53.27	55.52	67.2	282.2	5+53.27	0.00	3.2	260.8
5+83.42	80.98	75.6	357.8	5+83.42	0.00	0.0	260.8
6+17.46	43.06	78.2	436.0	6+17.46	0.00	0.0	260.8
6+58.27	26.98	52.9	488.9	6+58.27	0.00	0.0	260.8

JEWELL CY Loose Fill (unadjusted)			
Station	Area	Volume	Total
0+95.38	4.24	0.0	0.0
1+50	6.26	10.8	10.8
2+00	3.73	9.3	20.1
2+58.43	4.61	9.0	29.1
2+90.87	1.23	3.5	32.6
3+26.49	5.07	4.2	36.7
3+50	4.54	4.2	40.9
4+00	7.63	11.3	52.2
4+50	6.63	13.2	65.4
5+00	13.18	18.3	83.7
5+53.27	7.30	21.5	105.2
5+83.42	0.00	4.4	109.6
6+17.46	0.11	0.1	109.7
6+58.27	4.83	3.7	113.4

