

PROJECT EARTH WORK TOTALS

LAKEWAY CY Excavation (unadjusted)				LAKEWAY CY Loose Fill (unadjusted)			
Station	Area	Volume	Total	Station	Area	Volume	Total
0+00	35.97	0.00	0.00	0+00	4.49	0.00	0.00
0+50	40.90	71.17	71.17	0+50	5.33	9.09	9.09
1+00	39.49	74.43	145.60	1+00	1.53	6.35	15.44
1+58.62	33.88	79.65	225.25	1+58.62	7.19	9.46	24.90
1+92.62	40.98	47.13	272.39	1+92.62	4.73	7.50	32.40
2+26.51	13.04	33.90	306.29	2+26.51	12.05	10.53	42.93
2+50	14.03	11.79	318.07	2+50	12.17	9.76	52.69
3+00	19.51	31.09	349.16	3+00	12.22	21.10	73.79
3+48.92	22.99	38.40	387.56	3+48.92	12.76	22.57	96.35
3+76.33	31.37	27.84	415.39	3+76.33	3.27	7.96	104.31
4+03.75	17.89	25.03	440.43	4+03.75	19.75	11.87	116.18
4+50	8.39	22.30	462.73	4+50	11.71	26.97	143.15
4+71.31	28.45	14.56	477.29	4+71.31	4.10	6.14	149.29

LAKEWAY CT CY Excavation (unadjusted)				LAKEWAY CT CY Loose Fill (unadjusted)			
Station	Area	Volume	Total	Station	Area	Volume	Total
0+37	52.58	0.00	0.00	0+37	0.20	0.00	0.00
0+50	77.92	31.42	31.42	0+50	0.00	0.05	0.05
1+00	12.03	83.28	114.70	1+00	13.31	12.32	12.37
1+54	16.08	28.11	142.81	1+54	22.16	35.47	47.84

LAKEWAY CT HAMMERHEAD CY Excavation (unadjusted)				LAKEWAY CT HAMMERHEAD CY Loose Fill (unadjusted)			
Station	Area	Volume	Total	Station	Area	Volume	Total
-0+14.81	23.35	0.00	0.00	-0+14.81	5.73	0.00	0.00
0+09.20	12.97	16.14	16.14	0+09.20	18.37	10.71	10.71
0+43.19	17.98	19.48	35.63	0+43.19	11.92	19.07	29.78
0+77.18	20.61	24.30	59.92	0+77.18	14.33	16.52	46.30

VENICE CT CY Excavation (unadjusted)				VENICE CT CY Loose Fill (unadjusted)			
Station	Area	Volume	Total	Station	Area	Volume	Total
1+33.88	14.23	0.00	0.00	1+33.88	26.78	0.00	0.00
1+50	15.86	9.02	9.02	1+50	14.56	12.23	12.23
2+00	12.16	26.76	35.77	2+00	5.83	17.82	30.05
2+50	10.22	20.73	56.50	2+50	15.43	19.69	49.74
2+83.99	11.65	13.77	70.27	2+83.99	16.06	19.83	69.57

VENICE CT Hammerhead CY Excavation (unadjusted)				VENICE CT Hammerhead CY Loose Fill (unadjusted)			
Station	Area	Volume	Total	Station	Area	Volume	Total
-0+15.45	0.00	0.00	0.00	-0+15.45	0.00	0.00	0.00
-0+15	0.04	0.00	0.00	-0+15	6.78	0.06	0.06
0+00	0.31	0.10	0.10	0+00	7.30	3.91	3.97
0+04	24.16	1.81	1.91	0+04	5.27	0.93	4.90
0+26	19.07	17.61	19.52	0+26	11.82	6.96	11.86
0+60	12.92	20.14	39.66	0+60	10.38	13.98	25.84
0+94	13.92	16.90	56.56	0+94	15.10	16.04	41.88
1+16	16.79	12.51	69.06	1+16	17.37	13.23	55.11
1+20	0.00	1.24	70.31	1+20	27.16	3.30	58.41
1+35	1.02	0.28	70.59	1+35	6.43	9.33	67.74
1+35.61	0.00	0.01	70.60	1+35.61	0.00	0.07	67.81

