

EARTHWORK						
Location	EXCAVATION ITEMS				Fill, Compacted (95% Density) (cy) #	Remarks
	Pavement and/or Curb Removed (sy)	Sidewalk, Drive, &/or Pkg Lot Removed* (sy)	Excavation (cy)	VMF		
	234.5	597.2	914.9		0.0	
				0.80		
Totals	234.5	597.2	914.9		0.0	

* Includes all sidewalk, ramps, driveways, bus pads and all pavement on private property.
 ≠ Fill is incidental and subsidiary to excavation

CONCRETE PAVEMENT AND BASE				
Location	Side	Concrete Pavement 8" (NRDJ) (sy)	Crushed Rock Base 7", Reinforced (sy)	Remarks
Sta. 46+93.62 to Sta. 55+37.58	Rt.	813.8	1,089.9	
Totals		813.8	1,089.9	

REINFORCED CONCRETE VALLEY GUTTER						
Location	Side	Concrete Pavement (VG) 8" (Reinf.) (sy)	Crushed Rock Base 7", Reinforced (sy)	Concrete Curb, Mono Edge (6" & 1-1/2") (lf)	Concrete Ramp Nose Section (ea)	Remarks
Sta. 50+00.00	34.44' Rt.	244.1	238.0	94.40	1	
Totals		244.1	238.0	94.40	1	

SIDEWALK CONSTRUCTION							
Location	Side	Concrete Sidewalk 4" (sf)	Future Concrete Sidewalk work (sf)	Sidewalk Thickening (lf)	Wheelchair Ramp w/ Detectable Warnings (ea)	Future Wheelchair work (ea)	Remarks
Sta. 46+93.62 to Sta. 49+65.00	Rt.	1764.6			1		
Sta. 50+35.00 to Sta. 54+60.36	Rt.	2571.7			1		
Sta. 50+45.36	Lt.		87.9			1	
Sta. 50+45.36	Rt.		49.7			1	
Sta. 52+61.34 to Sta. 54+32.28	Rt.			171.0			
Totals		4336.3	137.6	171.0	2	2	

CONCRETE CURB AND GUTTER			
Location	Side	Concrete C & G, Type 1 (6" & 1-1/2") (lf)	Remarks
Sta. 46+93.62 to Sta. 49+44.53	Rt.	251.2	
Sta. 50+55.53 to Sta. 55+37.58	Rt.	482.1	
Totals		733.3	

SUMMARY OF QUANTITIES - STORM SEWER PIPE AND STRUCTURES							
Line No.	Pipe		Inlets			Misc.	Remarks
	Pipe, SWS, RCP 15" (lf)	Fill, Sand (Flushed & Vibrated) (lf)	Inlet, Curb (Type 1) (L=10', W=3') (ea)	Pipe, SWS, PVC 4" Perforated (lf)	Inlet Hookup (ea)	Pipe Connect to Existing (ea)	
1	14	14	1	10	1	1	
2			1	10	1	1	
Totals	14	14	2	20	2	2	

REMOVAL OF EXISTING PIPES AND STORM STRUCTURES*			
Location	Offset	Item	Remarks
Sta. 48+19.2	26.0' Rt.	Curb Inlet	
Sta. 48+19.2 to Sta. 48+30.7	26.0' Rt.	6.0' of 15" RCP	
Sta. 48+30.7	26.0' Rt.	Curb Inlet	
Sta. 48+30.7	27.3' Rt.	5.6' of 15" RCP	
Sta. 53+53.5	27.3' Rt.	Curb Inlet	
Sta. 53+53.5	27.3' Rt.	11.3' of 15" RCP	

* This list does not necessarily constitute a complete list of items to be removed during construction. The list is provided for information only. Pavement removal is paid for separately. Sign removals are shown in the signing plans. Water meters and appurtenances are listed in the Utility Adjustmet tables on the paving plan sheets.



SENECA STREET IMPROVEMENTS FOR
STEEPLE BAY ADDITION
 WICHITA, KANSAS

©2018
 MKEC Engineering
 All Rights Reserved
 www.mkec.com
 These drawings and their contents, including, but not limited to, all concepts, designs, & ideas are the exclusive property of MKEC Engineering (MKEC), and may not be used or reproduced in any way without the express consent of MKEC.

SUMMARY OF QUANTITIES

PROJECT NO.	472-85451	
DATE	1/02/19	
SCALE	NONE	
DESIGNED	DRAWN	CHECKED
JRA	WNJ	JRA
NO.	REVISION	DATE