

STATION	DIST.	AREA			VOLUME				
		CUT S.F.	L.F. S.F.	C.F. S.F.	M.F. S.F.	CUT C.Y.	FILL C.Y.	C.F. C.Y.	M.F. C.Y.
WESTLAKES PARKWAY ENTRY PHASE 3									
4102.97	47.03	8.4	32.9	0.0	0.0	13.6	57.1	0.0	0.0
4150.00	50.00	7.2	32.7	0.0	0.0	15.5	57.3	0.0	0.0
4200.00	34.08	9.5	29.2	0.0	0.0	13.1	36.4	0.0	0.0
4234.08	15.92	11.3	28.5	0.0	0.0	6.3	17.0	0.0	0.0
4250.00	25.00	10.1	29.0	0.0	0.0	8.8	26.3	0.0	0.0
4275.00	15.50	8.8	27.8	0.0	0.0	4.4	16.4	0.1	0.0
4290.50	30.23	6.5	29.2	0.2	0.0	8.5	27.8	1.3	0.0
4320.73	30.23	8.7	20.5	2.2	0.0	9.3	20.2	3.1	0.0
4350.96	31.03	8.0	15.6	3.3	0.0	12.1	24.2	1.9	0.0
4381.99	18.01	13.1	26.5	0.0	0.0	10.5	16.1	0.0	0.0
4400.00	25.00	18.4	21.7	0.0	0.0	20.5	16.9	0.0	0.0
4425.00	25.00	25.8	14.8	0.0	0.0	28.0	10.4	0.0	0.0
4450.00	25.00	34.7	7.7	0.0		37.3	4.9	0.0	0.0
4475.00	17.95	45.9	2.9	0.0		33.0	1.2	0.0	0.0
4492.95	32.05	53.4	0.7	0.0		72.4	0.4	0.0	0.0
4525.00	25.00	68.6	0.0	0.0	0.0	77.8	0.0	0.0	0.0
4550.00	25.00	99.5	0.0	0.0	0.0	88.2	0.0	0.0	0.0
4575.00	25.00	91.1	0.0	0.0	0.0	75.6	0.0	0.0	0.0
4600.00	25.00	72.1	0.0	0.0	0.0	65.2	0.0	0.0	0.0
4625.00	25.00	68.8	0.0	0.0	0.0	61.5	0.0	0.0	0.0
4650.00	25.00	64.0	0.1	0.0	0.0	57.9	0.6	0.0	0.0
4675.00	25.00	61.0	1.3	0.0	0.0	51.5	1.5	0.0	0.0
4700.00	28.03	50.3	1.9	0.0	0.0	26.1	20.4	1.8	0.0
4728.03	33.78		37.4	3.4	0.0	27.8	28.1	2.1	0.0
4761.81	35.77	44.5	7.5	0.0	0.0	41.3	19.3	0.0	0.0
4797.58	26.16	17.9	21.7	0.0	0.0	13.8	24.3	0.0	0.0
4823.74	23.61	10.5	28.5	0.0	0.0	7.0	18.3	0.0	0.0
4847.35	0.79	5.6	13.4	0.0	0.0	0.5	0.4	0.0	0.0
4848.14	49.52	31.5	15.8	0.0	0.0	29.2	39.2	6.7	0.0
4897.66	12.21	0.3	27.0	7.3	0.0	0.2	13.1	4.0	0.0
4909.87	28.56	0.8	30.8	10.2	0.0	2.4	31.8	10.6	0.0
4938.43	0.01	3.8	29.4	9.9	0.0	0.0	0.0	0.0	0.0
4938.44		3.4	31.6	10.5	0.0				
TOTAL=						919.3	529.6	31.6	0.0

