



BROOK VIEW

Brookview CY Excavation (unadjusted)				Brookview CY Compacted Fill (unadjusted)				Brookview CY Loose Fill (unadjusted)			
Station	Area	Volume	Total	Station	Area	Volume	Total	Station	Area	Volume	Total
0+00	0.00	0.00	0.00	0+00	0.00	0.00	0.00	0+00	0.00	0.00	0.00
0+50	47.17	43.68	43.68	0+50	0.00	0.00	0.00	0+50	0.01	0.01	0.01
0+60	57.27	19.34	63.02	0+60	0.00	0.00	0.00	0+60	3.37	0.63	0.64
0+67.75	47.19	14.99	78.01	0+67.75	0.00	0.00	0.00	0+67.75	15.32	2.68	3.32
1+00	9.06	33.59	111.60	1+00	3.09	1.84	1.84	1+00	24.94	24.04	27.36
1+13.50	4.52	3.39	115.00	1+13.50	9.85	3.24	5.08	1+13.50	27.43	13.09	40.45
1+21.25	3.20	1.11	116.11	1+21.25	15.45	3.63	8.71	1+21.25	14.76	6.06	46.51
1+50	8.48	6.22	122.33	1+50	10.74	13.95	22.66	1+50	17.01	16.92	63.43
1+90.24	1.53	7.35	129.68	1+90.24	13.77	18.34	41.00	1+90.24	28.05	33.99	97.41
2+36	0.00	1.20	130.88	2+36	43.39	49.99	90.98	2+36	27.52	45.27	142.68
2+78.26	0.00	0.00	130.88	2+78.26	26.66	56.12	147.11	2+78.26	36.79	46.06	188.74
3+00	0.00	0.00	130.88	3+00	44.88	29.25	176.36	3+00	41.47	29.93	218.66
3+50	0.00	0.00	130.88	3+50	77.11	115.38	291.74	3+50	57.08	89.57	308.23
4+00	0.00	0.00	130.88	4+00	92.29	157.12	448.85	4+00	58.00	106.56	414.79
4+50	1.70	1.57	132.45	4+50	173.14	245.77	694.63	4+50	90.65	137.64	552.43
5+00	27.90	27.41	159.86	5+00	53.50	209.85	904.47	5+00	38.87	119.93	672.36
5+50	51.10	73.14	233.00	5+50	259.48	289.79	1194.26	5+50	51.16	83.36	755.72
6+00	0.00	47.31	280.31	6+00	77.17	311.71	1505.98	6+00	81.52	122.85	878.56
6+41.51	27.36	21.03	301.34	6+41.51	0.00	59.33	1565.31	6+41.51	11.44	71.47	950.03