COMBINED CURB and GUTTER

Sta. to Sta.		Length (ft)	Side
10+29.83	13+02.81	273.0	Lt
13+62.82	16+36.09	19.8	Lt
16+85.85	19+59.02	273.2	Lt
19+59.02	19+73.17	23.0	Lt
20+03.60	20+18.70	23.4	Lt
20+18.70	22+89.87	271.2	Lt
22+89.87	23+09.48	26.3	Lt
10+29.83	13+02.79	273.0	Rt
13+62.82	16+36.09	273.3	Rt
16+85.85	19+58.54	272.7	Rt
19+58.54	19+73.45	19.6	Rt
20+04.53	20+18.92	20.5	Rt
20+18.92	22+89.67	270.8	Rt
22+89.67	23+08.89	26.3	Rt
	Total	2066.1	

CRUSHED STONE SUBGRADE (5")

Sta. to Sta.		Length (LF)	Width (LF)	Area (SY)
10+29.99	13+02.82	272.83	33.00	1000.4
13+62.82	16+36.13	273.31	33.00	1002.1
16+85.85	19+58.92	273.07	33.00	1001.3
20+18.92	22+89.87	270.95	33.00	993.5
22+89.84	23+11.21			988.3
		Total		4985.6

BID ITEMS

Item	Quantity	UM
Paving Items		
Construction Traffic Control	1	L.S.
Clearing and Site Preparation	1	L.S.
Crushed Stone Subgrade (5 inch)	4986	Sq. Yd.
5" Asphalt Pavement (3" Base)	3150	Sq. Yd.
Combined Curb & Gutter	2066	L.F.
Common Excavation	1827	Cu. Yd.
Seeding (TRWPC)	1	LS
Irrigation Sleeve/Sprinkler System Repairs	1	LS
RCVG Pavement (7")	101	Sq. Yd.
AdJustment of Manholes	4	EA
Manhole (Type B)	1	EA.
8" Sanitary Sewer Pipe	264	L.F.
Flowable Fill	26	L.F.
Sidewalk Ramps	3	EA.
Concrete Pavement (6 inch)(Res. Drive)	85	Sq. Yd.

RCVG PAVEMENT (7")

Sta. to Sta.				Area (SY)
22+89.84	23+11.21			100.8
		Total		100.8

CONCRETE PAVEMENT (6")(RES. DRIVE)

Station	Offset	Area (sy)
14+28.53	Left	24.89
15+10.51	Left	29.91
22+18.24	Left	29.91
	Total	84.71

EARTHWORK

Sta. to Sta.		Common Excavation (CY)	Embankment (CY)	Contractor Furnished Excavation (CY)
10+29.99	13+02.82	463.6	10.0	
13+62.82	16+36.13	331.1	21.0	
16+85.85	19+58.92	349.2	8.3	
20+18.92	23+11.19	344.5	27.7	
	Totals	1490.4	67.0	

5" ASPHALT PAVEMENT

Sta. to Sta.		Length (lf)	Width (lf)	Area (sy)
10+29.99	13+02.82	272.83	26.00	788.2
13+62.82	16+36.13	273.31	26.00	789.6
16+85.85	19+58.92	273.07	26.00	788.9
20+18.92	22+89.87	270.95	26.00	782.7
			Total	3149.4

CITY OF WICHITA

20th STREET
HYDRAULIC TO PIATT

SUMMARY OF QUANTITIES

WICHITA KANSAS

PROJECT NO 125020011

REVISIONS | BY | DATE

TranSystems Corporation
245 North Waco, Suite 420
Wichita, Kansas 67202

DESIGNED:	J.R.L.	DRAWN:	M.P.M.
CHECKED:	B. A. L.	DATE:	2/2004
SCALE:	1" = 20'	SHEET NO.:	14