



Maize Rd SL Excavation (CY)			
STATION	AREA (sq ft)	VOLUME (cu yd)	CUM VOL (cu yd)
95+77.12	13.01	0.00	0.00
96+00.00	13.31	11.15	11.15
96+25.00	12.84	12.11	23.26
96+50.00	12.35	11.66	34.92
96+75.00	12.79	11.64	46.56
97+00.00	13.18	12.03	58.59
97+25.00	12.94	12.09	70.68
97+50.00	12.75	11.89	82.58
97+75.00	12.77	11.82	94.39
98+00.00	12.79	11.84	106.23
98+25.00	12.68	11.79	118.02
98+50.00	12.76	11.77	129.80
98+75.00	12.59	11.73	141.53
99+00.00	12.55	11.64	153.17
99+19.35	12.10	8.83	162.00

Maize Rd SL Loose Fill (CY)			
STATION	AREA (sq ft)	VOLUME (cu yd)	CUM VOL (cu yd)
95+77.12	131.03	0.00	0.00
96+00.00	134.52	112.52	112.52
96+25.00	128.22	121.64	234.16
96+50.00	122.04	115.86	350.02
96+75.00	122.56	113.24	463.26
97+00.00	123.13	113.75	577.01
97+25.00	124.10	114.46	691.47
97+50.00	123.65	114.70	806.17
97+75.00	127.01	116.05	922.22
98+00.00	127.91	118.02	1040.24
98+25.00	130.63	119.70	1159.93
98+50.00	134.91	122.93	1282.87
98+75.00	133.34	124.19	1407.05
99+00.00	130.24	122.03	1529.08
99+19.35	105.89	84.61	1613.69

Maize Rd SL Compacted Fill (CY)			
STATION	AREA (sq ft)	VOLUME (cu yd)	CUM VOL (cu yd)
95+77.12	24.03	0.00	0.00
96+00.00	28.56	22.28	22.28
96+25.00	29.05	26.67	48.96
96+50.00	28.45	26.62	75.58
96+75.00	28.54	26.38	101.96
97+00.00	28.27	26.30	128.26
97+25.00	28.55	26.31	154.57
97+50.00	29.70	26.97	181.53
97+75.00	30.20	27.73	209.27
98+00.00	31.17	28.41	237.68
98+25.00	32.57	29.51	267.19
98+50.00	34.40	31.01	298.20
98+75.00	33.46	31.42	329.61
99+00.00	35.97	32.14	361.76
99+19.35	35.05	25.45	387.20

