



Sta. 107+73.75, 55' Rt. @
Install Three (3) 6" dia. Steel
Pipes under sidewalk.
Length=10' (each)
In=1345.30
Out=1345.20
Grade R/W to drain to Pipes.
Grade from Pipes to top Inlet.
Adjust Sidewalk over pipes as
needed. Pipes are Subsidiary
to "Sidewalk" bid item.

Sta. 108+66.29, 53.00' Rt. Construct
Std. Wheelchair Ramp w/ Detectable Warning
(See Detail - Sheet 26)

Sta. 108+67, 54' Rt. Adjust
Water Valve Boxes (2)
from Elev. = 1346.65
to Elev. = 1346.84

Sta. 109+05.00, 28.00' Rt. Construct
Reinforced Valley Gutter Pavement (8")
(See Plan - Sheet 17)

Sta. 109+42.0, 48.5' Rt.
Gas Valve to Remain &
Be Set Flush w/ Sidewalk
(By Owner)

Sta. 109+42.80, 53.00' Rt. Construct
Std. Wheelchair Ramp w/ Detectable Warning
(See Detail - Sheet 26)

Sta. 110+73
Remove 17 L.F. of
Exist. 36" RCP.
Refer to Sht. 33
for Pipe Opening
Repair Detail.

Sta. 111+06
Remove 15 L.F. of
Exist. 24" RCP.
Refer to Sht. 33
for Pipe Opening
Repair Detail.

Sta. 111+20
Remove 5 S.Y. of
Exist. Rip-rap. May
be re-used

Sta. 110+90.11
Exist. 2 - 8' x 4' x 121.5' RCB
w/ Pedestrian Rail Lt. & Rt.
to Remain

Sta. 110+72
Remove 18 L.F. of
Exist. 24" RCP.
Refer to Sht. 33
for Pipe Opening
Repair Detail.

Sta. 110+55
Remove 5 S.Y. of
Exist. Rip-rap. May
be re-used

Sta. 111+20
Remove 4 S.Y. of
Exist. Rip-rap. May
be re-used

Sta. 111+06
Remove 15 L.F. of
Exist. 24" RCP.
Refer to Storm
Sewer Line 11.

Removal, typ.

Trees to be Removed, typ.



Drawn By: Schwab-Eaton, P.A.
Plotted: 5/3/2019 1:40 PM
File: 15.W01 Road.dwg

BM #2 Square Cut N. Nose of Island at
Forestview and 13th St. N.
Sta. 109+05.00, 64.29' Rt. Elev.=1347.78



CITY OF WICHITA
13TH STREET NORTH
STA. 104+70 TO STA. 111+20



DESIGNED	MS	DRAWN	JM	SCALE	1" = 20'-0"	SHEET NO.	9
CHECKED	MS	DATE	09/18				