VICINITY MAP
NOT TO SCALE

SHEET INDEX

1	G-0.00	COVER SHEET
2	G-0.01	VICINITY MAP, DRAWING INDEX AND QUANTITIES
3	G-0.02	GENERAL NOTES
4	G-0.03	TOE DRAIN DETAILS
5	G-0.04	TOE DRAIN DETAILS
6	C-1.01	KEY PLAN
7	C-2.06	LEVEE TOE DRAIN PLAN AND PROFILE
8	C-2.07	LEVEE TOE DRAIN PLAN AND PROFILE
9	C-2.08	LEVEE TOE DRAIN PLAN AND PROFILE
10	C-3.01	EROSION CONTROL DETAILS
11	C-4.01	TRAFFIC CONTROL DETAILS AND NOTES
12	C-4.02	TRAFFIC CONTROL DETAILS AND NOTES
13	C-4.03	TRAFFIC CONTROL DETAILS AND NOTES
14	C-4.04	TRAFFIC CONTROL DETAILS AND NOTES

TABLE OF QUANTITIES (BASE BID ITEMS)

Measured Quantity Basis

Item	Quantity	Unit
Top Soil Excavation and Stockpiling (NOTE 2)	1,498	Cubic Yards
Trench Excavation and Disposal of Existing Filter Media and Existing Toe Drain Pipe (NOTE 3)	13,482	Cubic Yards
Replacement Toe-Drain Pipe with Filter Sock (6" diameter perforated HDPE) (NOTE 4)	13,482	Linear Feet
Replacment Risers (6" diameter non-perforated HDPE)	360	Linear Feet
Replacement Riser Cap and Outlet Appurtenances (NOTE 5)	36	Each
Precast Concrete Manhole (48" dia. with lockable cover)	18	Each
Replacement Filter Media (Stone meeting ASTM C33 specification for concrete aggregate)	5,243	Cubic Yards
Earthfill (backfill with existing material)	9,737	Cubic Yards
Erosion Control BMP (Ditch Check Protection)	1	EA.
Erosion Control BMP (Stabilized Entrance)	2	EA.
Erosion Control Blanket (SC150 or equivalent)	37,450	Square Yards

Lump Sum Basis

Item	Quantity	Unit
Site Clearing (NOTE 1)	1	Lump Sum
Site Restoration (NOTE 6)	1	Lump Sum
Traffic Control	1	Lump Sum

1. Includes cost for mobilization, tree removal and trimming, debris and tree disposal, sod stripping, and grading.
2. Includes excavation of top 1.0 foot of soil, stockpiling, and any necessary temporary erosion control such as silt fence.
3. Includes all work associated with the trench excavation and disposal of the existing toe drain pipe, risers and filter media. Trench shoring is required for this project and it shall be assumed that a minimum of 200 feet of shoring will be on site at all times and shall be subsidiary to this bid item. Includes approx. 5,500 cu. yds. of existing pipe and filter media to be disposed of off site.
4. All appurtenant fittings such as tees, caps, and couplers shall be subsidiary to this bid item.
5. Includes Fabricated riser cap, 2 metal barrier posts, weed barrier around riser outlet, and crushed rock.
6. Shall include all equipment, materials and labor to restore the site and shall include such items as grading, seeding mulch, fertilizer and any additional items necessary to establish vegetation as described in the General Notes. Estimated seeding area is 12 acres.

LEGEND

EXISTING LEVEE CENTERLINE

960+00C — CORPS OF ENGINEERS LEVEE STATIONS (SHOWN FOR INFORMATION ONLY)

EXISTING TOE DRAIN RISERS (FIELD LOCATED IN 2010 BY GPS)

PROPOSED TOE DRAIN

R-## — PROPOSED TOE DRAIN RISER

MH-# — PROPOSED TOE DRAIN MANHOLE

PROPOSED TOE DRAIN CAP

MARK	DESCRIPTION	DATE	APPR

amec
AMEC Earth & Environmental, Inc.
1120 SW Wanamaker
Topeka, Kansas 66604
Phone: (785) 272-6830
Fax: (785) 272-6878

CITY OF WICHITA

LOWER LEVEE "C" TOE DRAIN REPLACEMENT
WICHITA-VALLEY CENTER LOCAL FLOOD PROTECTION PROJECT
WICHITA, KANSAS

PREPARED FOR
THE CITY OF WICHITA, KANSAS
455 N. Main
Wichita, KS 67202

DESIGNED BY: Larry Sample, PE		DATE: 08-13-2012
DWN BY: BES	CKD BY: LBK	APP BY: L. SAMPLE
FILE NAME: SFILESS		

AMEC PROJ. NO. 5-6150-0001

VICINITY MAP, SHEET INDEX

G-0.01

SHEET 2 OF 19