




**BENCHMARKS:**


BM #1: "□" Cut in top of curb, south of SE corner of Lot 82, Block A, Turkey Creek 3rd Addition.  
Elev. = 1335.49 NGVD29

BM #2: "□" Cut on top of curb inlet, SW of the SE corner of Lot 81, Block A, Turkey Creek 3rd Addition.  
Elev. = 1335.95 NGVD29

BM #3: "□" Cut on top of yard inlet, 5' N & 43.5' E of the SE corner of Lot 28, Block H, Turkey Creek 3rd Addition.  
Elev. = 1335.95 NGVD29

**EROSION CONTROL PLAN LEGEND**

-  - DROP INLET PROTECTION
-  - CURB INLET PROTECTION
-  - SILT FENCE



0 60 120  
Scale: 1" = 60'  
= Iron

— 1364 — Existing Ground



EROSION CONTROL MEASURE	INSTALL	MAINTAIN
MAINTAIN EROSION CONTROL BMP's (LS)	0	1

\* All existing BMP's including Construction Entrance, Sediment Barriers, Silt Fence, Cut-off Trench, and Erosion Control Mat shall be maintained and repaired if necessary.

- EROSION CONTROL NOTES:**
- Contractor shall make sure all erosion control is in place before project is accepted. This plan represents the minimum standard. Any additional erosion control measures shall be installed by the Contractor as needed.
  - All areas disturbed during construction shall be seeded, mulched, and fertilized as per Cover Sheet General Notes.



**Baughman** Turkey Creek 3rd Addition - Phase 4  
**EROSION CONTROL**  
Water Distribution System

315 Ellis St. Wichita, KS 67211 P 316.262.7271 F 316.262.0149  
ENGINEERING | SURVEYING | PLANNING | LANDSCAPE ARCHITECTURE

PROJECT NUMBER 448-2020-016837	DESIGN DMV	DRAWN JAK
REVISIONS:	APPROVED	DATE 9/10/2020
	SCALE Noted	SHEET <b>8 OF 16</b>

E:\Projects\Turkey Creek 3rd\Engineering\Phase 4\Wtr\_2020-E496\WTR PLANS.dwg