



CREST-FAIRFAX CY Excavation (unadjusted)				CREST-FAIRFAX CY Compacted Fill (unadjusted)				CREST-FAIRFAX CY Loose Fill (unadjusted)			
Station	Area	Volume	Total	Station	Area	Volume	Total	Station	Area	Volume	Total
5+10.51	21.81	0.00	0.00	5+10.51	3.33	0.00	0.00	5+10.51	5.32	0.00	0.00
5+50	21.87	31.85	31.85	5+50	1.98	3.10	3.10	5+50	7.54	9.54	9.54
5+93.33	11.27	26.46	58.31	5+93.33	3.61	3.59	6.69	5+93.33	14.01	17.75	27.29
6+20.71	12.36	12.44	70.75	6+20.71	3.88	3.05	9.74	6+20.71	7.21	10.60	37.89
6+48.21	12.29	13.30	84.06	6+48.21	5.68	3.91	13.65	6+48.21	14.25	10.50	48.39
7+00	11.78	23.49	107.54	7+00	5.21	8.38	22.04	7+00	11.39	24.49	72.88
7+50	17.49	27.11	134.65	7+50	1.50	5.97	28.01	7+50	16.94	26.50	99.37
8+00	13.77	28.95	163.60	8+00	2.91	4.09	32.10	8+00	11.65	26.48	125.85
8+50	29.71	40.26	203.86	8+50	3.09	5.56	37.65	8+50	5.78	16.14	141.98
8+77.83	25.13	28.43	232.29	8+77.83	3.16	3.09	40.74	8+77.83	7.85	6.85	148.83
9+08.81	20.32	26.50	258.79	9+08.81	2.06	2.76	43.50	9+08.81	2.46	5.68	154.51
9+39.80	12.10	18.79	277.58	9+39.80	3.34	2.85	46.35	9+39.80	9.83	7.12	161.63
9+50	11.12	4.33	281.91	9+50	3.98	1.27	47.62	9+50	8.87	3.60	165.23
10+00	10.10	19.48	301.40	10+00	1.45	4.71	52.33	10+00	12.40	20.00	185.23
10+50	8.59	17.40	318.79	10+50	2.26	3.70	56.03	10+50	11.63	21.77	207.00
10+87.74	38.28	32.69	351.48	10+87.74	1.12	2.52	58.55	10+87.74	1.00	8.72	215.71

