



CREST CIR CY Excavation (unadjusted)				CREST CIR CY Loose Fill (unadjusted)			
Station	Area	Volume	Total	Station	Area	Volume	Total
-0+50	0.00	0.00	0.00	-0+50	16.10	0.00	0.00
-0+35	9.36	2.60	2.60	-0+35	24.60	11.30	11.30
-0+15	18.54	10.33	12.93	-0+15	13.95	14.28	25.58
-0+00	16.40	9.70	22.64	-0+00	18.10	8.90	34.48
0+25.09	13.37	13.83	36.47	0+25.09	22.74	18.98	53.46
0+53.21	8.47	11.43	47.90	0+53.21	20.63	22.27	75.73
1+00	12.63	18.34	66.24	1+00	18.73	32.70	108.43
1+50	13.34	24.04	90.28	1+50	6.79	22.81	131.24
2+00	10.09	21.70	111.98	2+00	7.82	13.52	144.76
2+50	9.01	17.68	129.66	2+50	11.59	17.97	162.73
3+00	12.57	20.00	149.66	3+00	13.06	22.73	185.46
3+50	12.39	23.07	172.73	3+50	14.57	24.96	210.42
3+82.77	26.58	23.85	196.58	3+82.77	4.92	11.46	221.88

CREST CIR.