



WINSTON CIR WEST CY Excavation (unadjusted)				WINSTON CIR WEST CY Compacted Fill (unadjusted)				WINSTON CIR WEST CY Loose Fill (unadjusted)			
Station	Area	Volume	Total	Station	Area	Volume	Total	Station	Area	Volume	Total
4+36.52	3.73	0.00	0.00	4+36.52	0.00	0.00	0.00	4+36.52	24.86	0.00	0.00
4+50	3.74	1.80	1.80	4+50	0.00	0.00	0.00	4+50	24.66	12.63	12.63
4+60.74	17.32	4.33	6.14	4+60.74	7.01	1.57	1.57	4+60.74	8.04	6.49	19.13
4+70.20	18.13	5.99	12.13	4+70.20	7.06	2.25	3.81	4+70.20	7.05	2.78	21.90
4+77.76	17.66	4.84	16.97	4+77.76	1.62	1.11	4.92	4+77.76	6.41	1.98	23.88
4+83.17	17.28	3.50	20.46	4+83.17	1.69	0.33	5.25	4+83.17	6.05	1.25	25.13
4+90.75	16.73	4.60	25.06	4+90.75	7.33	1.15	6.41	4+90.75	5.69	1.73	26.86
5+00	17.22	5.61	30.68	5+00	7.56	2.33	8.74	5+00	5.11	1.94	28.80
5+50	26.26	39.06	69.73	5+50	8.14	13.26	21.99	5+50	5.17	9.99	38.79
5+61.06	36.45	12.51	82.24	5+61.06	6.27	2.69	24.68	5+61.06	2.40	1.63	40.42
5+65.26	22.55	4.59	86.84	5+65.26	0.00	0.49	25.17	5+65.26	5.94	0.65	41.07
5+73.99	25.78	7.82	94.66	5+73.99	0.00	0.00	25.17	5+73.99	6.09	1.90	42.98
5+86.07	33.13	13.15	107.80	5+86.07	0.00	0.00	25.17	5+86.07	5.89	2.66	45.63

WINSTON CIR.