



Sand, Flush, and Fill backfill shall be required along RCB excavation equivalent to the top of the box structure or to the existing ground elevation whichever is higher.

