

STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	472-83537	2003	56	73

SUMMARY OF
TRAFFIC CONTROL DEVICES
(EACH)

[illegible]

SUMMARY OF
TRAFFIC CONTROL DEVICES
(LUMP SUM)

TEMPORARY TRAFFIC SIGNALS (NO. OF SETS)	
---	--

SUMMARY OF
TRAFFIC CONTROL DEVICES
(EACH PER DAY)

* QUANTIFY MOST USED ON THE
PROJECT AT ANY ONE TIME

[illegible]

BARRICADES *	CHANNELIZING DEVICES	
TYPE III (1.2 m TO 2.4 m)	FIXED	PORTABLE
18		

LIGHTED DEVICES *	
CONSTRUCTION WARNING LIGHT (TYPE 'B' HIGH INTENSITY)	3
ARROW DISPLAY	
PORTABLE CHANGEABLE MESSAGE SIGN (LED)	

RECAPITULATION OF QUANTITIES

ITEM	QUANTITY	UNIT
CONSTRUCTION SIGNS (0 TO 0.85 m ²)		EACH PER DAY
CONSTRUCTION SIGNS (0.86 TO 1.50 m ²)		EACH PER DAY
CONSTRUCTION SIGNS (1.51 m ² & OVER)		EACH PER DAY
CONSTRUCTION BARRICADES (TYPE III - 1.2m TO 2.4 m)		EACH PER DAY
CHANNELIZER (FIXED)		EACH PER DAY
CHANNELIZER (PORTABLE)		EACH PER DAY
CONSTRUCTION WARNING LIGHT (TYPE "B" HIGH INTENSITY)		EACH PER DAY
ARROW DISPLAY		EACH PER DAY
PORTABLE CHANGEABLE MESSAGE SIGN (LED)		EACH PER DAY
PAVEMENT MARKING (TEMPORARY)		km/LINE
100 mm SOLID (TYPE I TAPE)		km/LINE
100 mm SOLID (TYPE II TAPE)		km/LINE
100 mm SOLID (PAINT)		km/LINE
100 mm BROKEN (2.5 m) (TYPE I TAPE)		km/LINE
100 mm BROKEN (2.5 m) (TYPE II TAPE)		km/LINE
100 mm BROKEN (2.5 m) (PAINT)		km/LINE
100 mm BROKEN (1.0 m) (TYPE I TAPE)		km/LINE
100 mm BROKEN (1.0 m) (TYPE II OR IIA TAPE)		km/LINE
100 mm BROKEN (1.0 m) (PAINT)		km/LINE
100 mm DOTTED EXTENSION (TYPE I TAPE)		km/LINE
100 mm DOTTED EXTENSION (TYPE II TAPE)		km/LINE
100 mm DOTTED EXTENSION (PAINT)		km/LINE
SOLID (LINE MASKING TAPE)		km/LINE
BROKEN (LINE MASKING TAPE)		km/LINE
EXISTING PAVEMENT MARKING REMOVAL		meter
PAVEMENT MARKING REMOVAL (TEMPORARY)(TYPE II TAPE)		meter
PAVEMENT MARKING REMOVAL (TEMPORARY)(PAINT)		meter
GLARE SCREEN		meter
CONCRETE SAFETY BARRIER (TYPE I)(TEMPORARY)		meter
CONCRETE SAFETY BARRIER (TYPE I)(TEMP.-INSTALL ONLY)		meter
CONCRETE SAFETY BARRIER (TYPE I)(TEMP.-RELOCATE)		meter
CONCRETE SAFETY BARRIER (TYPE IV)(TEMPORARY)		meter
CONCRETE SAFETY BARRIER (TYPE IV)(TEMP.-INSTALL ONLY)		meter
CONCRETE SAFETY BARRIER (TYPE IV)(TEMP.-RELOCATE)		meter
INERTIAL BARRIER SYSTEM		EACH
MODULE F90 (REPLACEMENT)		EACH
MODULE F180 (REPLACEMENT)		EACH
MODULE F320 (REPLACEMENT)		EACH
MODULE F640 (REPLACEMENT)		EACH
MODULE F960 (REPLACEMENT)		EACH
CONSTRUCTION SIGN (SPECIAL)		EACH
TEMPORARY RAISED PAVEMENT MARKER (TYPE I)		EACH
TEMPORARY RAISED PAVEMENT MARKER (TYPE II)		EACH
TRAFFIC SIGNAL INSTALLATION (TEMPORARY)		LUMP SUM
TEMPORARY TRAFFIC SIGNALS		LUMP SUM
TRAFFIC CONTROL (INITIAL SET UP)	LUMP SUM	LUMP SUM
TRAFFIC CONTROL		LUMP SUM
FLAGGER (SET)	1	hour

3				
2				
1	11-13-01	CHANGED PYMT. MKG. & CHANNELIZERS BID ITEMS	JH	S.A.B
NO.	DATE	REVISION	BY	APP'D

KANSAS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF DEVICES
 AND
 RECAPITULATION OF QUANTITIES

-TE795H-

FHWA APPROVAL 11-21-01 APP'D Michael P. McKenna

DESIGNED L.E.R.	DETAILED S.A.H.	QUANTITIES	TRACED
DESIGN CK.	DETAIL CK.	QUAN. CK.	TRACE CK.

Plotted By : mark	Thacher Bldg., 4th Floor
Plot File : h:\CM\IL\01053\DG\MT\E795SI.DGN	
Plot Date : 05/01/03	