


24' TYPICAL PAVEMENT DETAILS

TRANSVERSE SECTION



General Notes

FABRIC BASE REINFORCEMENT SHALL BE B X 1100 GEOGRID AS MANUFACTURED BY TENSAR CORPORATION OR APPROVED EQUAL. FABRIC BASE REINFORCEMENT SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS. CRUSHED ROCK SHALL BE UNIFORMLY GRADED FROM 1-1/2" MAXIMUM SIZE TO NOT MORE THAN 10% PASSING A NO. 200 SIEVE. ROCK QUALITY SHALL BE THE SAME AS SPECIFIED FOR COARSE AGGREGATE FOR CONCRETE MIXES.

ROCK BASE IS TO BE COMPACTED AND SMOOTHED WITH A STEEL FACED ROLLER PRIOR TO PLACEMENT OF ASPHALT. TACK COAT WILL NOT BE APPLIED TO ROCK BASE.

A TACK COAT OF EMULSIFIED ASPHALT (SC-1H OR CSS-1H) SHALL BE APPLIED AT AN APPROXIMATE RATE OF 0.05 GALLONS PER SQUARE YARD BETWEEN EACH LIFT OF ASPHALTIC MATERIAL.

BITUMINOUS BASE AND ASPHALTIC CONCRETE WEARING SURFACE SHALL BE PLACED WITH A LAYDOWN MACHINE HAVING AUTOMATIC CONTROLS FOR LINE AND GRADE.


CONSTRUCTION JOINTS IN EACH LIFT SHALL BE STAGGERED A MINIMUM DISTANCE OF ONE (1) FOOT FROM JOINTS IN PRECEDING LIFTS AND PLACED SO THAT A JOINT WILL BE CONSTRUCTED ON THE CENTERLINE OF THE TOP LIFT.

THE ASPHALTIC CONCRETE PAVEMENT BETWEEN THE COMBINED CURB AND GUTTER SHALL BE PAID AS SQUARE YARDS OF 5" ASPHALTIC CONCRETE (3" BITUMINOUS BASE).

CRUSHED ROCK GRADATION REQUIREMENTS

Percent of Aggregate Retained	
1 1/2"	0
3/4"	15-60
# 4	40-80
#40	74-92
P-200	4-12

Rock Quality Shall Be The Same As Specified For Coarse Aggregate For Asphalt Concrete Mixes.



TRANSVERSE CONSTRUCTION JOINTS

Transverse construction joints shall be constructed in flexible base pavements at locations where pavement joints existing flexible base pavement as shown by the detail. All costs associated with the construction of the transverse joint shall be included in the bid price for Square Yards 5" ASPHALTIC CONCRETE (3" BITUMINOUS BASE).

- ① TYPE B, MR-90 COMPACTION REQUIRED BELOW 5" CRUSHED ROCK SUBGRADE SECTION.
- ② TO BE CONSTRUCTED IN TWO (2) LIFTS.
- ③ IF UNSUITABLE MATERIAL IS ENCOUNTERED, IT SHALL BE EXCAVATED AS DIRECTED BY THE ENGINEER AND REPLACED WITH SELECT MATERIAL. THE SELECT MATERIAL SHALL HAVE COMPACTION REQUIREMENT TYPE B, MR-90. THIS WORK SHALL BE SUBSIDIARY TO "OTHER ITEMS IN THE CONTRACT".
- ④ THIS AREA TO BE BACKFILLED WITH TOPSOIL, COMPACTED AND SEEDDED UPON COMPLETION OF PAVING. COST IS SUBSIDIARY TO "OTHER ITEMS IN THE CONTRACT".

CITY OF WICHITA		
24' TYPICAL PAVEMENT DETAIL		
FOR STREET PAVING IMPROVEMENTS		
CED PROJ. NO.: 20030988		
CERTIFIED ENGINEERING DESIGN, P.A.		
810 WEST DOUGLAS, SUITE C		
WICHITA, KANSAS 67203		
PH.(316)282-8808 FAX.(316)282-1000		
DESIGNED: HDF	SCALE: NTS	SHEET
DRAWN: HDF	DATE: 7/03	3
CHECKED: HDF	CED FILE: 03-24typ.dwg	TOTAL 43