



Note:
The Temporary Erection Diaphragms shall be in place during placement and curing of the deck, after which they shall be removed with the exception of the 7/8" Dia. H.S. Bolts through the Web, which shall be reinserted in the holes and tightened.
Temporary Erection Diaphragms, Bent Plates and Bolts shall not be paid for directly, but shall be subsidiary to the bid item "Structural Steel, A709 (Gr. 36)". After Removal they shall become the property of the Contractor.

Revisions		By	Date
No.			

CITY OF WICHITA, KANSAS
MICHAEL E. LINDEBAK, P.E.-CITY ENGINEER
DOUGLAS AVENUE BRIDGE
OVER ARKANSAS RIVER
STRUCTURAL STEEL DIAPHRAGM DETAILS
CITY OF WICHITA PROJECT NO. 412-82721
PROFESSIONAL ENGINEERING CONSULTANTS, P.A.
ENGINEERS
WICHITA, KANSAS

Designed by	P.D.F.	Checked by	R.A.S.
Drawn by	J.G.P.	Date	Sept. 1997
		Job No.	95088-4

1:1995/95088.dwg
 drawn by: jgp
 plotted by: ras 8-26-97