



PHASING	HANDLING OF TRAFFIC	MAJOR CONSTRUCTION ITEMS	REMARKS
1	Erect traffic control in accordance with the plans. Maintain one lane of traffic in each direction during this phase. The northbound right turn lane and southbound left turn lane onto Harry shall remain open during this phase.	Construct temporary asphalt pavement widening along the west side of Tyler as shown on the traffic control plans and details.	
2	Erect traffic control in accordance with the plans. Maintain one lane of traffic in each direction during this phase. The southbound left turn lane onto Harry shall remain open during this phase.	Construct the east portion of the RCB as outlined in the plans. Construct temporary asphalt pavement widening along the east side of Tyler as shown on the traffic control plans and details.	
3	Erect traffic control in accordance with the plans. Maintain one lane of traffic in each direction during this phase. The southbound left turn lane onto Harry shall remain open during this phase.	Construct the west portion of the RCB as outlined in the plans.	
4	Erect localized traffic control and lane closures as necessary to complete the work. Maintain a minimum of one lane of traffic in each direction during this phase.	Construct remaining improvements including asphalt surface courses and permanent pavement markings.	



TEMPORARY PAVEMENT WIDENING
(At Temporary Concrete Barrier Locations)

Note: "A.C. Pavement 6", Temporary" and "Crushed Rock Base 5", Temporary" will be paid for separately. Work includes the eventual removal of pavement and base. Compacted fill and foundation treatment are subsidiary to temporary pavement bid items.



TEMPORARY PAVEMENT WIDENING
(At Areas Without Concrete Barrier)

©2021
MKEC Engineering
All Rights Reserved
www.mkec.com
These drawings and their contents, including, but not limited to, all concepts, designs, & ideas are the exclusive property of MKEC Engineering (MKEC), and may not be used or reproduced in any way without the express consent of MKEC.

CONSTRUCTION SEQUENCE SUMMARY

PROJECT NO.	1901010483	
DATE	FEB. 2021	
SCALE	N.T.S.	
DESIGNED	DRAWN	CHECKED
JRA	RAM	JRA

NO.	REVISION	DATE

SHEET NO.
28 OF 41