## SCHEDULE OF INLETS AND MANHOLES

| STATION | SIDE | TYPE: MAN-HOLES | TYPE: CURB INLETS | TYPE: DRIVEWAY INLETS | TYPE: DROP INLETS | SEWER DATA: INFLOW PIPES SIZE | INFLOW PIPES ℄ ELEV. | INFLOW PIPES SIZE | INFLOW PIPES ℄ ELEV. | INFLOW PIPES SIZE | INFLOW PIPES ℄ ELEV. | OUTFLOW PIPES SIZE | OUTFLOW PIPES ℄ ELEV. | OUTFLOW PIPES GRADE | ELEVATIONS: TOP | ELEVATIONS: FLOOR | DIMENSIONS: L (FT.) | DIMENSIONS: W (FT.) | DIMENSIONS: H (FT.) | STORM SEWER LIN. FT.: 15" | 18" | 21" | 24" | 30" | 36" |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 96+48.00 | Lt. | | | | 1 | 10 | 1294.76 | 10 | 1294.67 | 10 | 1294.67 | 36 | 1292.21 | 0.10 | 1297.00 | 1291.50 | 3'-6" | 3'-6" | 6'-0" | | | | | | |
| 99+00.00 | Lt. | | 1 | | | | | | | | | 18 | 1292.87 | 4.00 | 1291.90 | 1291.90 | 5'-0" | 4'-4" | 5'-6" | | 23 | | | | |
| 99+00.00 | Rt. | | 1 | | | | | | | | | 18 | 1292.91 | 4.00 | 1297.49 | 1291.99 | 5'-0" | 4'-4" | 5'-6" | | 24 | | | | |
| 99+09.00 | Lt. | 1 | | | | 36 | 1291.95 | 18 | 1291.95 | 18 | 1291.95 | 36 | 1291.85 | 0.10 | 1297.65 | 1291.15 | 5'-0" | 5'-0" | 6'-6" | | | | | | 261 |
| 99+94.00 | Rt. | Exist | | | | 36 | 1291.77 | 36 | Exist. | | | 36 | 1291.40 | Exist. | 1297.56 | | | | | | | | | | 85 |
| 101+62.39 | Rt. | Exist. | | | | 36 | Exist. | | | | | 36 | Exist. | Exist. | 1296.72 | | | | | | | | | | |
| 102+50.00 | Lt. | | 1 | | | | | | | | | 18 | 1293.38 | 2.00 | 1295.99 | 1291.99 | 5'-0" | 4'-4" | 4'-0" | | 29 | | | | |
| 102+50.00 | Rt. | | | 1 | | | | | | | | 18 | 1293.16 | 2.00 | 1295.64 | 1292.39 | 5'-6" | 3'-10" | 3'-3" | | 18 | | | | |
| 102+59.00 | Rt. | 1 | | | | 36 | 1291.38 | 18 | 1292.80 | 18 | 1292.80 | 36 | 1291.38 | Exist. | 1296.30 | 1290.30 | 5'-0" | 5'-0" | 6'-0" | | | | | | |
| 103+39.71 | Rt. | Exist. | | | | 36 | Exist | | | | | 36 | Exist. | Exist. | 1296.62 | | | | | | | | | | |
| 104+54.00 | Lt. | | 1 | | | | | | | | | 18 | 1293.20 | 2.00 | 1295.82 | 1291.82 | 5'-0" | 4'-4" | 4'-0" | | 30 | | | | |
| 104+54.00 | Rt. | | 1 | | | | | | | | | 18 | 1292.96 | 2.00 | 1296.20 | 1292.20 | 5'-0" | 4'-4" | 4'-0" | | 18 | | | | |
| 104+61.00 | Rt. | 1 | | | | 36 | | 18 | 1292.60 | 18 | 1292.60 | 36 | 1291.10 | Exist. | 1296.30 | 1291.30 | 5'-0" | 5'-0" | 6'-0" | | | | | | |
| TOTAL | | | | | | | | | | | | | | | | | | | | | 142 | | | | 346 |

CITY OF WICHITA

SCHEDULE
INLETS AND MANHOLES

Booker ASSOCIATES INC. OF KANSAS
Wichita Kansas

SCALE | DATE - MAY, 1997 | DWG. NO. K9540

Drawn By : $$USERNAME$$ | Plotted : $$$$$SYTIME$$$$$$
File : $$$$$$$$$$$$$$$$DGNSPEC$$$$$$$$$$$$$$$$