

1. *Underground utility service lines and overhead utility pole lines are to be adjusted by utility companies if necessary prior to construction unless the plans specifically call for their adjustment by the Contractor. Existing utilities and their location, as shown on the plans, represent the best information obtainable for design. The Contractor will be required to work around existing utilities within the right-of-way which do not conflict with proposed construction.*
2. *Rubble from the removal of miscellaneous structures and excess excavation which is to be wasted shall be disposed of on sites to be provided by the Contractor. These sites shall be approved by the Engineer as to suitability, appearance and site location. Locations that, in the opinion of the Engineer, will leave an unsightly appearance will not be approved.*
3. *All disposal sites must be approved by the Kansas Department of Health and Environment. Material either stockpiled or disposed of in a flood plain would require a Kansas State Board of Agricultural permit. Any material dumped in waters of the United States or wetlands is subject to U.S Corps of Engineers permitting regulations. Any material buried or stockpiled beyond approved construction limits would require additional archaeological investigations unless buried in a previously approved borrow location.*
4. *The Contractor shall give all property owners and/or tenants of developed property abutting the construction of this project a minimum of ten (10) days notice prior to start of construction and again 48 hours prior to any work actually starting.*
5. *The Contractor shall be responsible for preserving property irons. The Contractor will be required to re-establish any shown property irons which are disturbed by his construction operations. Such irons shall be re-established by a licensed Land Surveyor in accordance with state laws.*
6. *Contractor is required to provide a minimum notice of forty-eight (48) hours to utility companies prior to starting any excavation as follows:*

Kansas One-Call 316-687-2470 or 1-800-DIG-SAFE

The Contractor must notify the following before construction and in case of an emergency.

Cox Communications (was Multimedia)	262-4270 or 263-2061
Kansas Gas Service	383-8650
WESTAR (was KGE)	383-8600
Aquila Networks(was Peoples/Arkla)	942-8350 or 263-8161
Southwestern Bell Company (or SBC)	1-571-2611
City of Wichita Water Department	268-4908
City of Wichita Sewer Maintenance	268-4071

7. *All salvageable drainage pipes, manhole rings and covers, and inlet grates shall be carefully removed and stockpiled at locations within the right-of-way as directed by the Engineer for removal by City personnel.*
8. *Contractor shall maintain two-way traffic during the project for the entire length of the project.*

9. *Underground Irrigation Systems. Properties within the project may have underground irrigation systems (lawn sprinklers) which conflict with new construction. Contractor shall remove such components as needed during construction of the project. The irrigation system shall be reinstalled in like kind before project completion. Any irrigation system modifications required because of project improvements shall be coordinated with the property owner. Portions of underground irrigation systems not in conflict with new construction shall be protected from damage and shall remain in place.*
10. *When working near or over the 1.500mm Transmission Waterline from Cheney Reservoir, use extreme caution. Contact Randy Schultz with the Water Department @ 269-4767 prior to any type of construction near the transmission waterline.*
11. *Existing signal equipment is be returned to 1801 South McLean, to Central Maintenance Facility, Jim Parks, 268-4033.*

UTILITY CONTRACTOR LIST

WESTAR (was KGE)
1900 East Central
P.O. Box 208
Wichita, KS 67202
316-261-6251
Contact: Jim Horton or Shane Price

Kansas Gas Service
1021 East 26th Street North
Wichita, KS 67201
316-832-3121
Contact: Jim Stoltz or Charlene Lawless

Cox Communications (was Multimedia)
701 East Douglas
Wichita, KS 67202
316-262-4270
Contact: Bryan Ring

SW Bell or SBC (was Southwestern Telephone Co.)
154 North Broadway
Wichita, KS 67202
316-268-2245
Contact: Bob Alley

Stormwater Utility
City of Wichita
City Hall - 8th Floor
455 North Main
Wichita, KS 67202
316-268-4498
Contact: Chris Carrier

Dept. of Water & Sewer
City of Wichita
City Hall - 8th Floor
455 North Main
Wichita, KS 67202
316-268-4555
Contacts: LaDonna Lawrenz (Sewer)
Bill Perkins (Water)
Randy Schultz (Water) 269-4767

Traffic Engineering
City of Wichita
City Hall - 7th Floor
455 North Main
Wichita, KS 67202
316-268-4446
Contact: Paul Gunzelman

Sedgwick County Emergency
Management Agency
535 N. Main, Suite B10
Wichita, KS 67203-3702
316-383-7546
Contact: Jack Kegley

Aquila Networks (was Peoples/Arkla)
1611 S. Hoover
Wichita, KS 67209
316-941-1608
Emergency # 1-800-303-0357
Contact: Calvin Briggs

*REF: Project Number 472-83138

	21st & 119th Streets Signalization General Notes			
	CITY ENGINEER NEIL CABLE, P.E.			
	PROJECT NUMBER 472-83609*	CCA NUMBER 710216	DATE 09/2002	
	CITY ENGINEER'S OFFICE CITY HALL - SEVENTH FLOOR 455 NORTH MAIN STREET WICHITA, KANSAS 67202-1620 (316) 268-4501 (316) 268-4114 FAX		DESIGN TEB	DRAWN MWS
	SHEET 2 OF 7			