


TOTAL VOLUME TABLE							
STATION	CUT AREA (sq ft)	FILL AREA (sq ft)	CUT VOL (cu yd)	FILL VOL (cu yd)	CUM CUT VOL (cu yd)	CUM FILL VOL (cu yd)	NET VOL (cu yd)
12+00.00	17.63	0.84	0.00	0.00	0.00	0.00	0.00
12+50.00	14.98	0.00	30.19	0.78	30.19	0.78	29.41
13+00.00	21.61	0.00	33.88	0.00	64.07	0.78	63.29
13+50.00	41.38	0.00	58.32	0.00	122.39	0.78	121.61
14+00.00	40.32	0.00	75.65	0.00	198.04	0.78	197.26
14+50.00	40.66	0.00	74.98	0.00	273.02	0.78	272.24
15+00.00	41.43	0.00	76.00	0.00	349.02	0.78	348.24
15+50.00	23.27	0.00	59.90	0.00	408.93	0.78	408.15
16+00.00	23.73	0.00	43.52	0.00	452.44	0.78	451.66
16+50.00	25.85	0.01	45.91	0.01	498.35	0.79	497.56
17+00.00	21.58	0.01	43.92	0.01	542.27	0.80	541.47
17+38.78	20.23	0.40	30.03	0.29	572.30	1.10	571.20
21+00.00	18.48	1.25	258.95	11.04	831.24	12.14	819.11
21+50.00	19.33	0.00	35.00	1.16	866.25	13.29	852.95
22+00.00	27.21	0.00	43.09	0.00	909.34	13.29	896.05
22+50.00	27.41	0.00	50.58	0.00	959.92	13.29	946.62
23+00.00	21.66	0.00	45.43	0.00	1005.35	13.29	992.06
23+50.00	11.42	0.00	30.63	0.00	1035.98	13.29	1022.68
23+67.95	7.23	0.02	6.20	0.01	1042.18	13.30	1028.88

**PRELIMINARY PLAN. NOT FOR CONSTRUCTION.**  
 This document is preliminary in nature and is not a final, signed and sealed document.



**BAUGHMAN COMPANY**

315 Ellis St.  
 Wichita, KS 67211  
 316-262-7271  
 BaughmanCo.com

13TH STREET WIDENING

**CROSS SECTIONS**

CIP IMPROVEMENTS

PROJECT NUMBER:  
 472-2020-085654

DESIGN: LP DRAWN: LP  
 DATE: Apr. 8, 2021

SHEET OF  
**32 32**