SUMMARY OF QUANTITIES (FOR INFORMATION ONLY)

ITEM DESCRIPTION	UNITS	PER SHEET QUANTITY														TOTAL QUANTITY
		MCLEAN BOULEVARD	WACO AVENUE	WACO LT DETAIL	CENTURY II PED XING	WATER STREET	MAIN STREET	MARKET STREET	BROADWAY	TOPEKA	EMPORIA AVENUE	ST. FRANCIS	ROCK ISLAND PED XING	WASHINGTON AVENUE	HYDRAULIC STREET	
Mobilization	LS	–	–	–	–	–	–	–	–	–	–	–	–	–	–	1
Site Clearing and Restoration	LS	–	–	–	–	–	–	–	–	–	–	–	–	–	–	1
Transportation of Salvageable Material	LS	–	–	–	–	–	–	–	–	–	–	–	–	–	–	1
Traffic Signalization	LS	–	–	–	–	–	–	–	–	–	–	–	–	–	–	1
Traffic Control	LS	–	–	–	–	–	–	–	–	–	–	–	–	–	–	1
Erosion Control – Back of Curb Protection	LF	–	–	–	–	–	–	–	–	–	–	–	–	–	–	50
Erosion Control – Curb Inlet Protection	EA	2	1	–	–	8	8	–	8	–	–	–	–	–	–	27
Pavement Markings	LS	–	–	–	–	–	–	–	–	–	–	–	–	–	–	1
Pavement Removed	SY	–	–	50	–	–	–	–	–	–	–	–	–	–	–	50
AC Pavement Removed & Replaced, 7" (5" Bit Base) (BM–2,PG 70–28)	SY	–	–	50	–	–	–	–	–	–	–	–	–	–	–	50
Concrete Pavement, Remove and Replace	SF	–	740	–	–	–	–	–	–	–	–	–	–	–	–	740
Curb and Gutter, Remove and Replace	LF	–	–	–	–	15	–	–	10	–	–	–	–	–	–	25
Concrete Sidewalk, Remove and Replace	SF	–	430	–	–	–	–	20	20	130	165	105	–	–	–	870
Brick Pavers, Remove and Replace	SF	–	35	–	–	30	–	–	–	–	–	15	–	–	–	80
Concrete Pavers (Red), Remove and Replace	SF	–	–	–	–	–	90	–	230	–	–	–	–	–	–	320
MH, Adjusted	EA	–	–	–	–	–	2	–	2	–	–	–	–	–	–	4
Traffic MH Adjusted w/New Traffic Rated Lid & Cover	EA	–	–	1	–	–	–	–	–	–	–	–	–	–	–	1
Wheelchair Ramp with Detectable Warning	EA	3	4	–	–	6	8	–	8	–	–	–	–	–	–	29
Pedestrian Push Button Foundation, shallow (18")	EA	–	–	–	–	–	–	–	–	–	–	–	–	–	–	4
Pedestrian Push Button Foundation, Full–Depth (30")	EA	–	–	–	–	–	–	–	–	–	–	–	–	–	–	12
Pedestrian Push Button, Sono Tube	EA	–	–	–	–	–	–	–	–	–	–	–	–	–	–	4
Electronic Message Board (each per day)	DAY	–	–	–	–	–	–	–	–	–	–	–	–	–	–	30
Wavetronix WX–SS–225, SmartSensor Matrix	EA	4	2	–	–	1	4	1	4	1	2	2	–	–	–	21
Wavetronix WX–SS–611, Sensor Mounting Bracket	EA	4	2	–	–	1	4	1	4	1	2	2	–	–	–	21
Wavetronix Click!600 Cabinet Interface	EA	1	1	–	–	1	1	1	1	1	1	1	–	–	–	9
Wavetronix CLK114 4 CH Rack Cards	EA	4	2	–	–	1	4	1	4	1	2	2	–	–	–	21
Wavetronix Matrix System Cable 18AWG/3PR	LF	980	420	–	–	200	735	225	695	25	200	400	–	–	–	3880

PLANS PREPARED BY:

iteris®
1700 Carnegie Avenue, Suite 100
Santa Ana, CA 92705-5551
Phone: (949)270-9480
Fax: (949) 270-9481

BAUGHMAN COMPANY
315 Ellis St. Wichita, KS 67211 316-262-7271
BaughmanCo.com

THIS PLAN IS ACCURATE FOR EQUIPMENT UPGRADE WORK ONLY.

811 Know what's below. Call before you dig.
ONE CALL KANSAS
KS: (800) 344-7233 WICHITA: (316) 687-2470
The Contractor shall provide a minimum advance notice of TWO (2) Working Days to Utility Companies prior to any excavation.

REVISIONS

NO.	DATE	DESCRIPTION	APP.

REFERENCES

BENCH MARK NO.
ELEVATION
DESCRIPTION
BASIS OF BEARING

DESIGNED BY: BAUGHMAN CO. & ITERIS, INC	DATE 05/07/21	CHECKED BY: STEVEN P. GARBE	DATE 05/07/21
DRAWN BY: BAUGHMAN CO. & ITERIS, INC	DATE 05/07/21		
RECOMMENDED BY:			
APPROVED BY:			

STEVEN PHILLIP GARBE LICENSED 16369 KANSAS PROFESSIONAL ENGINEER
P. E. SEAL

DOUGLAS AVENUE TRAFFIC SIGNAL IMPROVEMENTS

DOUGLAS AVENUE EQUIPMENT UPGRADES
SUMMARY OF QUANTITIES

CITY OF WICHITA

SHEET 3 **OF** 23

PLAN NUMBER