



BEDFORD

BEDFORD CY Excavation (unadjusted)				BEDFORD CY Compacted Fill (unadjusted)				BEDFORD CY Loose Fill (unadjusted)			
Station	Area	Volume	Total	Station	Area	Volume	Total	Station	Area	Volume	Total
0+74.93	15.46	0.00	0.00	0+74.93	0.98	0.00	0.00	0+74.93	10.16	0.00	0.00
1+00	20.18	16.89	16.89	1+00	0.00	0.54	0.54	1+00	5.31	6.77	6.77
1+19.96	19.80	15.30	32.19	1+19.96	0.00	0.00	0.54	1+19.96	5.31	3.34	10.11
1+50	21.30	23.77	55.96	1+50	0.00	0.00	0.54	1+50	5.31	5.03	15.15
1+65	15.46	10.48	66.43	1+65	0.98	0.32	0.86	1+65	10.16	4.05	19.20
2+00	15.46	20.04	86.47	2+00	0.98	1.51	2.37	2+00	10.16	13.04	32.24
2+50	15.46	28.63	115.11	2+50	0.98	2.11	4.48	2+50	10.16	18.66	50.89
3+00	15.46	28.63	143.74	3+00	0.98	1.82	6.31	3+00	10.16	18.81	69.70
3+50	15.46	28.63	172.38	3+50	0.98	1.97	8.27	3+50	10.16	18.73	88.43
4+00	15.46	28.63	201.01	4+00	0.98	1.85	10.13	4+00	10.16	18.79	107.22
4+50	15.46	28.63	229.65	4+50	0.98	1.79	11.92	4+50	10.16	18.82	126.04
5+00	15.46	28.63	258.28	5+00	0.98	1.67	13.59	5+00	10.16	18.89	144.93
5+07.77	15.46	4.45	262.73	5+07.77	0.98	0.26	13.86	5+07.77	10.16	2.93	147.86
5+44.79	23.56	26.76	289.49	5+44.79	0.00	0.67	14.53	5+44.79	5.31	10.60	158.47
5+81.77	15.46	26.73	316.21	5+81.77	0.98	0.67	15.20	5+81.77	10.16	10.59	169.06
6+00	15.46	10.44	326.66	6+00	0.98	0.66	15.87	6+00	10.16	6.86	175.92
6+50	15.46	28.63	355.29	6+50	0.98	1.82	17.69	6+50	10.16	18.81	194.72
7+00	15.46	28.63	383.93	7+00	0.98	1.82	19.51	7+00	10.16	18.81	213.53
7+38.12	15.46	21.83	405.76	7+38.12	0.01	0.70	20.21	7+38.12	9.71	14.02	227.55



**BAUGHMAN
COMPANY**

315 Ellis St.
Wichita, KS 67211
316-262-7271
BaughmanCo.com

WILLOW CREEK EAST 3RD
ADDITION - PHASE II

**EARTHWORK
CROSS
SECTIONS**

Street Paving Improvements

PROJECT NUMBER:
472-85507

DESIGN: DMV DRAWN: JAK
DATE: 6/21/21

SHEET
21 OF **27**

File: E:\Projects\Willow Creek East 3rd Addition_17-04-P283\Engineering\Phase 2\STR_20-10-E742\STR PLANS.dwg