

INLET AND MANHOLE DATA																								FOR INFORMATION ONLY						REMARKS						
ROUTING SEQUENCE		LOCATIONS OF INSTALLATIONS					CONSTRUCT OR INSTALL						DIMENSIONS					ELEVATIONS					INFLOW CONDUITS					OUTFLOW CONDUITS			CLASS III EXC. (CU. YD)	CAST IRON (LBS.)	STRUCT. STEEL (LBS.)	REINF. STEEL (LBS.)	CLASS A CONC. (CU. YD)	STEPS
		STATION	ROUTE IDENTIFICATION	DISTANCE LEFT/RIGHT	NORTH COORDINATE	EAST COORDINATE	INLET (TYPE 22) CURB	DITCH INLET (TYPE I)	DITCH INLET (TYPE II)	R.C. M.H.	INLET-M.H. (SPECIAL)	G&F TYPE	L&F TYPE	L (FT.)	W (FT.)	H (FT.)	H _T (FT.)	TOP	FLOOR	SIZE DIRECT.	FLOWLINE ELEV.	SIZE DIRECT.	FLOWLINE ELEV.	SIZE DIRECT.	FLOWLINE ELEV.	SIZE DIRECT.	FLOWLINE ELEV.	SIZE DIRECTION	FLOWLINE ELEV.							
FROM	TO																																			
400	401	59+40	Central	22.00' Rt.	576740.8410	377532.0345	I					C	10'-0"	4'-0"	5'-0"		1349.75	1345.25									15' (W)	1345.50			Inside face of wall 2'-7"x7' R.C.B.					
401	-	59+17.06	Central	25.58' Rt.	576736.8738	377509.1564							-	-	-		-	-	15' (E)	1343.60																
500	501	64+70	Central	22.00' Lt.	576793.7160	378061.2228	I					C	10'-0"	4'-0"	4'-6"		1349.07	1345.07									15' (E)	1345.80								
501	502	65+48	Central	22.00' Lt.	576795.0231	378139.2119	I					C	5'-0"	4'-0"	5'-0"		1349.45	1344.95	15' (W)	1345.30							15' (E)	1345.20			Inside face of wall 7"x7' R.C.B.					
502	-	65+85.13	Central	28.00' Lt.	576801.6444	378176.2382							-	-	-		-	-	15' (W)	1342.02																
600	601	64+70	Central	22.00' Rt.	576749.7222	378061.9601	I					C	10'-0"	4'-0"	4'-6"		1349.07	1345.07									15' (E)	1345.80								
601	602	65+48	Central	22.00' Rt.	576751.0292	378139.9492	I					C	5'-0"	4'-0"	5'-0"		1349.45	1344.95	15' (W)	1345.30							15' (E)	1345.20			Inside face of wall 7"x7' R.C.B.					
602	-	65+85.13	Central	28.00' Rt.	576745.6523	378177.1767							-	-	-		-	-	15' (W)	1342.02																
700	701	79+00	Central	28.00' Rt.	576767.6854	379491.8599	I					C	5'-0"	4'-0"	4'-6"		1364.18	1360.18									15' (N)	1360.40								
701	703	79+00	Central	28.00' Lt.	576823.6775	379490.9215	I					C	5'-0"	4'-0"	5'-0"		1364.18	1359.68	15' (S)	1360.03							15' (W)	1359.93								
702	703	76+90	Central	23.99' Rt.	576768.1725	379281.8222	I					C	5'-0"	4'-0"	4'-6"		1360.40	1356.40									15' (N)	1356.62								
703	706	76+90	Central	23.99' Lt.	576816.1526	379281.0181	I					C	5'-0"	4'-0"	5'-0"		1360.40	1355.90	15' (E)	1356.20	15' (S)	1356.20					15' (W)	1356.10								
704	706	74+48.50	Central	49.25' Lt.	576837.3588	379039.1288			I		Z		6'-8"	4'-7"	4'-3"		1355.50	1351.75									18' (S)	1352.00								
705	706	74+50	Central	22.00' Rt.	576766.1440	379041.8225	I					C	5'-0"	4'-0"	4'-6"		1356.08	1352.08									15' (N)	1352.29								
706	708	74+50	Central	22.00' Lt.	576810.1378	379041.0852	I					C	5'-0"	5'-0"	6'-0"		1356.08	1350.58	15' (E)	1352.09	18' (N)	1351.92	15' (S)	1352.09			30' (W)	1350.92								
707	708	72+77	Central	22.00' Rt.	576763.2450	378868.8468	I					C	10'-0"	4'-0"	4'-6"		1354.52	1350.52									15' (N)	1350.72								
708	709	72+77	Central	22.00' Lt.	576807.2388	378868.1095	I					C	10'-0"	5'-0"	6'-0"		1354.52	1349.02	30' (E)	1349.42	15' (S)	1350.52					30' (W)	1349.32								
709	710	72+00	Central	22.00' Lt.	576805.9486	378791.1203	I					C	10'-0"	5'-0"	6'-6"		1354.70	1348.70	30' (E)	1349.12							30' (W)	1349.00								
710	712	69+50	Central	22.00' Lt.	576801.7593	378541.1554	I					C	10'-0"	5'-0"	6'-6"		1353.48	1347.48	30' (E)	1347.92							30' (W)	1347.82								
711	712	68+00	Central	22.00' Rt.	576755.2520	378391.9138	I					C	5'-0"	4'-0"	4'-6"		1351.98	1347.98									15' (N)	1348.18								
712	713	68+00	Central	22.00' Lt.	576799.2458	378391.1765	I					C	5'-0"	5'-0"	6'-6"		1351.98	1345.98	30' (E)	1346.38	15' (S)	1347.54					30' (W)	1346.28								
713	714	66+25	Central	22.00' Lt.	576796.3133	378216.2011	I					C	5'-0"	5'-0"	7'-0"		1350.22	1343.72	30' (E)	1344.31							30' (W)	1344.21			Inside face of wall 7"x7' R.C.B.					
714	-	65+92.13	Central	28.00' Lt.	576801.7617	378183.2372							-	-	-		-	-	30' (E)	1342.45																
TOTALS							18	-	1	-	-																									

CONDUIT DATA																																						
ROUTING SEQUENCE		LOCATIONS OF INSTALLATIONS			CONSTRUCT OR INSTALL		CONDUIT FLOWLINES		SEWER EXCAVATION		STORM SEWER (LIN. FT.)								END SECTIONS (EACH)				AASHTO CONC. CLASS	FLOWABLE FILL (L.F.)									REMARKS					
		STATION	ROUTE IDENTIFICATION	DISTANCE LEFT/RIGHT	TYPE OF CONDUIT SIZE	MATERIAL	LENGTH (L.F.)	INFLOW ELEV.	OUTFLOW ELEV.	ROCK (CU. YD)	COMMON (CU. YD)	15"	18"	24"	30"																							
400	401	59+40	Central	22.00' Rt.	15"	R.C.P.	19	1345.50	1343.60			19										III															Connect to 2'-7"x7' R.C.B.	
500	501	64+70	Central	22.00' Lt.	15"	R.C.P.	72	1345.80	1345.30			72										III															Connect to 7"x7' R.C.B.	
501	502	65+48	Central	22.00' Lt.	15"	R.C.P.	33	1345.20	1342.02			33										III																
600	601	64+70	Central	22.00' Rt.	15"	R.C.P.	72	1345.80	1345.30			72										III															Connect to 7"x7' R.C.B.	
601	602	65+48	Central	22.00' Rt.	15"	R.C.P.	33	1345.20	1342.02			33										III																
700	701	79+00	Central	28.00' Rt.	15"	R.C.P.	61	1360.40	1360.03			61										III	60															
701	703	79+00	Central	28.00' Lt.	15"	R.C.P.	207	1359.93	1356.20			207										III																
702	703	76+90	Central	23.99' Rt.	15"	R.C.P.	53	1356.62	1356.20			53										III	52															
703	706	76+90	Central	23.99' Lt.	15"	R.C.P.	236	1356.10	1352.09			236										III																
704	706	74+48.50	Central	49.25' Lt.	18"	R.C.P.	20	1352.00	1351.92				20									III																
705	706	74+50	Central	22.00' Rt.	15"	R.C.P.	49	1352.29	1352.09			49										III	48															
706	708	74+50	Central	22.00' Lt.	30"	R.C.P.	167	1350.92	1349.42							167						III																
707	708	72+77	Central	22.00' Rt.	15"	R.C.P.	49	1350.72	1350.52			49										III	48															
708	709	72+77	Central	22.00' Lt.	30"	R.C.P.	68	1349.32	1349.12							68						III																
709	710	72+00	Central	22.00' Lt.	30"	R.C.P.	241	1349.00	1347.92							241						III																
710	712	69+50	Central	22.00' Lt.	30"	R.C.P.	144	1347.82	1346.38							144						III																
711	712	68+00	Central	22.00' Rt.	15"	R.C.P.	49	1348.18	1347.54			49										III	48															
712	713	68+00	Central	22.00' Lt.	30"	R.C.P.	171	1346.28	1344.31							171						III															Connect to 7"x7' R.C.B.	
713	714	66+25	Central	22.00' Lt.	30"	R.C.P.	32	1344.21	1342.45							32						III																
TOTALS												933	20	-	823									256														

i:\1995\95297\002\sched-2.dgn
Plotted by: DJW 12-2-97

1

No.

Revisions

By

Date

SEDGWICK COUNTY BUREAU OF PUBLIC SERVICES

SCHEDULE OF INLETS AND MANHOLES

PROJECT NO. 618-34 SEDGWICK COUNTY

PROFESSIONAL ENGINEERING CONSULTANTS,P.A.
ENGINEERS
WICHITA, KANSAS

Designed by JPS
Checked by WDH
Drawn by GDR
Date JULY