PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
618-34	1998	53	100

INLET AND MANHOLE DATA

ROUTING SEQUENCE FROM	ROUTING SEQUENCE TO	LOCATIONS OF INSTALLATIONS: STATION	ROUTE IDENTIFICATION	DISTANCE LEFT/RIGHT	NORTH COORDINATE	EAST COORDINATE	CONSTRUCT OR INSTALL: INLET (TYPE 22 CURB)	INLET (TYPE 22 CURB ①)	R.C. M.H.	INLET-M.H. (SPECIAL)	END SECTION	G&F TYPE	L&F TYPE	DIMENSIONS: L (FT.)	W (FT.)	H (FT.)	H_T (FT.)	ELEVATIONS: TOP	FLOOR	INFLOW CONDUITS: SIZE DIRECT.	FLOWLINE ELEV.	SIZE DIRECT.	FLOWLINE ELEV.	SIZE DIRECT.	FLOWLINE ELEV.	OUTFLOW CONDUITS: SIZE DIRECTION	FLOWLINE ELEV.	FOR INFORMATION ONLY: CLASS III EXC. (CU. YD)	CAST IRON (LBS.)	STRUCT. STEEL (LBS.)	REINF. STEEL (LBS.)	CLASS A CONC. (CU. YD)	STEPS	REMARKS
925	926	43+40	Greenwich	40.00' Lt.	577375.1253	374618.8722	1						C	5'-0"	4'-0"	5'-0"		1371.03	1366.53							15" (E)	1366.85							
926	927	43+40	Greenwich	70.00' Lt.	577375.7246	374648.8662			1				A or B	6'-6"	6'-0"	6'-0"	2'-0"	1368.50	1361.00	36" (S)	1361.88	15" (W)	1363.63			42" (E)	1361.38							
927	928	43+40.94	Greenwich	334.61' Lt.	577380.0701	374913.4399			1				A or B	6'-6"	6'-6"	6'-6"	2'-0"	1364.30	1356.30	42" (W)	1357.22					48" (N)	1356.72							
928	-	42+38.21	Greenwich	336.66' Lt.	577482.8201	374913.4363					*			-	-	-		-	-	48" (S)	1355.02													
TOTALS							1		2																									

* End Sections are recapitulated with the Conduits below.

CONDUIT DATA

ROUTING SEQUENCE FROM	ROUTING SEQUENCE TO	LOCATIONS OF INSTALLATIONS: STATION	ROUTE IDENTIFICATION	DISTANCE LEFT/RIGHT	CONSTRUCT OR INSTALL: TYPE OF CONDUIT SIZE	TYPE OF CONDUIT MATERIAL	LENGTH (L.F.)	CONDUIT FLOWLINES: INFLOW ELEV.	OUTFLOW ELEV.	SEWER EXCAVATION: ROCK (CU. YD)	COMMON (CU. YD)	STORM SEWER (LIN. FT.): 15"	18"	24"	30"	36"	42"	48"		END SECTIONS (EACH): 48" (R.C.)				AASHTO CONC. CLASS	FLOWABLE FILL (L.F.)										REMARKS
925	926	43+40	Greenwich	40.00' Lt.	15"	R.C.P.	23	1366.85	1363.63			23												III									
926	927	43+40	Greenwich	70.00' Lt.	42"	R.C.P.	260	1361.38	1357.22								260							III									
927	928	43+40.94	Greenwich	334.61' Lt.	48"	R.C.P.	100	1356.72	1355.02									100		1				III									
TOTALS												23					260	100		1													

No.	Revisions	By	Date
1			

SEDGWICK COUNTY BUREAU OF PUBLIC SERVICES

SCHEDULE OF INLETS AND MANHOLES

PROJECT NO. 618-34 SEDGWICK COUNTY

PROFESSIONAL ENGINEERING CONSULTANTS, P.A.
ENGINEERS
WICHITA, KANSAS

Designed by	JPS	Checked by	WDH
Drawn by	GDR	Date	JULY 1997

Job No. 95297-2

I:/1995/95297/002/sched4.dgn
Plotted by: maf 8-14-97