PIPE CULVERT SUMMARY

STATION	OFFSET	TYPE	SIZE OR BID DESIGNATION SQ. FT.	FLOW LINE IN	FLOW LINE OUT	LENGTH OF PIPE	HEIGHT OF FILL (MIN.) FT.	CONCRETE PIPE AASHTO CLASS NO.	REMARKS
102+67.48	RCP	24"		1323.20	1322.80	100.4	0.73	Class V	w/ 2 - 24" End Sections

DRAINAGE STRUCTURES

STATION	SIDE	SIZE	TYPE	ENTRANCE PIPES RCP 15"	ENTRANCE PIPES RCP 24"	END SECTIONS RC 15"	END SECTIONS RC 24"	REMARKS
102+67.48	Lt.	24"	RCP		100.4		2	
			TOTAL		100.4		2	

PIPE REMOVED

STATION	LOCATION	DESCRIPTION
102+64.74	Lt.	53.9 L.F. 24" RCP w/ End Sections

SUMMARY OF STORM QUANTITIES

ITEM	QUANTITY	UNIT
Pipe Removed	54	L.F.
Pipe, SWS 24"	100	L.F.
Pipe End Section 24"	2	L.F.
		EA.
		EA.
		EA.
		EA.

TranSystems
245 NORTH WACO
SUITE 222
WICHITA, KANSAS 67202
PHONE: 316-303-3000
FAX: 316-462-5629

CONSULTANTS:

HOOVER ROAD MULTI-USE PATH
& TRAFFIC SIGNAL
ZOO BLVD. TO 29TH STREET NORTH

WICHITA, KANSAS

CITY OF WICHITA

REVISIONS:

MARK	DATE	DESCRIPTION

PROJ NO: 472-85394
SCALE: N/A
DATE: 9/30/2020
DESIGNED BY: MCG
DRAWN BY: MCG
CHECKED BY: CCB

SHEET TITLE:

SCHEDULE
OF
STORM SEWER

SHEET NO.
12
SHEET 12 OF 44

ccbanka
9/30/2020 - 8:32:17 PM - c:\transystems\pw_local\transyscorp-pw1\ccbanka\d0735211\C-DET- RD050.dgn

IF THIS DRAWING IS LESS THAN 22" X 36" IT IS A REDUCED SIZE DRAWING