SUMMARY OF EARTHWORK -FOR INFORMATION ONLY-

STATION to STATION		COMMON EXCAVATION C.Y.	VMF	CONTRACTOR FURNISHED C.Y.	FILL, COMPACTED (95% DENSITY) C.Y.
99+98.29	103+31.22	46.1	0.85	225.0	230.4
TOTALS (C.Y.)		46.1	0.85	225.0	230.4

CONCRETE SIDEWALK 5"

STATION to STATION		WIDTH (FT)	S.F.
99+98.29	100+33.85	Varies	915.6
100+02.85, Lt.	100+02.99, Lt.	Varies	92.8
101+62.95	101+72.14	10.0	91.9
102+02.10	102+76.93	10.0	729.1
TOTALS (S.F.)			1,829.4

RIP-RAP, LIGHT STONE

STATION	SIDE	S.Y.
102+20.00	Rt.	30.4
TOTALS (S.Y.)		30.4

TEMPORARY PAVEMENT (8")

STATION	SIDE	S.Y.
102+96.50	Lt.	39.0
TOTALS (S.Y.)		39.0 †

† Temporary Pavement may be Concrete or HMA

WHEELCHAIR RAMPS W/ DETECTABLE WARNINGS

STATION	OFFSET	SIDE	EA
100+02.99	67.72'	Lt.	1
100+03.42	30.64'	Lt.	1
100+33.85	5.00'	Lt.	1
101+62.95	5.00'	Lt.	1
101+72.41	5.00'	Lt.	1
102+02.10	5.00'	Lt.	1
TOTALS (EA.)			6

SUMMARY OF REMOVAL

STATION to STATION		PAVEMENT REMOVED	SIDEWALK REMOVED
99+98.57	100+07.38		16.3
99+97.28	100+11.98		57.5
102+76.93	103+06.61	39.0	
TOTALS (S.Y.)		39.0	73.8

CONCRETE C & G, TYPE I (6" & 1-1/2")

STATION to STATION		SIDE	L.F.
101+44.96	101+63.27	Rt. /Lt.	30.6
TOTALS (L.F.)			30.6

RECAPITULATION OF ROAD QUANTITIES

ITEM	QUANTITY	UNIT
Mobilization	1	LSUM
Site Clearing	1	LSUM
Site Restoration	1	LSUM
Removal of Existing Structures	1	LSUM
Pavement Removed	39	S.Y.
Sidewalk Removed	74	S.Y.
Earthwork	1	LSUM
Concrete Sidewalk 5"	1829	S.F.
Wheelchair Ramp w/ Detectable Warnings	6	EA.
Concrete C & G, Type I (6" & 1-1/2")	31	L.F.
Temporary Pavement (8")	39	S.Y.
Pipe Removed	54	L.F.
Pipe, SWS 24"	100	L.F.
Pipe End Section 24"	2	EA.
Rip-Rap, Light Stone	30	S.Y.
Grading, Ditch	1	LSUM
BMP, Silt Fence	200	L.F.
BMP, Ditch Check	3	EA.
BMP, Erosion Control Blanket	10	S.Y.
Pavement Markings	1	LSUM
Signing	1	LSUM
Seeding	1	LSUM
Traffic Control	1	LSUM
Traffic Signalization	1	LSUM

See Sheet 12 for Storm Sewer Quantities
See Sheet 21 for Traffic Signalization Quantity
See Sheet 31 for Pavement Marking Quantities
See Sheet 33 for Signing Quantities

TranSystems
245 NORTH WACO
SUITE 222
WICHITA, KANSAS 67202
PHONE: 316-303-3000
FAX: 316-462-5629

CONSULTANTS:

HOOVER ROAD MULTI-USE PATH
& TRAFFIC SIGNAL
ZOO BLVD. TO 29TH STREET NORTH

WICHITA, KANSAS

CITY OF WICHITA

REVISIONS:

MARK	DATE	DESCRIPTION

PROJ NO: 472-85394
SCALE: N/A
DATE: 9/30/2020
DESIGNED BY: MCG
DRAWN BY: MCG
CHECKED BY: CCB

SHEET TITLE:

SUMMARY OF QUANTITIES

SHEET NO.
18

IF THIS DRAWING IS LESS THAN 22" X 36" IT IS A REDUCED SIZE DRAWING

ccbanka
9/30/2020 - 8:32:39 PM - c:\transystems\pw_local\transyscorp-pw1\ccbanka\d0735211\rd050.dgn