

Sta. 4+849.984
Begin Construction
TC Elev. = 33.630

POT: PK Nail @ Sta. 4+756.160
8.269 M To Nails on SE side of Pole
8.022 M SE to Chiseled 'X' in top of curb, South side of Maple
14.015 M SW to Nails on Northeast side of Power Pole

Sta. 4+940.000
PVI, No V.C.
TC Elev. = 33.360

FWA REG. NO.	STATE	PROJECT NO.	YEAR	SHEET NUMBER	TOTAL SHEETS
7	KANSAS	87 N-0099-01	1998	6	62

+0.30 %
Sta. 4+960.000
TC Elev. = 33.420

Sta. 4+978.600
Begin Return
TC Elev. = 33.478

SCALE: 1:200

Petroleum Market Co.
1102 West Maple

D-499

SEE SHEET
FOR
DETAILS

Sta. 4+849.984
Begin Construction
Match Existing

12.192 M R/W (Existing)

Construction Limits

Sta. 4+905.000
End Taper


Sta. 4+897.857 (Maple) =
Sta. 1+000.000 (Dodge)

Install Comb. C & G (Type I or II)

Install 100 MM Conc. Sidewalk (1.5 M Wide)

Sta. 4+940.000, Rt.
Install Sta. Type I Inlet
Install Storm Sewer 600 MM RCP
X 55.695 M (E)
Install 600 mm RCP Stub X 1.0 M (W)
and Plug
See Sheets 29, 30, 31, 32
Plug is subsidiary to Bid Item 'Storm Sewer 600 mm RCP'

LEGEND:



Remove Existing Pavement

①

Remove

②

To Be Adjusted or Relocated by Others

③

Remove and Install
Sidewalk, 1 M Beyond R/W
to match existing

Install 50MM RGC for Comm. Cable

ⓐ

Install Junction Boxes @ 45 M Spacing

Kansas Masonic Home

D-6105

Bench Mark # 100: Chiseled Square on top of NE
corner of flagpole base on North side of Masonic
Home, Sta. 4+846.835, Rt.
Elev. = 34.250

PLAN SHEET - MAPLE		
From Sta. 4+849.984 to Sta. 4+978.600		
SCALE:	APPROVED:	DRAWN BY:
DATE:	CHECKED:	
PROJECT NO.	SHEET NO.	

ME MUNICIPAL ENGINEERS, P.A.
254-LAURA, SUITE 201, WICHITA, KANSAS 67211
316-262-3842 (TEL.)
316-262-6634 (FAX)