









SEE CITY OF WICHITA STANDARD MANHOLE FRAME
AND COVER DETAIL SHEET FOR COVER DETAILS
TO BE USED WITH INLET FRAME.






PRECAST SLAB AND FLOOR REINFORCING											
		W=4'-4"		W=5'-4"		W=6'-4"		W=7'-4"		W=8'-4"	
Mark	Size	No.	Length	No.	Length	No.	Length	No.	Length	No.	Length
#a1	#4	6	6'-7"	6	8'-7"	6	10'-7"	6	12'-7"	6	14'-7"
a2	#4	4	6'-0"	4	8'-0"	4	10'-0"	4	12'-0"	4	14'-0"
a3	#4	13	4'-1"	13	5'-1"	13	6'-1"	13	7'-1"	13	8'-1"
b1	#4	1	4'-9"	1	4'-9"	1	4'-9"	1	4'-9"	1	4'-9"
#b2	#4	23	6'-1"	29	6'-1"	35	6'-1"	41	6'-1"	47	6'-1"
#1	#4	8	3'-10"	8	4'-2"	8	4'-6"	8	4'-10"	8	5'-2"
WALL REINFORCING											
		W=4'-4"		W=5'-4"		W=6'-4"		W=7'-4"		W=8'-4"	
Mark	Size	No.	Length	No.	Length	No.	Length	No.	Length	No.	Length
w1	#4	①	6'-1"	①	6'-1"	①	6'-1"	①	6'-1"	①	6'-1"
w2	#4	①	4'-1"	①	5'-1"	①	6'-1"	①	7'-1"	①	8'-1"
w3	#4	32	②	36	②	40	②	44	②	48	②

* Field bend or cut Reinforcing as required for clearance.

① $4(HI-12")$; $(HI-12")$ Round down to nearest 0.5'

② $HI-3"$

STANDARD CURB INLET PRECAST TOPS			
W	PRE-CAST TOP SIZE	PIPE SIZE	CU. YD. CONC.
4' 4"	3'8" x 6'4" x 7 1/2"	21" @ SMALLER	0.38 ±
5' 4"	4'8" x 6'4" x 7 1/2"	24" @ 30"	0.51 ±
6' 4"	5'8" x 6'4" x 7 1/2"	36" @ 42"	0.84 ±
7' 4"	6'8" x 6'4" x 7 1/2"	48" @ 54"	0.77 ±
8' 4"	7'8" x 6'4" x 7 1/2"	60" @ 66"	0.90 ±



REVISED 11-30-1988	
REVISED 12-21-1984	Revised 2-16-1989

~~REVISED 12-21-1984~~ Revised 2-16-1989

DETAIL STANDARD TYPE 1A CURB INLET
CITY OF WICHITA, KANSAS
INLET OPENING = 6" x 5' 0"
L = 6' - 4"
JUNE 1984

CITY OF WICHITA, KANSAS

INLET OPENING = 6" x 5' 0"

6-4'

JUNE 1984