


| WILDWOOD PH 1<br>CY Excavation (unadjusted) |       |        |        |
|---|-------|--------|--------|
| Station                                     | Area  | Volume | Total  |
| -0+00                                       | 15.46 | 0.00   | 0.00   |
| 0+50  | 15.46 | 28.63  | 28.63  |
| 1+00  | 15.46 | 28.63  | 57.27  |
| 1+50  | 15.46 | 28.63  | 85.90  |
| 2+00  | 15.46 | 28.63  | 114.54 |
| 2+50  | 15.46 | 28.63  | 143.17 |
| 3+00  | 15.46 | 28.63  | 171.81 |
| 3+50  | 15.58 | 28.73  | 200.54 |
| 4+11.63                                     | 15.47 | 35.42  | 235.96 |
| 4+50  | 15.46 | 21.98  | 257.95 |
| 5+00  | 15.83 | 29.09  | 287.04 |
| 5+39.21                                     | 15.42 | 22.78  | 309.82 |
| 5+71.65                                     | 20.70 | 22.07  | 331.89 |
| 6+08.65                                     | 15.36 | 24.70  | 356.60 |
| 6+42.30                                     | 15.61 | 19.30  | 375.90 |
| 6+85.42                                     | 15.67 | 24.98  | 400.88 |
| 7+16.77                                     | 15.65 | 18.17  | 419.05 |
| 7+41.87                                     | 22.15 | 18.40  | 437.45 |
| 7+66.93                                     | 13.74 | 17.49  | 454.94 |
| 8+20  | 12.71 | 25.91  | 480.85 |
| 8+68.07                                     | 15.86 | 25.37  | 506.22 |

| WILDWOOD PH 1<br>CY Loose Fill (unadjusted) |       |        |        |
|---|-------|--------|--------|
| Station                                     | Area  | Volume | Total  |
| -0+00                                       | 6.84  | 0.00   | 0.00   |
| 0+50  | 10.20 | 18.83  | 18.83  |
| 1+00  | 7.65  | 18.00  | 36.83  |
| 1+50  | 13.61 | 19.33  | 56.16  |
| 2+00  | 7.27  | 19.00  | 75.17  |
| 2+50  | 13.46 | 18.87  | 94.04  |
| 3+00  | 11.60 | 23.16  | 117.20 |
| 3+50  | 11.44 | 21.37  | 138.57 |
| 4+11.63                                     | 5.31  | 18.91  | 157.48 |
| 4+50  | 5.57  | 9.53   | 167.01 |
| 5+00  | 5.31  | 12.42  | 179.44 |
| 5+39.21                                     | 5.36  | 9.51   | 188.94 |
| 5+71.65                                     | 1.24  | 4.15   | 193.09 |
| 6+08.65                                     | 5.80  | 4.83   | 197.92 |
| 6+42.30                                     | 5.31  | 6.92   | 204.84 |
| 6+85.42                                     | 10.08 | 12.29  | 217.13 |
| 7+16.77                                     | 5.44  | 9.84   | 226.97 |
| 7+41.87                                     | 0.00  | 3.12   | 230.09 |
| 7+66.93                                     | 6.08  | 3.48   | 233.57 |
| 8+20  | 6.45  | 15.19  | 248.76 |
| 8+68.07                                     | 5.31  | 12.12  | 260.88 |

| WILDWOOD PH 1<br>CY Compacted Fill (unadjusted) |      |        |       |
|---|------|--------|-------|
| Station   | Area | Volume | Total |
| -0+00   | 0.98 | 0.00   | 0.00  |
| 0+50  | 1.26 | 1.48   | 1.48  |
| 1+00  | 1.26 | 2.09   | 3.58  |
| 1+50  | 1.26 | 2.44   | 6.02  |
| 2+00  | 1.26 | 2.44   | 8.46  |
| 2+50  | 1.26 | 2.44   | 10.90 |
| 3+00  | 1.26 | 2.44   | 13.34 |
| 3+50  | 1.26 | 2.44   | 15.78 |
| 4+11.63   | 1.26 | 3.01   | 18.79 |
| 4+50  | 1.26 | 1.28   | 20.07 |
| 5+00  | 1.26 | 1.67   | 21.74 |
| 5+39.21   | 1.26 | 1.31   | 23.05 |
| 5+71.65   | 0.98 | 1.20   | 24.25 |
| 6+08.65   | 0.98 | 1.35   | 25.59 |
| 6+42.30   | 0.98 | 1.23   | 26.82 |
| 6+85.42   | 0.98 | 1.57   | 28.39 |
| 7+16.77   | 1.02 | 0.83   | 29.22 |
| 7+41.87   | 1.12 | 0.71   | 29.93 |
| 7+66.93   | 1.25 | 0.78   | 30.71 |
| 8+20  | 1.42 | 1.86   | 32.57 |
| 8+68.07   | 0.98 | 1.72   | 34.29 |

WILDWOOD/WESTGATE/GRABER



**BAUGHMAN  
COMPANY**  
315 Ellis St.  
Wichita, KS 67211  
316-262-7271  
BaughmanCo.com

SCHULTE-JOHNSON 2ND  
ADD. - ENTRANCE

**CROSS  
SECTIONS**

STREET IMPROVEMENTS

PROJECT NUMBER:  
472-2020-085633

DESIGN: AEG DRAWN: HJW

DATE: July 19, 2021

SHEET OF  
**20 26**

File: C:\Projects\Schulte-Johnson 2nd Addition\Engineering\Phase 1\STR\STR Plans.dwg