



KESSLER CIR CY Ground Removed (unadjusted)				KESSLER CIR CY Ground Fill (unadjusted)			
Station	Area	Volume	Total	Station	Area	Volume	Total
0+00	45.85	0.00	0.00	0+00	24.22	0.00	0.00
0+25	54.38	25.17	25.17	0+25	9.39	4.35	4.35
0+50	34.76	41.27	66.44	0+50	4.00	6.20	10.55
1+00	28.92	58.96	125.40	1+00	3.99	7.39	17.94
1+50	28.54	53.20	178.60	1+50	4.57	7.92	25.86
2+00	35.85	58.97	237.57	2+00	1.07	5.56	31.42
2+50	53.75	82.85	320.42	2+50	0.18	1.09	32.51
3+00	68.29	113.02	433.44	3+00	0.00	0.14	32.65
3+32.44	70.44	81.17	514.61	3+32.44	0.04	0.03	32.68
3+50	83.15	50.25	564.86	3+50	0.97	0.32	33.00
3+70.39	86.18	64.11	628.97	3+70.39	0.00	0.35	33.35
4+00	72.84	87.64	716.61	4+00	0.00	0.00	33.35
4+09.20	79.16	25.90	742.51	4+09.20	0.05	0.01	33.36
4+50	94.52	132.08	874.59	4+50	0.00	0.04	33.40
5+00	68.25	151.48	1026.06	5+00	0.00	0.01	33.41
5+50	39.39	100.04	1126.10	5+50	0.02	0.02	33.43
6+00	17.53	52.72	1178.82	6+00	4.61	4.35	37.77
6+50	2.32	18.26	1197.08	6+50	18.19	21.32	59.09
6+70.51	1.36	1.37	1198.45	6+70.51	30.71	18.70	77.80