


DEMOLITION NOTES:

1. FLUSH WETWELL & FORCE MAIN WITH 10,000 GALLONS OF CLEAN WATER.
2. ABANDON FORCE MAIN IN PLACE.
3. DEMOLISH UNDERGROUND STRUCTURES BY REMOVING MATERIAL TO AT LEAST 4 FEET BELOW FINISH GRADE. BREAK UP STRUCTURAL FLOORS TO ALLOW DRAINAGE FLOW. FILL STRUCTURAL SHELL AND EXCAVATION WITH SAND COMPACTED TO 95% DESITY ASTM D-698. BACKFILL TO GRADE.
4. SANITARY SEWER FLOWS TO WASTEWATER TREATMENT PLANT #2. CALL TIM HOPWOOD (316) 303-8787.

**CONFORMING TO
CONSTRUCTION RECORDS
4/20/07**



NO.	BY	DATE	DESCRIPTION
0	DLM	10/17/05	ISSUE FOR CONSTRUCTION
	MJV	4/26/07	CONFORMING TO CONSTRUCTION RECORDS DELETED AIR RELEASE VAULT, ADDED 1'-0" TO EAST SIDE OF VALVE VAULT.



**CITY OF WICHITA, KANSAS
15th STREET PUMP STATION
AND FORCE MAIN**

SITE DEMOLITION PLAN II

DESIGNED BY	DLM	CHECKED BY	DLM
DRAWN BY	BDM	DATE	JUNE, 2005
PROJECT	0301030310	CONTRACT	-
DRAWING	D2	REVISION	0